

EPI

Please note that the PreScore report for this site is located in the files in the HRS room. Please see one of the HRS coordinators for more information.

SITE NAME

Lighting and
Houston Power - Webster Generating Plant

TDD #

F06-8902-25

PAN

FTX0807PAA

CERCLID

TXD 000837369

PEER REVIEW TRACKING FORM

Project No: FT1306 Site Name/ID#: Houston Lighting & Power
 TOD#: FC890225 PAN#: FTD807DAA Author: FC890225
 Report Title: PA Under EPI for HLEP Webster Generating Plant

First Review			Second Review		
Reviewer	Date	Section	Reviewer	Date	Section
<u>JS</u>	<u>4/20</u>	<u>_____</u>	<u>_____</u>	<u>_____</u>	<u>_____</u>
<u>sl</u>	<u>4/25</u>	<u>all</u>	<u>_____</u>	<u>_____</u>	<u>_____</u>
<u>fr</u>	<u>4/26/89</u>	<u>memo</u>	<u>_____</u>	<u>_____</u>	<u>_____</u>
<u>gpt</u>	<u>5/10/89</u>	<u>_____</u>	<u>_____</u>	<u>_____</u>	<u>_____</u>
<u>_____</u>	<u>_____</u>	<u>_____</u>	<u>_____</u>	<u>_____</u>	<u>_____</u>

Approved for Release:

Author

Date

AFITOM

Date

FITOM

Date



ICF TECHNOLOGY INCORPORATED

TO: Ed Sierra, EPA Region VI, RPO

THRU: K. H. Malone, Jr., FITOM *am*

THRU: Tim A. Hall, AFITOM *for TAIH*

FROM: Pam Fetzer, FIT Geologist *P. Fetzer*

DATE: May 3, 1989

SUBJ: Preliminary Assessment Under the Environmental Priorities Initiative Program Regarding Houston Lighting and Power - Webster Generating Plant CERCLIS # TXD000837369, TDD # F-6-8902-25, PAN FTX0807PAA.

SITE INFORMATION

The Houston Lighting and Power - Webster Generating Plant is located at 19301 State Highway 3, in Webster, Texas, one mile south of NASA Highway 1 (Mailing address P.O. Box 1700, Houston, Texas 77001). The latitude and longitude are 29°31'47" N and 95°06'10" W, respectively (Figure 1). The facility encompasses 607 acres and is publicly owned by Houston Industries.

The purpose of this investigation is to perform a Preliminary Assessment (PA) under the Environmental Priorities Initiative (EPI) Program for the EPA. The FIT was also tasked to determine the net worth and sales value of the company.

BACKGROUND/OPERATING HISTORY

The Webster Generating Plant began operating the first gas turbine electric generating unit in 1954. In 1965, the third (final) turbine went on-line and is currently operating (Figure 2).

The plant has the sole function of producing electricity by generating steam from a gas-operated turbine. In the production process, water from ground water wells is heated in the boilers and is then cooled, condensed, demineralized, chemically treated and then discharged via the discharge canal. After the effluent is routed through the surface impoundments to settle out the solids, the water is pumped through the chemical treatment process for flocculation and binding of chromium, barium, arsenic, selenium, lead, mercury, and cadmium. By-products such as phosphates, nitrates, ammonia and citric acid are treated to produce an acceptable effluent discharge (5).

No specific contaminants of concern were found within the CERCLA, RCRA and the TWC files, however, EP Toxicity (EP TOX) analyses were conducted on 4 samples for arsenic, barium, chromium, lead, cadmium, mercury, selenium and silver concentrations. These will be considered the contaminants of concern (6, 11).

Contaminants discharged from the outfalls are aluminum sulfate, ammonia, chlorine, sodium nitrate, sodium phosphates and sodium hydroxide (23). These constituents have been generated during equipment cleanings. Equipment cleanings are necessary to prevent corrosion and remove scale. Other substances such as waste oils, spent solvents, sandblasting grit, asbestos insulation, inorganic and organic sludge, and paint thinner are generated on the site.

The Texas Department of Water Resources (TDWR) analytical data concern the classification of waste. On April 8, 1981, EP TOX analyses were performed on several samples collected at the site. The results of these tests indicated that the waste materials from the demineralizer regenerant sludge, metal cleaning inorganic sludge, and organic acids collection pond sludge (11, pg. 1) were Class II wastes (TWC 241470).

The Analytical Petroleum Research (APR) Laboratories analyzed a sample of a waste oil floor drain sump and gas turbine oil trap through EP TOX analysis on September 25, 1984. Arsenic, barium, cadmium, chromium, lead, mercury, selenium and silver were below detection limits. No analytical methods were included in the report (11).

During the July 1, 1986 closure inspection, samples were taken from the demineralizer regenerant/boiler blowdown surface impoundment. The composite soil samples, taken from 18 inches and 2 to 4 inches from the surface, were analyzed by the TDWR for EP TOX metals. The analyses revealed barium at 326 to 390 μ /l (6). Ground water monitoring well samples revealed high conductivity levels for MW-1, which is located near the discharge canal. The ground water from the monitoring wells was tested for pH by EPA method 150.1 (5). The April 24, 1987 sampling of MW-1 and MW-2 for the Comprehensive Ground water Monitoring Evaluation (CME) yielded the following results (see Page 3 of this report).

Analyses of monitoring well samples were collected on April 24, 1987 for the CME. The analytical methods used to determine the conductivity, and pH of chloride, sulfate, iron, manganese, sodium phenol, and total organic carbon were from EPA 600/4-79-020 "Methods for Chemical Analysis of Water and Wastes" (March 1979) 120.1, 150.1, 325.3, 375.4, 236.1, 243.1, 273.1, 420.1, and 415.1, respectively. Total organic halogen analysis is tested by the EPA Interim Method, 1980 "Interim Method for Total Organic Halide" 450.1. These analyses are used by Analytical Petroleum Research Laboratories, Inc., Dickinson, Texas, for the Webster Plant. No QA/QC documentation was found, nor is there any indication that duplicate samples were collected.

None of the sampling data found in the files revealed significant contamination from the impoundment sludge or water or the waste oil drain, with the exception of the values derived from the CME sampling results. The validity of the sampling data is questionable because there are no QA/QC, duplicates and background samples (5). Higher values of magnesium, iron, zinc and manganese were found for MW-1, as compared to MW-2 (26).

MW-1 (4-24-87) BY HOUSTON POWER & LIGHT*

Note: Results revealed high conductivity headings between MW-1 and MW-2 when comparing 1984 and 1987:

Parameters	MW-1 (mg/l)		MW-2 (mg/l)	
	1984 Assessment	TWC-1987 CME	1984 Assessment	TWC-1987 CME
Magnesium	270	246	34	42
Chloride	3,900	4,463	220	352
Iron	0.25	74.6	< 0.05	3.71
Zinc	1.6	0.15	0.05	< 0.02
Conductivity	12,000	17,000	1,600	3,190

*(26 Attachment S)

APR LAB RESULTS OF SAMPLES COLLECTED FROM
MW-1 AND MW-2 (4-27-87):**

Parameters	MW-1 (mg/l)	MW-2 (mg/l)
Magnesium	263	42.1
Total dissolved solids	11,546	1,400
Manganese	0.8	< 0.1

** (26, Attachment T)

TWC LAB RESULTS OF SAMPLES COLLECTED FROM*
MW-1 AND MW-2 (4-27-87)**

Parameters	MW-1 (mg/l)	MW-2 (mg/l)
Magnesium	246	42
Chloride	559	69
Iron	74.6	3.71
Manganese	0.850	0.043
Zinc	0.150	0.020

*** (26, Attachment V)

An off-site reconnaissance inspection was not performed because the impoundments have undergone closure and neither the facility nor the impoundments can be seen from the public road.

The plant was issued a Texas Solid Waste Disposal Act Permit (August 15, 1980), Texas Department of Water Resources Solid Waste Registration Permit (No. 31633), a Wastewater Disposal Permit (under Texas Water Code 01044), a Hazardous Waste Management Program Permit (from the EPA on August 18, 1980), and an NPDES Permit (No. TX0006532 from the EPA) (13).

Information about the facility was found from the CERCLA, RCRA and the TWC files. Other related information was obtained from various state and Federal agencies.

During a TWC inspection, it was noted in the plant manifest that approximately 150 cubic yards of soil contaminated by sodium hydroxide were removed from the site. According to plant personnel, a caustic line ruptured, spilling 1,000 pounds of sodium hydroxide (7). No other facts are known about the incident. No known emergency or remedial action was taken by the EPA or related agencies.

The book assets for Houston Lighting and Power total \$10 billion. The value of the plant has fully depreciated (19). The sales of the Company in 1987 totalled \$3 billion (14). The net value of the company has been determined (19).

UNIT DESCRIPTION/WASTE CONTAINMENT/HAZARDOUS SUBSTANCE IDENTIFICATION

Used water from the boiler is pumped into a clay lined pond to collect and equalize the demineralizer regenerant wastes prior to wastewater treatment. The water from the demineralizer regenerant/boiler blowdown surface impoundment and the inorganic metal cleaning surface impoundment is pumped into a concrete chemical waste treatment system which is used to treat the water prior to NPDES discharge. The water is pumped into the 300 gallon mixing chamber, where the solids settle, and then is pumped into a flocculation chamber, where a flocculent is added. The type of flocculent used could not be determined. The liquid then enters the settling chamber where the solids settle, and is neutralized in the pH readjustment chamber. The effluent is discharged in accordance with the NPDES permit. The sludge that accumulates in the settling chamber is pumped to the sand drying beds for dewatering and periodic off-site removal (11).

SWMU IDENTIFICATION

Eight Solid Waste Management Units (SWMUs) have been identified at the Webster Generating Plant. Although RCRA regulation status was not found in the files, all of the SWMUs are RCRA-regulated based on CFR 264.90, subsection F.

SWMU #1 Demineralizer Regenerant/Boiler Blowdown Surface Impoundment:

The impoundment, located south of SWMU #2, is 200 feet long by 130 feet wide by 5 feet deep. Since 1970, it has been used as a holding pond for recycled water from the demineralizer regenerant and boiler

blowdown. The 3 foot clay lined unit has the capacity of 372,000 gallons. The annual volume of waste received by the impoundment was reportedly 79,300,000 gallons in 1984, but the total volume of waste received has not been determined. Sludge is removed periodically for off-site disposal and is classified as a Class II (non-hazardous) waste (TWC 241470). The files did not contain information about other contaminants present. Certification of closure was submitted September 2, 1986 (5), but in the Comprehensive Ground Water Monitoring Evaluation Report (CME), the unit is referred to as closed. According to the closure plan, all of the sludge and the first foot of the clay liner was to be removed, drummed and shipped off-site for disposal (8). It is not known whether the sludge and clay were removed and the material analyzed. Subsurface migration is considered unlikely because the permeability of the clay soil is 5.6×10^{-9} cm/sec (12). Results of borehole sampling revealed that the clay extended to a depth of 20 feet below the ground surface (12). The amount of freeboard and the diking condition are not known, so the likelihood of overflowing is undetermined. Should the impoundment overflow, the drainage pathway would be into Clear Creek, approximately 1,000 feet east of the unit (2).

SWMU #2

Inorganic Metal Cleaning Surface Impoundment:

This SWMU is located on the north side of the demineralizer regenerant surface impoundment. It is 200 feet long by 135 feet wide by 4.25 feet deep. It has been active since 1977. This unit received spent acids from metal cleaning operations. The wastewater is pumped to a concrete wastewater treatment system where it is treated and discharged under an NPDES permit (9). The total volume of waste received is not known, but it has been determined that in 1980, 18,287,000 pounds were received. Sludge from the bottom of the pond is periodically removed for off-site disposal and is classified as a Class II waste (TWC 241210)(11). The impoundment is lined with 3 feet of compacted clay. The amount of freeboard and the condition of the diking structure are not known. No report of overflowing was found in the files. If the impoundment dikes are breached, the drainage pathway would be to the east toward Clear Creek. Results of borehole sampling revealed that the permeability was 2.2×10^{-9} cm/sec (12). Subsurface migration is unlikely. The impoundment was closed and submitted for certification on November 4, 1985. In the CME, the unit is referred to as closed. Construction of a concrete tank at the impoundment is proposed.

SWMU #3

Organic Acid Waste Pond:

Located south and adjacent to the demineralizer regenerant surface impoundment, is the organic acid waste pond. This clay lined, active unit is used to store ammoniated citric acid effluent generated from boiler and equipment cleanings (11). The unit has been in operation since 1977. It has a 270,000 gallon capacity. The total amount of

waste received is not known, but it has been determined that in 1980 2,752,500 pounds of waste were received (13). The TWDR declassified the waste to a Class II waste (TWC 215290) due to EP TOX test results (11). The condition and current status of this unit are not known. Should the impoundment overflow or the dike be breached, the drainage pathway would be to the east toward Clear Creek or to the north toward a drainage ditch that is parallel to the discharge canal.

SWMU #4

Sludge Drying Beds:

This clay lined unit is located south of the organic acid waste pond. Each bed has a 1,790 gallon capacity (13). The total waste volume, dimensions, and documentation of the unit have not been determined. Sludge from the settling chamber of the chemical waste treatment system and the oily waste treatment system is pumped to the drying beds for dewatering. The dried sludge is periodically drummed and shipped off-site for disposal (11). The sludge is classified as a Class II waste (TWC 204540). Should the unit overflow, it is possible that the material could enter Clear Creek from the west (10).

SWMU #5

Hazardous Waste Container Storage Area:

This unit is located adjacent to the waste oil tank east of the gas turbine building (7). Active since 1980, it is used to store 55-gallon drums of liquid and solid hazardous and non-hazardous wastes, including refractory brick, spent solvents, paint thinner, waste oils and sandblasting grit. The drums are stored temporarily, prior to off-site disposal. All containers in storage were disposed by Rollins (location undetermined) and the resulting cleaning materials and contaminated equipment were disposed at BFI (location undetermined) as Class II waste. The number of drums used is not known. Houston Lighting and Power submitted a closure plan on May 13, 1985, but plans to open the area as a less than 90-day storage facility (8, pg. 3). At the present time, it is not known if the facility has been opened. The July 14, 1986 inspection revealed a 500-gallon tank half full of waste oil and two empty 55-gallon drums. One of the drums was labeled "waste solvent." The waste oil and spent solvent are collected by a recycling firm. In 1980, 9,700 pounds of waste oil and spent solvent were generated; by 1984, none was generated. The sandblasting grit is stored in bins prior to off-site disposal. The unit has a concrete floor. No other protective containment device was noted during the inspection. The condition of the drums was not noted during the inspection.

SWMU #6

Chemical Waste Treatment System:

Active since 1977, the unit is used to treat demineralizer regenerant, inorganic metal cleaning waste and boiler blowdown prior

to the NPDES discharge. Located north of the intake water canal and northwest across the plant road from the inorganic pond, the unit consists of the mixing chamber (300 gallon), flocculation chamber (1,100 gallon), settling chamber (6,900 gallon) and pH adjustment chamber, (300 gallon). The Hazardous Waste Components List describes the unit as a surface processing tank but the type of tank is not known (13). 8,600 gallons were generated from this unit in 1980 (11, pg. 2). The files did not contain information about containment structures or drainage pathways.

SWMU #7 Waste Oil and Sludge Collection Facility:

Oily sludge from the oily waste treatment system is classified as either a Class I (nonhazardous) or Class II waste. No other information (quantity, age, location, pathways) about this unit was available (11, pg. 3).

SWMU #8 Asbestos in Insulation:

The original location of the asbestos insulation is not known. In 1980, 3,600 pounds of asbestos were placed in bags and then wet before being removed off-site (13, pg. 14). The waste was classified as a Class I nonhazardous waste (TWC 170750) (11). The plant map shows that the asbestos is stored in an implement shed north of, and adjacent to, the warehouse. It is not known if more asbestos insulation is present.

PATHWAY CHARACTERISTICS

Air Pathway Characteristics

No information about air pathway characteristics was available. The contaminants of concern are primarily heavy metals in the form of liquids and sludges. Migration into the air pathway is unlikely.

Ground Water Characteristics

The plant is located in the Gulf Coastal Plain on the Beaumont Formation. The lithology of the subsurface consists mainly of deltaic clays and silts grading to the south towards the Gulf of Mexico. The Beaumont Formation is part of a larger stratigraphic unit known as the Chicot Formation. The formation is approximately 700 feet thick and forms the uppermost aquifer under the site. It is used as a drinking water source for this area.

In the Webster area, the formation is differentiated into the Upper and Lower Chicot with the Alta Loma Sand member (approximately 120 feet thick) as being the main water bearing sand of the Lower Chicot.

The Upper and Lower Chicot Sands are interconnected hydrologically. The upper unit is tight because of the higher clay to sand ratio. The plant and the surrounding area pump predominantly from the Alta Loma Sand. Ground water flow direction regionally is to the south, but due to the heavy usage from the Houston area, the ground water flow is to the northwest. The generating plant has two on-site wells with total depths of 636 feet and 664 feet. They are screened in the Lower Chicot aquifer (17). The company well has a 20 foot sand bed at 100 feet and a 120 foot sand bed at 500 feet. The material between these layers is predominantly clay and silty clay. The 500 foot sand bed is the Alta Loma Member.

The formation stratigraphically below the Chicot Sand is the Evangeline Formation. Although it is also a water bearing unit, the encroachment of salt water is increasing so most wells are screened in the Alta Loma Sand unit.

Four monitoring wells are located around the impoundments at the site. The stratigraphy from the borings around the surface impoundments revealed a deltaic lithology. The stratigraphy beneath the impoundments is undefined 30 feet below the ground surface. A 15 foot sand is located 40 feet beneath the impoundments. A 15 foot silty clay layer, overlying a sandy clay, is located 60 to 80 feet beneath the impoundments. The static water level recorded in the monitoring wells is located 6 to 14 feet below the ground surface level (5). Water levels from the monitoring wells revealed that MW-1 is influenced by the cooling water discharge canal. MW-1 is located approximately 100 feet south of the canal, which has a water elevation of 12.82 feet. The canal may act as a recharge feature since the water elevation for MW-1 is 10.53 feet (5, pg. 9).

The net precipitation for the plant area is -2 inches (1).

Surface Water Characteristics

The local topography is flat, with a slight general slope to the south-southeast. The plant is located approximately 1,000 feet from Clear Creek. The intake and discharge canals are located approximately 100 to 200 feet from the surface impoundments. The surface water runoff from the ponds would flow south into Clear Creek (2). The discharge canal flows approximately 3 miles into a sewage disposal plant then, and into Clear Lake, which flows into Galveston Bay. Both are used for recreational purposes. Galveston Bay is also used for commercial fishing (22). The site is located in the San Jacinto River Basin (2).

No intakes are located on these surface water bodies because they are subject to tidal surges (15). The annual stream flow and upgradient drainage area estimates are not known.

Located in a 100 year floodplain, the site area receives a two year, 24 hour average rainfall of 5 inches. Flooding of the facility is unlikely because the

elevation difference between the site and the banks of Clear Creek is approximately 20 feet (2).

On-Site Pathway Characteristics

The facility is active, with both controlled access and a fence surrounding the property. The number of employees present on-site and the number of employees coming into direct contact with the waste process are not known. Data suggest that the waste treatment process is a closed system in which contents are pumped from one SWMU to another without being handled by employees. The sandblasting grit is in an open bin and the surface impoundments are also open. It has not been determined how the solvents, waste oils, paint thinner and sludges are drummed and removed.

TARGETS

According to the Galveston County Health Department, private drinking water wells are used, but the exact number and location of the wells is not known. Most of southeast Harris County and Galveston County use 90% to 97% surface water from Lake Houston. The remaining 3% to 10% is mixed with ground water from public supply wells (17). Irrigation well data are available, but it is not known how many of the wells are currently used for this purpose (20). According to the CME, there are 152 water wells in a 2.5 mile radius of the site. This includes 60 domestic wells, 26 public wells, 25 undocumented wells, 19 wells no longer in use, 13 industrial wells, 3 observation wells, 1 livestock well and 1 service station well. The wells range from 84 to 700 feet deep and are screened in either the Upper Chicot or the Lower Chicot Aquifer (5).

The surface water (Clear Lake) is used as contact recreation for boating, swimming and fishing. On the bay, fishing is a commercial enterprise (22).

There are no data supporting an air target or on-site target. The population within one mile is estimated at 800 (2).

CONCLUSIONS

The function of the plant is to produce electricity. The waste process is generated through the boiling and subsequent cooling of water used in the generation of steam.

The SWMUs are the receptacles for the process water pathway. The eight identified SWMUs include 3 surface impoundments, 1 set of drying beds, the chemical waste treatment system, the waste oil and sludge collection facility, the hazardous waste container storage area and the asbestos in insulation. The original location of the asbestos and the manner in which it was removed have not been determined.

The sampling results found in the 1987 CME show significant contamination of the ground water from MW-1 as compared to MW-2. MW-1 could be affected by the

discharge canal 100 feet north. Elevated levels of manganese, magnesium, iron and zinc were reported. Robert Hahn, Inspector for the TWC noted that the possibility of acid leaching metals from the soil around the surface impoundments was possible because the background soil analysis showed a higher concentration of arsenic, mercury and chromium than the soil around the impoundments. Sample analyses of other on-site areas show no significant contamination.

The state has certified a clean closure for the demineralizer regenerant surface impoundment and the inorganic metal cleaning surface impoundment. An affidavit of exclusion was granted on August 17, 1987. Clean closure requires the removal of residues but does not require the plant to fill and cap the impoundments. It is not known whether post-closure sampling has taken place.

The financial status of Houston Lighting and Power appears to be sound. The sales of the company totalled (b) (4). The net value of the company has not been determined.

The results from the monitoring well installation showed clay to a depth of 20 feet. The contaminants present are metals, which will not migrate quickly through clay (5).

The primary pathway of concern is ground water because the surface water used for public supply is upgradient from the site. The ground water is used to supplement the public water supply. The Alta Loma Sand Member of the Lower Chicot Aquifer is the source of the local ground water. The Lower and Upper Chicot are interconnected and the Upper Chicot outcrops on the land surface. The Upper Chicot is composed of deltaic silts, sands and clays which retard vertical migration in the Upper member. No known wells are screened in the Upper Chicot.

The static water levels in the monitoring wells ranged from 6 to 14 feet from the surface, but the levels in one of the company wells and in a City of Webster well in 1971 were 200 and 207 feet, respectively. Both static water levels have dropped since the 1950s (21). Although the aquifer is interconnected, the water bearing zone is approximately 500 to 600 feet below the land surface and horizontal migration is calculated to be approximately 6 feet per year. The exact rate of vertical migration could not be determined, but it is probable that migration is slow since the plant is located on the Beaumont Formation which has a high clay content (5). Although the site specific ground water movement is not known, the evidence indicates the discharge canal influences the background MW-1 based on high conductivity readings at both locations.

Houston Lighting & Power - Webster
STATE: Texas
NUMBER: TXD000837369

For the Reference

Hazardous Waste Site Ranking System:
263. July 16, 1982,

Topographic map. League City.

Hazardous Properties of Industrial
Van Nostrand Reinhold Company.

Soil Frequency Atlas of the United
Agriculture Soil Conservation
40. 1961.

Water Commission Inspector.
Monitoring Evaluation (CME)
June 5, 1987.

Water Commission Hazardous and Solid
Waste Compliance Monitoring
No. 31633, October 21, 1986.

Water Commission Hazardous and Solid
Waste Compliance Monitoring
No. 31633, July 14, 1986.

Water Commission Hazardous and Solid
Waste Compliance Monitoring
No. 31633, December 12, 1985.

League City, Hazardous Waste Management
From: W.F. McGuire, Manager,
Department, Houston Lighting and
Power Information Request. November

Chief, Solid Waste Section Texas
Department. From: W.F. McGuire, Manager,
Department, Houston Lighting and
Power Closure Plan for Hazardous Waste
Site, 1985.

ch
l.

is
rt

14,

DES.

rom:
the

isive
No.


n
r

:
r

um
le

es
I.
ch

is.
of



NOT TO SCALE

Facility Plot Plan
HOUSTON LIGHTING AND POWER
WEBSTER GENERATING PLANT
WEBSTER, TX

Figure 2

PA DOCUMENTATION LOG SHEET	SITE NAME: Houston Lighting & Power - Webster CITY: Webster STATE: Texas IDENTIFICATION NUMBER: TXD000837369
Reference Number	Description of the Reference
1	U.S. EPA Uncontrolled Hazardous Waste Site Ranking System: A Users Manual. 47FR31219-31263. July 16, 1982, (Appendix A, CERCLA).
2	U.S.G.S. 7.5 minute series Topographic map. <u>League City, TX</u> . 1982.
3	Sax, N. Irving. 1984. <u>Dangerous Properties of Industrial Materials</u> . Sixth Edition. Van Nostrand Reinhold Company.
4	Hershfield, David M. Rainfall Frequency Atlas of the United States. U.S. Department of Agriculture Soil Conservation Service. Technical Paper No. 40. 1961.
5	Hahn, Robert, Texas Water Commission Inspector. Comprehensive Ground Water Monitoring Evaluation (CME) Report, TWC Reg. No. 31633, June 5, 1987.
6	Thetford, Paula, Texas Water Commission Hazardous and Solid Waste Specialist. Solid Waste Compliance Monitoring Inspection Report, TWC Reg. No. 31633, October 21, 1986.
7	Thetford, Paula, Texas Water Commission Hazardous and Solid Waste Specialist. Solid Waste Compliance Monitoring Inspection Report, TWC Reg. No. 31633, July 14, 1986.
8	Bleam, Karen, Texas Water Commission Hazardous and Solid Waste Specialist. Solid Waste Compliance Monitoring Inspection Report, TWC Reg. No. 31633, December 12, 1985.
9	Letter. To: William N. Rhea, Hazardous Waste Management Division, EPA Region VI. From: W.F. McGuire, Manager, Environmental Protection Department, Houston Lighting and Power. Re: RCRA Section 3007 Information Request. November 8, 1985.
10	Letter. To: Jay Snow, P.E., Chief, Solid Waste Section Texas Department of Water Resources. From: W.F. McGuire, Manager, Environmental Protection Department, Houston Lighting and Power. Re: Supplement to Closure Plan for Hazardous Waste Surface Impoundments. May 6, 1985.

PA DOCUMENTATION LOG SHEET	SITE NAME: Houston Lighting & Power - Webster CITY: Webster STATE: Texas IDENTIFICATION NUMBER: TXD000837369
Reference Number	Description of the Reference
11	Letter. To: Ray Henry Austin, P.E., Storage and Processing Facilities Unit, Texas Water Commission. From: W.F. McGuire, Manager, Environmental Protection Department, Houston Lighting and Power. Re: Revised Part A Application. February 8, 1985.
12	Letter. To: James R. Mertink, Houston Lighting and Power Company. From: Edward J. Ulrich, Jr., P.E., Engineer Manager, McClelland Engineers, Inc. Re: Geotechnical Investigation, Class I Disposal Ponds. November 16, 1981.
13	Part A - Permit Application Facility Background Information for Houston Lighting and Power, Webster Generating Station. August 18, 1980.
14	Standard and Poor's Corporation, Register of Corporations, Directors and Executives, Vol. I. 1989.
15	ROC. To: Mr. Sewers, Houston Water Authority. From: Pam Fetzer, FIT Geologist, EPA Region VI. Re: Intake Locations for Lake Houston. March 14, 1989.
16	ROC. To: Mr. Will Moberly, Clear Lake Water Authority. From: Pam Fetzer, FIT Geologist, EPA Region VI. Re: Public Water Source for Clear Lake City. March 13, 1989.
17	ROC. To: Ernest Baker, Hydrologist, U.S.G.S. From: Pam Fetzer, FIT Geologist, EPA Region VI. Re: Hydrogeology of the Southeast Houston area. March 14, 1989.
18	ROC. To: Joe Castleberry, Analyst, Texas Public Utilities Commission. From: Pam Fetzer, FIT Geologist, EPA Region VI. Re: Financial History of the Webster Generating Plant. March 7, 1989.
19	ROC. To: Dan Bulla, Shareholder Relations, Houston Industries. From: Pam Fetzer, FIT Geologist, EPA Region VI. Re: Value of the Webster Generating Plant. March 7, 1989.

PA DOCUMENTATION LOG SHEET

SITE NAME: Houston Lighting & Power - Webster
CITY: Webster STATE: Texas
IDENTIFICATION NUMBER: TXD000837369

Reference Number	Description of the Reference
20	ROC. To: Janet Greenwood, Supervisor, Galveston County Health Department. From: Pam Fetzner, FIT Geologist, EPA Region VI. Re: Privately Owned Ground Water Wells. March 14, 1989.
21	Texas Water Development Board, Ground-Water Data for Harris County, Texas, Volume II, Records of Wells, 1892-1972, Report 178: pp. 172, 173. January 1974.
22	ROC. To: Henry Fleming, Engineer, Corps. of Engineers From: Pam Fetzner, FIT Geologist, EPA Region VI. Re: Surface Water Use In Southeast Houston Area, March 14, 1989.
23	Application for Permit to Discharge Waste Water Form 2C NPDES. U.S. EPA Region VI. April 14, 1987.
24	ROC. To: Gene Keepper, Biologist, U.S. EPA, Region VI. From: Pam Fetzner, FIT Geologist, EPA Region VI. Re: Wetlands in the Southeast Houston Area. March 23, 1989.
25	Hahn, Robert, Texas Water Commission Inspector. Comprehensive Ground Water Monitoring Evaluation (CME) Report, TWC Reg. No. 31633, September 16, 1987.



Uncontrolled Hazardous Waste Site Ranking System

A Users Manual (HW-10)

Originally Published in
the July 16, 1982, *Federal Register*

United States
Environmental Protection
Agency

1984



Site Location Map
HOUSTON LIGHTING & POWER
WEBSTER PLANT

WEBSTER, TX

TDD NO. F-6-8902-25
CERCLIS NO. TXD000837369



QUADRANGLE LOCATION
DALLAS, TX

Dangerous Properties



Industrial Materials

Sixth Edition

 **N. Irving Sax** 

792 CHROMIUM OXYCHLORIDE

Carcinogenic Determination: Animal Positive IARC** 23,205,80; Indefinite IARC** 2,100,73. *Toxicology Review*: 85DHAX Cr,22,74; 27ZTAP 3,38,69.

Standards and Regulations: OSHA Standard Air: CL 100 ug(CrO₃)/m³ (SCP-0) FEREAC 39,23540,74. DOT: Oxidizer, Label: Oxidizer FEREAC 41,47018,76. Occupational Exposure to Cr(VI) recm std: Air: TWA 25 ug(Cr(VI))/m³; CL 50 ug/m³/15M NTIS**. Meets Criteria for Proposed OSHA Medical Records Rule FEREAC 47,30420,82.

THR: MUT data. An exper TER, CARC. HIGH scu. See also chromium compounds.

Disaster Hazard: Powerful oxidizer.

Incomp: Acetic acid; acetic anhydride; acetic anhydride + tetrahydronaphthalene; acetone; alcohols; alkali metals; ammonia; arsenic; bromine pentafluoride; butyric acid; N,N-dimethylformamide; hydrogen sulfide; peroxyformic acid; phosphorus; potassium hexacyanoferrate; pyridine; selenium; sodium; sulfur.

CHROMIUM OXYCHLORIDE

CAS RN: 14977618 NIOSH #: GB 5775000
mf: Cl₂CrO₂; mw: 154.90

Dark red liquid, musty burning odor. mp: -96.5°; bp: 115.7°; d: 1.9145 @ 25°/4°; vap press: 20 mm @ 20°.

SYNS:

CHROMYL CHLORIDE
CHLORURE DE CHROMYLE
(FRENCH)

CHROMIC OXYCHLORIDE
CHROMIUM CHLORIDE OXIDE
CHROMIUM DICHLORIDE DIOXIDE
CHROMIUM DIOXIDE DICHLORIDE
CHROMIUM (VI) DIOXYCHLORIDE
CHROMYLCHLORID (GERMAN)

CHROMOXYLCHLORIDE (DUTCH)
CROMILE, CLORURO DI (ITALIAN)
CROMO, OSSICLORURO DI (ITALIAN)

DICHLORODIOXOCHROMIUM
DIOXODICHLOROCHROMIUM
OXYCHLORURE CHROMIQUE
(FRENCH)

TOXICITY DATA: 3 CODEN:
mmo-sat 50 ug/plate CRNGDP 1,583,80
mma-sat 100 ug/plate CRNGDP 1,583,80

Aquatic Toxicity Rating: TLm96: under 1 ppm WQCHM* 2,-,74. TLV-TWA 25 ppb DTLVS* 4, 100,80. DOT: Corrosive Material, Label Corrosive FEREAC 41,57018,76. Occupational Exposure to Chromium (VI) recm std: Air: CL 1 ug (Cr(VI))/m³ NTIS**. Reported in EPA TSCA Inventory, 1980.

THR: HIGH via scu and inhl routes. A strong irr. Hydrolyzes to form chromic and hydrochloric acids. See chromium compounds. Reacts violently with alcohol, ether, acetone, turpentine, NH₃, (Cl₂ + C), F₂, P, PCl₃, NaN₃, S, SCl.

Disaster Hazard: Dangerous; see chlorides.

Incomp: During preparation can violently explode. Ammonia; disulfur dichloride; organic solvents; phosphorus, or phosphorus trichloride; sodium azide; sulfur.

CHROMIUM(6+)

ZINC OXIDE HYDRATE (1:2:6:1)

CAS RN: 15930946 NIOSH #: GB 3260000
mf: CrO₄•H₂O₂•Zn₂•H₂O; mw: 298.78

SYNS:

BUTTERCUP YELLOW
ZINC CHROMATE HYDROXIDE
ZINC CHROMATE (VI) HYDROXIDE

ZINC HYDROXYCHROMATE
ZINC YELLOW

TOXICITY DATA: 3 CODEN:

Carcinogenic Determination: Animal Positive IARC** 2,100,73; Human Positive IARC** 23,205,80. *Toxicology Review*: PEXTAR 12,102,69; 85DHAX Cr,22,74; AMTODM 3,209,77. Occupational Exposure to Chromium (VI) recm std: Air: CL 1 ug(Cr(VI))/m³ NTIS**.

THR: A hmn + CARC. An exper CARC. See also chromium and zinc compounds.

CHROMOMYCIN SODIUM

NIOSH #: RK 4385300

Produced by a strain of *Actinomyces Olivoreticuli* (85ERAY 2,1322,78)

SYN: OLIVOMYCIN, SODIUM SALT

TOXICITY DATA: 3 CODEN:

ipr-rat LDLo: 1 mg/kg
ivn-rat LDLo: 1 mg/kg
ori-mus LDLo: 250 mg/kg
ipr-mus LD50: 12700 ug/kg
scu-mus LD50: 15600 ug/kg
ivn-mus LD50: 138 mg/kg
ivn-dog LDLo: 300 ug/kg
ivn-rbt LDLo: 2500 ug/kg
ipr-gpg LDLo: 2 mg/kg

ANTBAL 7,53,62
ANTBAL 7,53,62
ANTBAL 7,53,62
ANTBAL 7,53,62
ANTBAL 7,53,62
85ERAY 2,1322,78
ANTBAL 7,53,62
ANTBAL 7,53,62
ANTBAL 7,53,62

THR: HIGH ipr, ivn, orl, scu.

Disaster Hazard: When heated to decomp it emits acrid smoke and irr fumes.

CHROMYL AZIDE CHLORIDE

mf: ClCrN₃O₂; mw: 161.47

Explosive.

CHROMYL ISOCYANATE

mf: C₂CrN₂O₄; mw: 168.03

Weak explosion of salt when evaporated with heat at atmospheric pressure.

CHROMYL PERCHLORATE

mf: Cl₂CrO₁₀; mw: 282.90

Incomp: Self-explodes or organic solvents.

C.I. 45405

CAS RN: 6441776 NIOSH #: LM 5820000
mf: C₂₀H₆Br₄Cl₂O₅•2K; mw: 794.93

SYNS:

C.I. ACID RED 98
PHLOXINE

TOYO ACID PHLOXINE

TOXICITY DATA:
mmo-esc 15 mg/L

CODEN:
MUREAV 16,165,72

ipr-rbt LD50:250 mg/kg
scu-rbt LDLo:500 mg/kg
ivn-rbt LDLo:400 mg/kg

JPETAB 42,253,31
JPETAB 49,187,33
JPETAB 60,125,37

THR: MOD by ingestion. Large doses cause marked depression (sometimes preceded by excitation), prolonged coma and death. Allergic skin reactions may occur from contact. Has been implicated in development of aplastic anemia. A truly habit forming drug. An exper TER in mus. MUT data.

Fire Hazard: Slight, when heated.

Disaster Hazard: When heated to decomp it emits tox fumes of NO₂.

BARBITURATES

SYNS:

DERIVATIVES OF BARBITURIC
ACID; I.E.
BARBITAL

BARBITONE
BARBITAL SODIUM

THR: MOD by ingestion. Large doses cause marked depression (sometimes preceded by excitation), prolonged coma and death. Allergic skin reactions may occur from contact. Has been implicated in development of aplastic anemia. A truly habit forming drug.

Fire Hazard: Slight, when heated.

BARBITURIC ACID

mf: C₄H₄O₃N₂; mw: 128.1

Crystals or white to yellow-white powder. mp: 245°; bp: 260° (decomp).

THR: MOD irr to skin, eyes and mu mem. An allergen. Has no hypnotic properties.

Fire Hazard: Slight.

BARBITURIC ACID, 5,5-DIETHYL MIXED WITH 4-(DIMETHYLAMINO)ANTIPYRINE

CAS RN: 69401338

NIOSH #: CD 2630000

SYN: PYRABITAL

TOXICITY DATA: 3
scu-mus TDLo:600 mg/kg (9-11D
preg)

CODEN:
TJADAB 16,118,77

THR: An exper TER.

Disaster Hazard: When heated to decomp it emits tox fumes of NO₂.

BARIUM

CAS RN: 7440393

NIOSH #: CA 8370000

af: Ba; at wt: 137.36

Silver-white, slightly lustrous, somewhat malleable metal. mp: 725°, bp: 1640°, d: 3.5 @ 20°, vap. press: 10 mm @ 1049°.

TOXICITY DATA: **CODEN:**
TLV: Air: 500 ug/m³ DTLVS* 4,35,80. Reported in EPA TSCA Inventory, 1980.

THR: No data. See also barium compounds.

Fire Hazard: Dangerous and explosive in form of dust when exposed to heat or flame or by chemical reaction.

Incomp: Acids, CCl₄, C₂Cl₃F₃, C₂H₂FCF₃, C₂Cl₄, C₂HCl₃ and water. 1,1,2-trichloro trifluoro ethane, fluorotrichloroethane, fluorotrichloromethane, trichloroethylene can detonate in contact with Ba.

For further information see Vol. 1, No. 7 and Vol. 3, No. 4 of *DPIM Report*.

BARIUM ACETATE

CAS RN: 543806

NIOSH #: AF 4550000

mf: C₄H₆O₄•Ba; mw: 255.44

White cryst. Water sol.

SYNS:

ACETIC ACID, BARIUM SALT
BARIUM DIACETATE

OCTAN BARNATY (CZECH)

TOXICITY DATA:

3-2

CODEN:

ori-rat LD50:921 mg/kg
ivn-mus LD50:11 mg/kg
scu-rbt LDLo:96 mg/kg
ivn-rbt LDLo:12 mg/kg

MarJV # 29MAR77
TXAPA9 22,150,72
EQSSDX 1,1,75
EQSSDX 1,1,75

OSHA Standard: Air: TWA 500 ppm (SCP-X) FEREAC 39,23540,74. Reported in EPA TSCA Inventory, 1980.

THR: HIGH ivn, scu. MOD ori.

Disaster Hazard: When heated to decomp it emits acrid smoke.

BARIUM ACETYLIDE

mf: C₂Ba; mw: 161.35

Incomp: Halogens, selenium.

BARIUM AZIDE

CAS RN: 18810587

NIOSH #: CQ 8500000

mf: BaN₆; mw: 221.40

Monoclinic prisms. mp: -N₂ @ about 120°, bp: explodes, d: 2.936.

TOXICITY DATA:

3

CODEN:

Aquatic Toxicity Rating: TLM96:100-10 ppm WQCHM* 2,-,74. Reported in EPA TSCA Inventory, 1980.

THR: See barium compounds (sol) and azides.

Explosion Hazard: Mod when shocked or exposed to heat. Around 275°, spont flammable in air. Very unstable.

Disaster Hazard: Dangerous; shock and heat will explode it.

BARIUM AZIDE (WET)

CAS RN: 18810587

NIOSH #: CQ 8510000

Compound contains 50% or more water (FEREAC 41,15972,76)

TOXICITY DATA:

3

CODEN:

DOT: Flammable Solid, Label: Flammable Solid FEREAC 41,57018,76. Reported in EPA TSCA Inventory, 1980.

THR: HIGH tox. See also barium compounds and azides.

Disaster Hazard: Possibly explosive.

610 CADMIUM

TOXICITY DATA:

Currently tested by NTP for carcinogenesis by standard bioassay protocol as of December 1980.

THR: No data. Under CARC test.

Disaster Hazard: When heated to decomp it emits acrid smoke and fumes.

CADMIUM

CAS RN: 7440439
mf: Cd; mw: 112.40

NIOSH #: EU 9800000

Hexagonal crystals, silver-white malleable metal. mp: 320.9°, bp: 767 ± 2°, d: 8.642, vap. press: 1 mm @ 394°.

SYNS:

C.I. 77180

KADMIUM (GERMAN)

TOXICITY DATA: 3

ivn-rat TDLo: 1250 ug/kg/(9D preg): TER
ipr-mus TDLo: 2248 ug/kg/(8D preg): TER
ivn-ham TDLo: 2 mg/kg/(8D preg): TER
ims-rat TDLo: 45 mg/kg/4W-I: NEO

ims-rat TD: 70 mg/kg: ETA
ims-rat TD: 63 mg/kg: ETA
ihl-man TCLo: 88 ug/m3/8.6Y: SYS
ihl-hmn LCLo: 39 mg/m3/20M
unk-man LDLo: 15 mg/kg
ori-rat LD50: 225 mg/kg
ipr-rat LD50: 4 mg/kg
scu-rat LD50: 9 mg/kg
ivn-rat LD50: 3 mg/kg
unk-rat LD50: 712 mg/kg
unk-mus LD50: 636 mg/kg
ori-rbt LDLo: 70 mg/kg
scu-rbt LDLo: 6 mg/kg
ims-ham LDLo: 25 mg/kg
cyt-ham: ovr 1 umol/L
ipr-rat TDLo: 1124 ug/kg (1D male)
scu-rat TDLo: 250 ug/kg (19D preg)
ori-mus TDLo: 448 mg/kg (MGN)

CODEN:

EVHPAZ 28,245,79
TJADAB 13,33A,76
EXPEAM 25,56,69
NCIUS* PH-43-64-886, SEPT, 71
BJCAAI 18,124,64
NATUAS 193,592,62
AEHLAU 28,147,74
AIHAAP 31,180,70
85DCAI 2,73,70
TXAPA9 41,667,77
TXAPA9 41,667,77
TXAPA9 41,667,77
TXAPA9 41,667,77
GTPZAB 22(5),6,78
GTPZAB 22(5),6,78
AMPMAR 34,127,73
PROTA* -,55
NCIUS* PH-43-64-886
CGCGBR 26,251,80
TXAPA9 41,194,77
APTOD9 19,A122,80
AEHLAU 23,102,71

Carcinogenic Determination: Animal Positive IARC** 2,74,73.

TLV: Air: 0.05 mg/m3 DTLVS* 4,59,80; TRBMAV 33(1),85,75; JDSCAE 58(12),1767,75; JFDSA 39,321,74; AMBOCX 3(2),55,74; QURBAW 7(1),75,74; AEMBAP 40,239,73; NTIS** PB-221,198; KOTTAM 11(11),1300,75; FOREAE 7,313,42; STEVA8 2(4),341,74; FCTXAV 9,105,71; AJMEAZ 38,409,65; ENVRAL 4,71,71; 85CVA2 5,63,70; PEX-TAR 12,102,69; PDTNBH 6,204,77; BNYMAM 54,413,78; AMTODM 3,209,77; GSAMAQ 123,109,71. OSHA Standard: Air: TWA 200 ug/m3; CL 600 (SCP-W) FEREAC 39,23540,74. Occupational Exposure to Cadmium recm std: Air: TWA 40 ug/m3; CL 200 ug/m3/15M NTIS**. "NIOSH Manual of Analytical Methods" VOL 1 191,223,224, VOL 3 S312, S313, VOL 5 173#. Reported in EPA TSCA Inventory, 1980.

THR: MUT data. An exper TER, NEO, ETA, CARC. A human SYS. HIGH hmn ihl, unk. HIGH ori, ipr,

scu, ivn, ims. MOD unk. See also cadmium compounds.
Fire Hazard: Mod, in the form of dust when exposed to heat or flame or by chemical reaction with oxidizing agents, metals, HN₃, Zn, Se and Te.

Explosion Hazard: Mod, in the form of dust when exposed to flame.

Disaster Hazard: Dangerous; cadmium dust can react vigorously with oxidizing materials.

For further information see Vol. 1, No. 1 and Vol. 3, No. 5 of *DPIM Report*.

CADMIUM (II) ACETATE

CAS RN: 543908

NIOSH #: EU 9810000

mf: C₂H₄O₂·1/2Cd; mw: 116.25

Monoclinic colorless crystals, odor of acetic acid. mp: 256°, bp: decomp, d: 2.341.

SYNS:

BIS(ACETOXY)CADMIUM
CADMIUM DIACETATE

C.I. 77185

TOXICITY DATA: 3

otr-ham: emb 1 umol/L
dnd-ham: emb 1 umol/L
ipr-mus LD50: 14 mg/kg
cyt-hmn: lym 10 nmol/L
ipr-rat TDLo: 2371 ug/kg (14D preg)
ipr-rat TDLo: 1 mg/kg (14D preg)
ipr-rat TDLo: 2 mg/kg (20D preg)

CODEN:

CNREA8 39,193,79
CNREA8 39,193,79
TXAPA9 49,41,79
MUREAV 85,236,81
BECTA6 20,206,78
BECTA6 23,25,79
BECTA6 23,25,79

Reported in EPA TSCA Inventory, 1980.

THR: MUT data. HIGH ipr. See also cadmium compounds.

Disaster Hazard: When heated to decomp it emits toxic fumes of Cd.

CADMIUM BIS(2-ETHYLHEXYL) PHOSPHITE

CAS RN: 7495934

NIOSH #: TG 6475000

mf: C₃₂H₆₈O₆P₂·Cd; mw: 723.34

SYN: PHOSPHORUS ACID, BIS(2-ETHYLHEXYL) ESTER, CADMIUM SALT

TOXICITY DATA: 3

ipr-mus LDLo: 250 mg/kg

CODEN:

CBCCT* 7,790,55

Occupational Exposure to Cadmium recm std: Air: TWA 40 ug/m3; CL 200 ug/m3/15M NTIS**.

THR: HIGH ipr. See also cadmium compounds.

Disaster Hazard: When heated to decomp it emits toxic fumes of PO₂ and Cd.

CADMIUM CAPRYLATE

CAS RN: 2191108

NIOSH #: RH 0370000

mf: C₁₆H₃₀O₄·Cd; mw: 398.86

SYN: OCTANOIC ACID, CADMIUM SALT (2:1)

TOXICITY DATA: 3-2

ori-rat LD50: 950 mg/kg
itr-rat LDLo: 10 mg/kg
ori-mus LD50: 300 mg/kg

CODEN:

JHEMA2 18,144,74
JHEMA2 18,144,74
JHEMA2 18,144,74

Occupational Exposure to Cadmium recm std: Air: TWA 40 ug/m3; CL 200 ug/m3/15M NTIS**. Reported in EPA TSCA Inventory, 1980.

SYN: MERCURY NUCLEATE, SOLID (DOT)

TOXICITY DATA: 3

DOT: Poison B, Label: Poison FEREAC 41,57018,76.

Occupational Exposure to Inorganic Mercury recm std:

Air: TWA 0.05 mg(Hg)/m³ NTIS**.

THR: A poison. See also mercury compounds.

Disaster Hazard: When heated to decomp it emits tox fumes of Hg.

MERCUROPHEN

CAS RN: 17140737

NIOSH #: OW 4550000

mf: C₆H₄HgNO₄·Na; mw: 377.70Brick-red odorless powder. Sol in hot H₂O.

TOXICITY DATA: 3

CODEN:

ivn-rat LDLo: 8 mg/kg

12VXA5 8,661,68

ims-rat LDLo: 12 mg/kg

12VXA5 8,661,68

ivn-rbt LDLo: 4 mg/kg

12VXA5 8,661,68

Occupational Exposure to Inorganic Mercury recm std:

Air: TWA 0.05 mg(Hg)/m³ NTIS**.

THR: HIGH ivn, ims. See also mercury compounds. Poison.

Disaster Hazard: When heated to decomp it emits very tox fumes of NO₂ and Hg vapors.**MERCUROPHYLLINE**

CAS RN: 8012348

NIOSH #: OV 8650000

SYNS:

MERCUPURIN

MERCUZANTHIN

TOXICITY DATA: 3-2

CODEN:

ivn-hmn TDLo: 28 mg/kg; CNS

JAMAAP 117,1806,41

scu-mus LD50: 163 mg(Hg)/kg

JPETAB 105,336,52

ivn-mus LD50: 1410 mg/kg

JPETAB 99,149,50

ivn-cat LDLo: 250 mg/kg

JPETAB 99,149,50

ivn-rbt LDLo: 177 mg/kg

JPETAB 99,149,50

Occupational Exposure to Inorganic Mercury recm std:

Air: TWA 0.05 mg(Hg)/m³ NTIS**.

THR: A hmn CNS. HIGH scu, ivn. MOD ivn. See also mercury compounds.

Disaster Hazard: When heated to decomp it emits tox fumes of Hg.

MERCUROUS CHLORIDE

CAS RN: 7546307

NIOSH #: OV 8750000

mf: Cl₂Hg₂; mw: 472.09

White, odorless, tasteless, heavy powder or crystals. Sunlight causes it to decomp into mercuric chloride and metallic Hg. Insol in H₂O, alc and ether. Protect from light. Subl @ 400°; d: 7.150.

SYNS:

MERCURY(I) CHLORIDE
C.I. 77764

CALOMEL

CALOMELANO (ITALIAN)

CHLORURE MERCUREUX

(FRENCH)

CLORURO MERCUROSO (ITALIAN)

KALOMEL (GERMAN)

MERCUROCHLORIDE (DUTCH)

MERCURY MONOCHLORIDE

MERCURY PROTOCHLORIDE

MILD MERCURY CHLORIDE

QUECKSILBER(I)-CHLORID (GERMAN)

SUBCHLORIDE OF MERCURY

TOXICITY DATA: 3

CODEN:

mrc-bcs 50 mmol/L

MUREAV 77,109,80

ori-rat LD50: 210 mg/kg

WRPCA2 9,119,70

Toxicology Review: SDGTB3 1(2),177,71; RREVAH 42,103,72; 27ZTAP 3,91,69. Occupational Exposure to Inorganic Mercury recm std: Air: TWA 0.05 mg(Hg)/m³ NTIS**. Reported in EPA TSCA Inventory, 1980.

THR: MUT data. HIGH ori. See also mercury compounds.

Disaster Hazard: When heated to decomp it emits very tox fumes of Cl⁻ and Hg.

Human Tox: Excessive doses may cause Hg poisoning.

Antidote: BAL (Dimercaprol). If laxation from oral mercurous chloride should not occur, saline laxative must be administered to prevent possibility of Hg poisoning.

Med Incomp: Bromides, iodides, alkali chlorides, sulfates, sulfites, carbonates, hydroxides, lime water, acacia, ammonia, golden antimony sulfide, cocaine, cyanides, copper salts, hydrogen peroxide, iodine, iodoform, Pb salts, silver salts, soap, sulfides.

MERCURY

CAS RN: 7439976

NIOSH #: OV 4550000

af: Hg; aw: 200.59

Silvery liquid, metallic element. mp: -38.89°, bp: 356.9°, d: 13.546, vap. press: 1 mm @ 126.2°. vap press: @ 25° = 2 × 10⁻³ mm.

SYNS:

COLLOIDAL MERCURY

KWIK (DUTCH)

MERCURE (FRENCH)

MERCURIO (ITALIAN)

MERCURY, METALLIC (DOT)

NCI-C60399

QUECKSILBER (GERMAN)

QUICK SILVER

RTEC (POLISH)

TOXICITY DATA: 3

CODEN:

ihl-rat TCLo: 890 ng/m³/24H (16W male)

GISAAA 45(3),72,80

ihl-rat TCLo: 7440 ng/m³/24H (16W male)

GISAAA 45(3),72,80

ipr-rat TDLo: 400 mg/kg/14D-1: ETA

ZEKBAI 61,511,57

ihl-wmn TCLo: 150 ug/m³/46D: GIT

AEHLAU 33,186,78

ihl-wmn TCLo: 150 ug/m³/46D: CNS

AEHLAU 33,186,78

ihl-rbt LCLo: 29 mg/m³/30H

AMIHBC 7,19,53

TLV: Air: 0.05 mg(Hg)/m³ (skin) DTLVS* 4,254,80.

Toxicology Review: AJOGAH 126(3),390,76; JTEHD6 2(3),491,77; TRBMAV 33(1),85,75; PHJOAV 213(5781),159,74; JDSCAE 58(12),1767,75; CPEDAM 13,783,74; QURBAW 7(1),75,74; AEMBAP 48,463,74; JAVMA4 164(3),277,74; 31ZNAA 2,365,73; AEMBAP 40,239,73; CTOXAO 5(2),151,72; BIOGAL 41(7),208,75; ADTEAS 5,51,72; RREVAH 42,103,72; FOREAE 7,313,42; NISIA9 27(9),942,74; MIBUBI 9(4),321,75; STEVA8 2(4),341,74; ENVRAL 13,36,77; 85CVA2 5,63,70; JOCMA7 2,337,60; PEXTAR 12,102,69; PDTNBH 6,204,77.

OSHA Standard: Air: CL 1 mg/10m³ (SCP-N) FEREAC 39,23540,74. DOT: ORM-B, Label: None FEREAC 41,57018,76. Occupational Exposure to Inorganic Mercury recm std: Air: TWA 0.05 mg(Hg)/m³ NTIS**. "NIOSH Manual of Analytical Methods" VOL 1

SYNS:

SILICON TETRACHLORIDE

TETRACHLOROSILANE

TOXICITY DATA: 2

CODEN:

ihl-rat LC50: 8000 ppm/4H

JIHTAB 31,343,49

Aquatic Toxicity Rating: TLm96: 1000-100 ppm
 WQCHM* 4,-,74. DOT: Corrosive Material, Label:
 Corrosive FEREAC 41,57018,76. Reported in EPA
 TSCA Inventory, 1980. EPA TSCA 8(a) Preliminary
 Assessment Information Proposed Rule FERREAC
 45,13646,80.

SKIN AND EYE IRRITATION

DATA:

CODEN:

skn-rbt 500 mg/24H SEV

28ZPAK -,14,72

eye-rbt 20 mg/24H SEV

28ZPAK -,14,72

THR: SEV skn, eye irr. MOD ihl. Decomp by water
 with much heat into silicic acid and HCl.

Disaster Hazard: Dangerous; when heated to decomp it
 emits highly tox fumes of HCl; will react with water
 or steam to produce heat and tox and corrosive fumes.

Incomp: Dimethyl sulfoxide, K, Na.

SILICON FLUORIDE

CAS RN: 7783611

NIOSH #: VW 2327000

mf: F₄Si; mw: 104.09

Colorless gas, very pungent odor; mp: -77°; bp: -65°
 @ 181 mm; d: 4.67.

TOXICITY DATA: 3

CODEN:

DOT: Nonflammable Gas, Label: Nonflammable Gas
 FEREAC 41,57018,76. Reported in EPA TSCA Inven-
 tory, 1980.

THR: No data. See also fluorides and hydrofluoric acid.
 Very irr to skn, eyes and mu mem.

Disaster Hazard: When heated to decomp it emits tox
 fumes of F⁻.

SILICON OXIDE

mf: OSi; mw: 44.09

THR: No tox data. Explodes spontaneously in air.

SILICON TETRAAZIDE

mf: N₁₂Si; mw: 196.17

THR: No tox data. See also azides. Has exploded spont.

Disaster Hazard: When heated to decomp it emits tox
 fumes of NO_x.

SILK

NIOSH #: VW 2700000

TOXICITY DATA: 3

CODEN:

imp-rat TDLo: 36 mg/kg: ETA

CNREA8 15,333,55

THR: An exper ETA. In the form of dust it is an allergen
 and a nuisance dust. A MOD fire hazard and expl
 hazard.

Disaster Hazard: When heated to decomp it emits acrid
 smoke and fumes.

SILVER

CAS RN: 7440224

NIOSH #: VW 3500000

af: Ag; aw: 107.87

Soft, ductile, malleable, lustrous, white metal. mp:
 961.93°, bp: 2212°, d: 10.50 @ 20°.

SYNS:

ARGENTUM

SILBER (GERMAN)

C.I. 77820

SILVER ATOM

SHELL SILVER

TOXICITY DATA: 3

CODEN:

mul-rat TDLo: 330 mg/kg/43W-1

ZEKBAI 63,586,60

TFX: ETA

imp-rat TDLo: 2400 mg/kg TFX: ETA

CNREA8 16,439,56

imp-mus TDLo: 11 gm/kg TFX: ETA

NATWAY 42,75,55

imp-rat TD: 2570 mg/kg TFX: ETA

NATWAY 42,75,55

ihl-hmn TCLo: 1 mg/m3 TFX: SKN

DTLVS* 3,231,71

TLV: Air: 0.1 mg/m3 DTLVS* 4,367,80. Toxicology Re-
 view: FOREAE 7,313,42; MIBUBI 9(4),321,75;
 PTPAD4 1,127,76; AJMEAZ 38,409,65; PEXTAR
 12,102,69. OSHA Standard: Air: TWA 10 ug/m3
 (SCP-N) FEREAC 39,23540,74. Reported in EPA
 TSCA Inventory, 1980.

THR: An exper ETA. A hmn SKN. See also silver com-
 pounds.

Fire Hazard: Mod, in the form of dust, when exposed
 to flame or by chemical reaction with C₂H₂, NH₃, bro-
 moazide, ClF₃, ethylene imine, H₂O₂, oxalic acid,
 H₂SO₄, tartaric acid. See also powdered metals.

For further information see Vol. 1, No. 1 of DPIM Report.

SILVER ACETYLIDE

mf: C₂HAg; mw: 132.90

THR: No tox data. See also silver compounds.

Explosion Hazard: Very high.

Disaster Hazard: When heated to decomp it emits acrid
 smoke and fumes.

SILVER AMIDE

mf: AgH₂N; mw: 123.89

THR: No tox data. See also silver compounds. Very ex-
 plosive when dry.

Disaster Hazard: When heated to decomp it emits tox
 fumes of NO_x.

SILVER 5-AMINOTETRAZOLIDE

mf: CH₂AgN₅; mw: 191.93

THR: No tox data. See also silver compounds. When
 heated it explodes.

Disaster Hazard: When heated to decomp it emits tox
 fumes of NO_x.

SILVER AMMONIUM COMPOUNDS

THR: See silver compounds.

Explosion Hazard: Severe, when shocked, exposed to heat
 or by chemical reaction.

2390 SELENIOUS ACID

Disaster Hazard: When heated to decomp it emits tox fumes of Se.

SELENIOUS ACID

CAS RN: 7783008 NIOSH #: VS 7175000
mf: H_2O_3Se ; mw: 128.98

Transparent colorless crystals; mp: decomp; d: 3.004 @ $15^\circ/4^\circ$; vap press: 2 mm @ 15° . Very sol in alc; insol in ammonia.

TOXICITY DATA:	3	CODEN:
orl-rat LDLo: 25 mg/kg		NCNSA6 5,28,53
ipr-rat LDLo: 10 mg/kg		NCNSA6 5,28,53
ivn-mus LD50: 11 mg/kg		CSLNX* NX#05656

OSHA Standard: Air: TWA 200 ug(Se)/m³ (SCP-X) FEREAC 39,23540,74. Reported in EPA TSCA Inventory, 1980.

THR: HIGH orl, ipr, ivn. See also selenium.

Disaster Hazard: When heated to decomp it emits tox fumes of Se.

SELENIUM

CAS RN: 7782492 NIOSH #: VS 7700000
af: Se; aw: 78.96

Steel gray, non-metallic element; mp: 170° - 217° ; bp: 690° ; d: 4.81-4.26; vap press: 1 mm @ 356° .

SYNS:

SELENIUM ALLOY	ELEMENTAL SELENIUM
SELENIUM BASE	SELEN (POLISH)
SELENIUM HOMOPOLYMER	SELENIUM DUST
C.I. 77805	

TOXICITY DATA:	3	CODEN:
orl-mus TDLo: 134 mg/kg (MGN)		AEHLAU 23,102,71
orl-mus TDLo: 480 mg/kg/60D-C:ETA		YMBUA7 11,368,60
ihl-rat LDLo: 33 mg/kg/8H		AMIHBC 4,458,51
ivn-rat LD50: 6 mg/kg		AMIHBC 4,458,51
unk-frg LDLo: 3 mg/kg		PHREA7 23,305,43

TLV: Air: 0.2 mg/m³ (Se) DTLVS* 4,361,80.

Toxicology Review: CTOXAO 6(3),459,73; CTOXAO 5(2),175,72; 31ZNAA 4(3),271,76; JAVMA4 164(3),277,74; CTOXAO 5(2),151,72; IJMDAI 10(4),416,74; JAMAAP 116,562,41; CHREAY 28, 179,41; ADTEAS 5,51,72; PHREA7 23,305,43; FOREAE 7,313,42; KOTTAM 11(11),1300,75; 85CVA2 5,63,70; PEXTAR 12,102,69; BNYMAM 54,413,78; AMTODM 3,209,77. OSHA Standard: Air: TWA 200 ug(Se)/m³ (SCP-X) FEREAC 39,23540,74. "NIOSH Manual of Analytical Methods" VOL 1 124,181, VOL 3 S190. Reported in EPA TSCA Inventory, 1980.

THR: An exper ETA. HIGH ihl, ivn, unk. See also selenium compounds.

Disaster Hazard: When heated to decomp it emits tox fumes of Se; Can react violently with barium carbide, bromine pentafluoride, calcium carbide, chlorates, chlorine trifluoride, chromic oxide (CrO_3), fluorine, lithium carbide, lithium silicon (Li_4Si_2), nickel, nitric

acid, sodium, nitrogen trichloride, oxygen, potassium, potassium bromate, rubidium carbide, zinc, silver bromate, strontium carbide, thorium carbide, uranium. For further information see Vol. 1, No. 3 of *DPIM Report*.

SELENIUM (COLLOIDAL)

CAS RN: 7782492 NIOSH #: VS 8310000

TOXICITY DATA: 3 CODEN:
ivn-rat LDLo: 6 mg/kg JPETAB 33,270,28

Reported in EPA TSCA Inventory, 1980.

THR: HIGH ivn. See also selenium and selenium compounds.

Disaster Hazard: When heated to decomp it emits tox fumes of Se.

SELENIUM COMPOUNDS

THR: HIGH via ivn and inhal routes. An exper carc.

Selenium in small amounts is essential for normal growth of some animals. Deficiency or excess is associated with serious disease in livestock. Long-term exposure may be a cause of amyotrophic lateral sclerosis in hmns, just as it may cause "blind staggers" in cattle. Elemental selenium has low acute systemic toxicity, but dust or fumes can cause serious irr of the respiratory tract. Hydrogen selenide resembles other hydrides in being highly toxic, and selenium oxychloride is a vesicant. Some organoselenium compounds have the high toxicity of other organometals. Inorganic selenium compounds can cause dermatitis. Garlic odor of breath is a common symptom. Pallor, nervousness, depression and digestive disturbances have been reported in cases of chronic exposure. Selenium compounds are common air contaminants.

SELENIUM DIMETHYLDITHIOCARBAMATE

CAS RN: 144343 NIOSH #: VT 0780000
mf: $C_{12}H_{24}N_4S_8 \cdot Se$; mw: 559.84

Yellow powd, cryst; d: 1.58; M range: 140° - 172° .

SYNS:

METHYL SELENAC	TETRAKIS(DIMETHYL CARBAM- ODITHIOATO-S,S')SELENIUM
----------------	---

TOXICITY DATA: 3 CODEN:

Carcinogenic Determination: Indefinite IARC** 12, 161,76. **Toxicology Review:** 85CVA2 5,250,70. Reported in EPA TSCA Inventory, 1980.

THR: An exper \pm CARC. See also selenium compounds and carbamates.

Disaster Hazard: When heated to decomp it emits very tox fumes of Se, SO_2 and NO_2 .

SELENIUM (IV) DIOXIDE (1:2)

CAS RN: 7446084 NIOSH #: VS 8575000
mf: O_2Se ; mw: 110.96

White to slightly reddish, lustrous crystalline powder or

17-9

PREFACE

U.S. DEPARTMENT OF COMMERCE
L. A. HUGHES, Secretary

WEATHER BUREAU
F. W. REICHELDERFER, Chief

TECHNICAL PAPER NO. 40

RAINFALL FREQUENCY ATLAS OF THE UNITED STATES

for Durations from 30 Minutes to 24 Hours and
Return Periods from 1 to 100 Years

Prepared by
DAVID M. HENSHFIELD
Cooperative Studies Section, Hydrologic Services Division
for
Engineering Division, Soil Conservation Service
U.S. Department of Agriculture

THIS ATLAS IS OBSOLETE FOR THE FOLLOWING 11 WESTERN STATES: Arizona, California, Colorado, Idaho, Montana, Nevada, New Mexico, Oregon, Utah, Washington, and Wyoming.

NOAA ATLAS 2: PRECIPITATION-FREQUENCY ATLAS OF THE WESTERN UNITED STATES (GPO: 11 Vols., 1973) supersedes the Technical Paper 40 data for those states.

All but 3 of the 11 state volumes are out of print, and no reprint is presently planned.

Institutions in the eleven western states likely to have copies of these volumes for their state for public inspection are:

US Department of Agriculture Soil Conservation Service Offices
US Army Corps of Engineers Offices
Selected University Libraries
National Weather Service Offices (may also have volumes for adjacent states).
National Weather Service Forecast Offices (may have all eleven volumes)

Elsewhere, libraries of universities where hydrology and meteorology degree programs are offered may shelve some of the eleven volumes.

The three volumes in print as of 1 Jan 1983 at the GPO are:

Vol	State	GPO Stock Number	Price
IV	New Mexico	003-017-00158-0	\$10.00
VI	Utah	003-017-00160-1	12.00
VII	Nevada	003-017-00161-0	9.50

The GPO Order number is 702-781 3230 for VISA and MASTERCARD orders which

NOTICE
Rainfall-frequency information for durations of 1 hour and less for the Central and Eastern States has been superseded by NOAA Technical Memorandum NWS HYDRO-35 Five to Sixty-Minute Precipitation Frequency for the Eastern and Central United States. This publication (Accession No. PB 272-112/AS) is obtainable from:


National Technical Information Service
5285 Port Royal Road
Springfield, VA 22161




WASHINGTON, D.C.

May 1961

Reference 4





CME

Reference 5

TWC Reg. No. 31633TEXAS WATER COMMISSION
Comprehensive GW Monitoring Evaluation (CME) ReportINSPECTION COVER SHEETEPA ID No. TX D 0008377369

JUN 08 1987

C.O. Use Only

Date Entry Date

NAME OF COMPANY Houston Lighting and Power-WebsterSITE ADDRESS P.O. Box 1700, Houston, Texas Tel (713) 922-2186COUNTY Harris TYPE OF INDUSTRY Electric Power GenerationCurrent GW Monitoring Status: Detection Monitoring before closure(Specify for each Waste
Management Area "WMA")HL&P is no longer sampling wellsInspection Information:Inspector(s) Robert Hahn (TWC) Date(s) 4-24-87Participants Doug Chin (HL&P), Richard Bye (HL&P)Type of Inspection (check) EV CME X SA Evaluation:

	S	U
A. Monitoring System	<u>X</u>	<u> </u>
B. Sampling Procedures	<u>X</u>	<u> </u>
C. Analysis & Results	<u> </u>	<u> </u>
D. Records & Response	<u>X</u>	<u> </u>

Signed: Robert W. HahnInspector
Date: 5-27-87Signed: Mary L. AmbroseReviewer
Date: 6/5/87

PSL - 6/5/87

S= Satisfactory U= Unsatisfactory

Overall Evaluation: Compliant X NonCompliant

TWC Reg. No. 31633

TEXAS WATER COMMISSION
Comprehensive GW Monitoring Evaluation (CME) Report

CONTENTS SHEET

FACILITY NAME Houston Lighting and Power - Webster Generating Station

- X 1. Code Sheet (0814)
- 2. Interoffice Memorandum (IOM)
- X 3. Inspection Cover Sheet
- X 4. Technical Report, with supporting Attachments
 - X A. Monitoring System
 - X B. Sampling Procedures
 - * C. Analysis and Results
 - X D. Records and Response
- 5. EV Inspection Checklist (if joint inspection with District Office)
- 6. Notice of Violation (NOV) / Enforcement Letter to Facility
- 7. Other (describe) _____

* If a required Checklist is omitted, Explain: _____

* Section will be submitted when results of sample analysis are completed.

COMPREHENSIVE MONITORING EVALUATION
SUMMARY

The Comprehensive Monitoring Evaluation was conducted at the Houston Lighting and Power Webster Generating Plant on April 24, 1987.

Findings:

The locations of monitor wells installed at the Webster Plant were approved on July 22, 1982 by the Texas Department of Water Resources. The following findings represent deficiencies in the ground-water monitoring program which is no longer in operation due to certified closures of the surface impoundments under an approved closure plan.

1. Background ground-water quality was not properly defined. The upgradient well, MW1, is influenced by water quality from the saline Discharge Canal.
2. All monitor wells appear to have been improperly surveyed or reported incorrectly. Elevations of screened intervals and total depths reported with respect to Mean Sea Level do not take into consideration stick up lengths or ground surface elevations.
3. Total well depth measurements have not been performed to confirm discrepancies noted in various reports.
4. Total Organic Carbon and phenols have not been preserved with acid in the field.

Because of the following: (1) the locations of the monitor wells were approved by the TWC (then the TDWR), (2) the surface impoundments have been certified clean closed and soil and water samples have not confirmed any release, no further action required by the company is warranted. The company should be requested to resolve the discrepancies noted concerning monitor well elevations, total depths, and screened interval elevations for the Central Records files and before approval of the Affidavit of Exclusion.

TECHNICAL REVIEW
Comprehensive Ground Water Monitoring Evaluation

I. Introduction

A. Company - Houston Lighting and Power Company
Webster Generating Station

1. Process description: Electrical power generation.
2. Plant site has been in operation since: May 1965.

B. Physiography and Climate

1. Site Topography - Attachment A (indicate site location directly on map or reproduction)

Slope <1% to the south.

2. Average Annual:

- a. Rainfall - 48 inches
- b. Temperature - 69 °F
- c. Evaporation - 50 inches

3. Was an annual water balance budget submitted by the company (yes/no)? NO.

4. Surficial Soils Map - Attachment B

- a. Soil type - Midland silty clay loam.
- b. Soil properties, including permeability, texture, etc. -

The surface impoundments are constructed on Midland Series silty clay loam soils. This soil series consists of multicolored clays which are slightly to strongly acidic, very hard, sticky and plastic. The soil is characterized as having a high to very high shrink swell capacity, high available water capacity, low permeability, poor drainage, and contains some non-intersecting slickensides, few iron, manganese and some calcium carbonate concretions below a depth of 30 inches. Attachment B also presents a table of the soil properties.

5. Proximity to surface water bodies and other recharge/discharge features: The site is adjacent to Clear Creek and 1 mile east of Clear Lake. Two plant water wells screened at 460 and 640 ft. depths exist on-site for use as process water. A cooling water discharge canal which influences water quality in Monitor well MW-1, is located north of MW-1. The distance as indicated on a map is approximately 130 ft. away from MW-1; however, the actual

distance is less than 100 ft. A small ditch full of water is located approximately 15 ft. between MW-1 and the discharge canal. The bank of the discharge canal is approximately 10 ft. higher in elevation in comparison to the ground elevation at MW-1.

6. Proximity to water supply wells:

A survey of water wells located within a 2.5 mile radius of the plant revealed the presence of 152 water wells which included 60 domestic wells, 26 public or municipal wells, 25 wells without documentation, 19 wells no longer in use, 13 industrial wells, 3 water level observation wells, 1 livestock well and 1 service station well. The wells range in depth from 84 to 700 feet deep and are either completed in the Beaumont Aquifer (Upper Chicot) or Evangeline Aquifer (Lower Chicot). Two plant water wells having screen depths of 460 and 640 feet are located within the property boundaries.

C. Waste Management Units:

1. Indicate units on Site Diagram (Attachment C)
2. Indicate waste management area (WMA) boundaries on Site Diagram (Attachment C)
3. Waste management units (complete this section for each waste management unit):

Unit name	- <u>Demineralizer Regenerant boiler blowdown surface impoundment</u>	<u>Inorganic Metal Cleaning Surface Impoundment</u>
Size	- 5'x200'x130' (.794 acres)	4.25'x200'x135'
Year in service-	1970	1977
Status*	- Closed	Closed
Construction	- 3 ft.compacted clay liner	3 ft. compacted clay liner
Type of waste	- Boiler water	Spent acids from metal cleaning operations.
Total volume of waste received	- Not available.	Not available.

* active, closed, inactive, regulated unit, nonhazardous

Comments:

Both surface impoundments have been certified closed and Affidavits of Exclusion from Hazardous Waste Permitting have been submitted and are currently being processed by the TWC Hazardous and Solid Waste Reports and Management Section. At the time of the CME, the surface impoundments were observed to be full of liquid. HL&P stated that the Demineralizer surface impoundment contained boiler blowdown water also. A third impoundment, known as the Organic Acid Waste pond which is not subject to permit requirements is still in use for storing ammoniated citric acid.

This impoundment is shown on Attachment C as SI-3.

4. If a unit is closing or closed, complete the closure checklist and include as Attachment D.

II. Technical Review

A. Hydrogeology

1. Regional Geology (Houston Sheet, Geologic Atlas of Texas)

a. Physiographic province: Gulf Coastal Plain

b. Formation(s): Beaumont Formation.

- 1) lithology - fluvial-deltaic clays and silts.
- 2) regional dip and gradient - <2 ft/mile for the Beaumont.
towards the Gulf of Mexico.

c. Usable quality (<10,000 TDS) ground water

- 1) depth to top/bottom - Top: 84 ft. reported for a domestic well drilled in 1971 for domestic use. Bottom: 2900;
- 2) reference - Baker (1979, TDWR 236).

d. Regional ground water flow:

- 1) direction - toward the Gulf although in the vicinity of the Webster Plant, the direction is toward the northwest as a result of the pumping of large quantities of groundwater in the Houston District.
- 2) reference - Baker (1979, TDWR 236).

e. Is the site located on the recharge area of a major/minor named aquifer (yes/no)? NO.

f. Part B Permit Application, Geology Report, pages: Section 8.

g. If a Part B Application was submitted, does it request a waiver from ground-water monitoring (yes/no)? NO. waiver rejected 3-82

Comments: The site is located on intertributary areas of fluvial dominated deltaic plains. The sediments are clay dominated and represent overbank flooding deposition. Subsidence in the Webster plant area has been reported at 7 feet since 1906.

2. Site Hydrology

a. Site Diagram - Attachment E (include locations of waste management area(s), borings, wells, lines of cross-sections)

b. Depth to water - 6 to 14 feet below ground surface level.
As determined by - water level measurements in monitor wells.

- c. Site stratigraphy to depth of investigation -1000 ft. (complete this section for each encountered unit)

Stratigraphy as determined from plant borings (Surface to 80 ft.). Attachment F presents electric log interpretations for the 2 on-site plant water wells to a depth of 1000 ft.

Unit	-	Clay
Depth encountered	-	Surface to 30 ft.
Description	-	<u>Surface to 5 ft:</u> Soft to very stiff dark brown clay often varying to yellowish brown or reddish brown in color below a depth of 1 foot, observed to contain calcareous and ferrous nodules, roots, gravel, shells, and occasional sand or silt lenses in the upper 5 feet. It is not considered a separate unit.
		<u>5 to approx. 20 ft:</u> Multicolored clay varying from brown, tan, reddish brown, light gray, observed to consist of calcareous and ferrous nodules and generally skickensided within the 8 to 13 ft. interval.
		<u>18 to 23 ft:</u> Reddish brown clayey to sandy silt varying from 1 to 4 ft. in thickness. Observed to contain sand pockets.
		<u>23 to 30 ft:</u> Stiff brown to tan clay.
Thickness	-	30 ft.
Saturated thickness	-	approximately 20 feet.
Confined/unconfined	-	Water table; presence of water thought to be due to seepage from the cooling water discharge canal.
Potentiometric rise	-	N/A

Comments: Below a depth of 30 feet, the stratigraphy directly beneath the surface impoundments has not been defined. However, plant borings approximately 1000 feet away possibly project a 15 foot tan colored sand at a depth of 40 feet beneath the impoundments. The sand appears to have a geometry similar to a crevasse splay deposit (Assessment Report, 5-29-84). From a depth of 60 to 80 feet, plant boring CB-1 revealed a 15 foot thick red and gray silty clay overlying a gray and tan sandy clay. At this same depth interval, CB-11 encountered a "calcium shell marl." No data is available for the 80 to 100 ft. interval.

Plant water well electric logs reveal a 20 ft. sand at a depth of 100 ft. followed by an interbedded sequence of sand and clay to a depth of 250 ft. From 250 ft. to approximately 450 ft depth, the sediments appear to be predominantly clay rich. A 120 ft. sand, which is screened in Plant water well #2, is present at a depth of 500 feet. The base of this thick sand represents the base of the Chicot Aquifer. Approximately 300

ft. of intertributary clayey sediments isolates this sand from another 100 ft. thick sand located at a depth of 900 ft. This sand is considered part of the Evangeline Aquifer.

- d. Hydraulic conductivity to depth of investigation - (complete this section for each encountered unit)

Unit	- Clay, 3 ft.	Clay, 7 ft.	Sandy Silt
			22-27 ft. 23-28 ft.
Hydraulic conductivity	- $1.2-6.3 \times 10^{-9}$ c/s	$1.4-1.0 \times 10^{-9}$ c/s	1.02×10^{-3} c/s
Type of test	- Falling head-lab	Falling head-lab	Slug test
Number of tests	- 2	2	2
Range of values	- As shown	As shown	1.5×10^{-4} to 2.7×10^{-3} cm/s.

- e. Cross-sections - Attachment G

- f. Is first water-bearing zone identified in c. above in communication with deeper zone(s) (yes/no)? It has not been determined.
- g. Is the aquitard(s) continuous beneath the site (yes/no)? Uncertain from available data. Clayey sediments vary from sandy to silty clay beneath the site.
- h. If yes for f. and g. above, calculate rate of downward vertical migration from upper aquifer to lower on Attachment and list results here:

Rate - Can not be determined.
 Aquitard thickness -
 Migration time -

Comments:

3. Site Ground Water Movement

- a. Potentiometric Surface Map(s) - Attachment H (indicate inferred flow directions directly on map. Include several maps to show range of observed water level measurements.)
- b. Calculate minimum and maximum observed gradients (i) in units of feet/foot. Show on Attachment H (above) and list here:
- i_{\min} - 0.001 ft/ft.
 i_{\max} - 0.022 ft/ft.
- c. Calculations of average linear velocity (v) for gradients reported above, showing all assumptions, Attachment I

v_{\min} - 0.44 ft/year using $i=0.001$, $K=1.5 \times 10^{-4}$ cm/s

v_{\max} - 176 ft/yr. using $i=0.022$, $K=2.7 \times 10^{-3}$ cm/s

Comments:

Included in the Part B, the Ground-water quality assessment report determined a velocity of 6 ft/year using a gradient of 0.0017, $K_{\text{ave}}=1.02 \times 10^{-3}$ cm/s and porosity = 30 %. This value is within an expected range for velocities reported in the Beaumont Clay (5-20 ft/yr.). The min and max values for the gradient (i) were determined from two separate 3 point problems involving different sets of 3 out of the 4 monitor wells. The maximum velocity determined in this CME using a $K=2.7 \times 10^{-3}$ cm/s appears to be high for the Beaumont Clay. Using a maximum gradient of 0.022 and $K=1.5 \times 10^{-4}$, a velocity of 9.75 ft/yr is calculated which also falls within an expected range. Using a 3 point problem, gradients of 0.022 and 0.021 were obtained from water level measurements collected on 4-24-87 (CME) and 4-19-85, respectively. The limited number of data points (4) and the possible mounding around the surface impoundments do not allow for a more precise velocity calculation to be performed. In addition, water levels determined on 12-14-83 showed the water elevation in the canal at 12.82 ft. and in MW-1 at 10.53 which indicates that the canal is probably a recharge feature. As shown on the water elevation maps, wide contour intervals which represent a flatter gradient are located between the canal and MW-1, -2, and -4. This flat gradient area may be due to a recharge mound located around the discharge canal. A steeper gradient is indicated toward MW-3 and another canal. The second canal known as the intake canal may represent a discharge feature. The TWC Cross-Section (Attachment G) shows the water table sloping toward MW3 and the intake canal. No water level measurements or chemical characteristics are available for the intake canal.

5. Monitor Well Construction

- a. Well Construction Diagrams - Attachment J
- b. Table of Well Construction Details - Attachment K
- c. Do monitor well installation and development techniques and materials of construction satisfy the requirements of 31 TAC 335.112(a)(5)/40 CFR 265.91(c) (yes/no)? NO . If no, explain in comments.

Comments:

Monitor wells at the Webster Plant have been either incorrectly surveyed and/or total well depths have been improperly reported. Several discrepancies have been found in the various reports incorporated into the Part B. The following table lists data presented in the reports as well as field data

collected during the CME. As shown, total depths from the three sources of data do not agree. Based on the general lithological descriptions and the positions of the screens, the Assessment Report dated 5-29-84 may be the most valid. Wells were resurveyed from the top of casing as part of the Assessment Plan dated October 1983. No ground level elevations or stick up lengths were reported.

Substantial Siltation: As shown in the table below, an expected decrease in total well depth which would indicate siltation of the well is not indicated when measurements taken during the CME are compared to the 5-29-84 reported data. The reference point used to determine the T.D. in the 7-22-82 data is not clear; however, the well construction diagram presented as Attachment shows the reference point as the ground surface level. The increase noted in total depth measurements may be due to: (1) incorrect measurements with respect to top of casing in the Part B reports; (2) collapse of the well. The wells were likely drilled to a depth of 30 feet as indicated from the lithological descriptions.

A high degree of siltation in the wells is indicated from the appearance of purged water from the wells. Initial bailer volumes of the purged water were clear. Siltation and turbidity seemed to increase with continued purging until only a very small volume of water was able to be evacuated from the wells. After waiting approximately 10 minutes, purging of the well was resumed. Clear water was noted again in the first bailer volume. It might be envisioned that the clear water noted might represent water recharging into the well from the very top of the well screen at a slow enough rate that the incoming water did not disturb the silt buildup in the well. Following removal of the first bailfull, the silt in the well was disturbed. The selection of a 0.020 inch slot size may not have been appropriate for the clayey sediments.

TOTAL DEPTH OF WELL (T.D.) TOC=Top of Casing GSL= Ground Surface Level

	<u>CME T.D.</u> from TOC	<u>Assessment Rpt</u> 5-29-84 (TOC)	<u>Installation Rpt</u> 7-22-82 (GSL ?)	<u>Lithology</u> 7-22-82
MW-1	23.49 ft	21	28	0 - 25 ft, clay 25- 29 ft, silty clay with sandy silt
MW-2	31.84 ft	28	29	0 - 12 ft, clay fill 12- 24 ft, clay 24- 27 ft, with silt seams 27- 30 ft, clay
MW-3	N.T.	29	28	0 - 21 ft, clay 21- 22 ft, interbedded with silt
MW-4	N.T.	28	21	0-17.5 ft, clay 17.5-19.5, sandy silt 19.5-30ft, clay

7. Monitor Well Placement

a. Upgradient/background monitor well(s)

- 1) Confirmed as upgradient [31 TAC 335.112(a)(5)/40 CFR 265.91(a)(1)] (yes/no)? NO, see comments.
- 2) Adequate to yield samples that are representative of background water quality [31 TAC 335.112(a)(5)/40 CFR 265.91(a)(1)(i)] (yes/no)? NO, see comments.
- 3) Unaffected by the WMA [31 TAC 335.112(a)(5)/40 CFR 265.91(a)(1)(ii)] (yes/no)? YES, see comments. Indicate distance(s) of upgradient well(s) from the WMA: 500 ft.

Comments: The upgradient well MW-1 is not influenced by the WMA (i.e., surface impoundments). However, MW-1 is strongly influenced in water quality by the discharge canal. A comparison of conductivity data collected on 12-14-83 is shown below:

<u>Sample</u>	<u>Conductivity umhos/cm</u>
MW-1	12,000
Canal	14,000
MW-2	1,600
MW-3	3,200
MW-4	3,000

b. Downgradient/perimeter monitor wells

- 1) Confirmed as downgradient and provide for immediate detection of hazardous waste or hazardous waste constituents that migrate from the WMA [31 TAC 335.112(a)(5)/40 CFR 265.91(a)(2)] (yes/no)? NO . If no, explain in comments. Indicate on Site Diagram, Attachment E above, lateral spacing of downgradient wells.
- 2) Describe operator's justification for lateral spacing: HL&P states that they have complied with TAC 335.112 by installing a background well and 3 down gradient wells. Only 4 wells were installed because the surface impoundments are in close proximity to each other.
- 3) Is the lateral spacing sufficient to satisfy the performance standard of 31 TAC 335.112(a)(5)/40 CFR 265.91(a)(2) (yes/no)? YES.

- 4) Indicate on Site Diagram, Attachment E, and tabulate below the distances of downgradient wells from the edge of the WMA in the direction of ground-water flow:

Well	MW-2	MW-3	MW-4	
Distance	50 ft.	100 ft.	150 ft.	
Velocity	6 ft/yr	6 ft/yr	6 ft/yr	-assumption using
Time	8.3	16.7	25	HL&P data

Calculate ground-water travel time based on the average linear flow velocity, v (calculated in II.A.4. above). Assuming conservative transport, indicate with (*) those wells that will not detect contaminants during the active life or post-closure care period of the WMA.

Comments:

Monitor wells MW-2 and MW-4 appear to be lateral to ground water flow. Limited number of data (4 wells) do not allow for a more defensible determination of ground-water flow directions. The downgradient wells appear to be located too far from the WMA's. According to the time calculations above, and assuming operation of the units began in 1977, any impact upon the groundwater would not be noticeable until after the Affidavit of Exclusion is granted.

- c. Vertical placement - Indicate on cross-sections (Attachment G) the screened and gravel-packed intervals of wells and tabulate below:

Well	Screen Length	Gravel Pack Interval	Aquifer Thickness	S/U*
MW-1	5 ft	10-21 ft.	2 ft.	S
MW-2	5 ft	18-28 ft.	2 ft.	S
MW-3	5 ft	18-29 ft.	3 ft.	S
MW-4	5 ft	18-29 ft.	4 ft.	S

*Explain in comments why vertical placement is unsatisfactory [31 TAC 335.112(a)(5)/40 CFR 265.91(c)]

Comments: The length of screen and gravel pack may be satisfactory for the selected monitored interval. However, it appears from plant borings located over 1000 feet away from the surface impoundments that a more appropriate zone for monitoring may be, if present, a 15 foot sand or clayey sand located at a probable depth of 40 ft. below the ground surface.

B. Sampling Procedures

Since HL&P is no longer sampling the monitor wells on a regular basis, facility sampling was not able to be observed. Instead, procedures used by the company during sampling were reviewed during a phone interview with Doug Chin, HL&P.

1. Facility Sampling Plan

a. Is a Sampling Plan [31 TAC 335.112(a)(5)/40 CFR 265.92(a)] maintained at the facility (yes/no)? YES. Include a copy as Attachment L

b. Does the plan address the following items (yes/no)?

- 1) sample collection procedures - Yes
- 2) sample preservation and shipment - Yes
- 3) analytical procedures - Yes
- 4) chain of custody procedures - Yes

c. List deficiencies/omissions/recommended changes:

Labels should contain mode of preservation; the Plan should specify measurements of temperature and specific conductivity to be conducted in the field; the decontamination procedure for bailers is inadequate; the Plan should specify preserving TOC and phenols with acid following sample collection; the Plan should specify the periodic determination of total well depth; the Plan should specify the collection of field blanks or equipment blanks if dedicated bailers are not used for each well.

d. Does the facility follow the plan during sampling events (yes/no)? NO. If not, describe inconsistencies between the plan and observed sampling procedures:

The types of bottles used are different than as specified in the Plan; the Plan specifies field filtering prior to preserving metal samples; the COC form specified in the plan is not used; the Plan specifies a preference to use dedicated bailers.

2. Are wells equipped with (yes/no):

- a. Caps - Yes
- b. Lockable caps - No, screw on caps.
- c. Annular seals - Yes (to prevent contamination from surface sources)

Comments: The Plant is surrounded by a fence with controlled access.

3. Describe water level and total well depth measurement equipment and techniques: Total depth measurements have not been performed since the 5-29-84 determination. Water level elevations are performed on each well prior to purging using a rope with weight attached and graduated every 2 feet. The weight is used to "sound" the water level. A ruler graduated in 0.10 ft. increments is used to refine the measurement.

4. Well evacuation

- a. Describe well evacuation equipment and techniques: A PVC bailer is used to evacuate the well. Three casing volumes are purged from the well. The total depth of well used in the calculations is obtained from data in the 1984 Assessment Report.
- b. Describe collection and disposal methods of bailed water: .
Is the observed disposal method appropriate (yes/no)? YES.
The purged water is emptied into a larger bucket which is then emptied at some distance away from the well.
- c. If the same equipment is used to evacuate each well, describe decontamination procedures: YES, distilled water is used to rinse the bailer.

5. Sample collection

- a. Describe the sample collection equipment and techniques:
A PVC bailer is used to sample the well. Sample containers are filled directly from the bailer.
- b. If the same equipment is used to sample each well, describe decontamination procedures: Distilled water is used to rinse the bailer.
- c. Indicate the order in which samples are taken:
 - 1) Non Preserved samples
 - 2) preserved samples

6. Field analytical procedures

- a. Complete the following table for each field analysis;

Parameter	Elapsed time*	Instrument	Field/ On-site lab
pH	?	Orion Model 611	Well Head
Conductivity	?	Lee & Northrop # 486	On-site lab

*between sample extraction and parameter analysis

- b. Describe field filtration equipment and techniques: None.
- c. Parameters filtered: None, samples are filtered in the contract lab.

7. Complete the following table for the facility's sampling program:

Container	Preservative	Parameters	S/U*
1 liter glass	ice	Ground water quality	S
1 liter glass	ice, nitric	Metals	S

*Explain in comments why the program is unsatisfactory

Comments: Table 7 is applicable for samples collected 4-24-87 during the CME.

8. Is the observed sampling methodology adequate for (NA/yes/no):

- a. Indicator parameters - No, TOC and phenols should be preserved. Conductivity should be measured at the well head.
- b. Quality parameters - Yes
- c. Drinking water parameters - Yes
- d. Metals - Yes, however, the company should have considered field filtering due to the very silty nature of the water.
- e. Volatile organics - N/A
- f. Floating immiscible organics - N/A
- g. Dense immiscible organics - N/A

9. Describe Quality Assurance/Quality Control (QA/QC) procedures used in the facility's sampling program:

- a. QA/QC at on-site lab - Equipment is not standardized on a frequent basis.
- b. Field calibration of instruments - Only occasional calibration is performed.
- c. Duplicate and/or spiked samples and blanks - None.
- d. (Other)

10. Chain of Custody (C.O.C.) procedures:

- a. Describe C.O.C. and shipping procedures: Label is equivalent to the COC tag. Sampler hand carries samples to the contract lab (Analytical Petroleum Research, APR, Dickinson, Texas). The samples are packed in ice.
 - 1) Example of C.O.C. Form or Tag - Attachment Not Available.
 - 2) Example of Sample Identification Tag or Label - Attachment Not available. L-2
 - 3) (Other)
- b. Do the C.O.C. and shipping procedures minimize the possibility of tampering with the samples (yes/no)? Yes

11. TWC co-sampling of monitor wells - complete the following if monitor wells are co-sampled with the facility operator:

a. Person(s) who collected samples for:

Facility - Doug Chin

TWC - Robert Hahn


b. Number of wells co-sampled - 2
Total number of RCRA wells - 4

c. TWC Sample Schedule - Attachment M

d. TWC Field Notes - Attachment N

III. Response

A. List, in chronological order, activities, events and correspondence relating to groundwater monitoring in Attachment O.




QUAD:
LEAGUE CITY, TEX.
N2930-W9500:7.5

1982

DMA 6043 II SE SERIES VASE

Attachment A-1
Site Topography



TEXAS WATER COMMISSION
District No.


ATTACHMENT A-2

SITE TOPOGRAPHY from
Part B Application

Soil name and map symbol	Soil texture	Unified	SAND TO	Percentage passing sieve number			Liquid limit	Plasticity index
				4	10	40		
Midland:	Silty clay loam	CL		100	100	100	20-25	10-20
Midland:	Silty clay	CH		100	100	100	20-25	10-20
Midland:	Sandy silty clay loam	SC		100	100	100	20-25	10-20


PHYSICAL AND CHEMICAL PROPERTIES OF SOILS

Soil name and map symbol	Depth	Permeability	Available water capacity	Soil reaction	Shrink-swell potential	Risk of corrosion		Erosion factors	
						Uncoated steel	Concrete	K	T
Midland:	A1	In. in	In. in	PH					
Midland:	0-7	0.06-0.2	0.20-0.22	5.1-6.5	Moderate	High	Moderate	0.37	5
Midland:	7-72	<0.06	0.18-0.20	5.6-8.4	High	High	Low	0.32	



TEXAS WATER COMMISSION
District No.

ATTACHMENT B
SURFICIAL SURFACE SOILS MAP



TWC Solid Waste Inspection Report


TWC Reg. No. 31633CLOSURE-in-PROGRESS CHECKLIST

Reg. Facility No. _____

Type of facility component: Surface Impoundments(2)


1. Is the facility component being closed a RCRA unit? YES ☒ NO ☐
2. Type of closure: Full-Facility Closure ☒ Partial Closure ☐ ***
3. Has closure plan received TWC approval or final modification? N/A ☐ YES ☒ NO ☐
Date of approval: August 6, 1985
Sept. 25, 1986
4. Is this the last on-site facility to be closed which requires RCRA groundwater monitoring? N/A ☐ YES ☒ NO ☐
5. Has an approved public notice of closure been published? N/A ☐ YES ☒ NO ☐
Date published: April 3, 1985
6. Is a public hearing required? YES ☐ NO ☒
Date of hearing: N/A
7. Has on-site closure work started? YES ☒ NO ☐
Date work initiated: June 17, 1986 (Demin)
Sept. 19, 1985 (Inorg)
8. Is closure work proceeding according to the work schedule in the approved closure plan? N/A ☐ YES ☒ NO ☐
9. Have 180 days elapsed since TWC approval of the closure plan? N/A ☐ YES ☐ NO ☒
- a. If Yes,
Has TWC approved an extension period? N/A ☐ YES ☐ NO ☐
10. Was District Office notified of sampling event when complete removal (clean closure) of a Land Disposal facility was to have been accomplished? N/A ☐ YES ☒ NO ☐
11. Were TWC samples taken to verify completion of closure? YES ☒ NO ☐
- NOTE: List chain-of-custody sample tag numbers in comments.
TWC was available SW 12329, 12328
12-23-86
12. Is the closure work completed? YES ☒ NO ☐
Date of completion: Nov. 1985
July 1, 1986
13. Has the closure certification been submitted to TWC? N/A ☐ YES ☒ NO ☐
Attach copy or explain. Date of certification: September 2, 1986
Demin.
Inorganic - Nov. 1985.


*** An entry in this column indicates explanation/response is needed.



ATTACHMENT E


SITE DIAGRAM. LOCATION
OF WELLS, BORINGS AND
CROSS SECTIONS.






ATTACHMENT G

CROSS-SECTION SHOWING
MONITOR WELLS, BORINGS
LOCATIONS OF SURFACE
IMPOUNDMENTS AND CANAL



ATTACHMENT H
POTENTIOMETRIC SURFACE
MAP.



Calculations of Average Linear Velocity

Assumptions Let $K = 1.5 \times 10^{-4} \text{ cm/s}$ slug test in MW-2
 $\phi = 35\%$ porosity, from assumptions made in HL&P Part B for Gulf Coast clayey sediments

For $i = 0.001 \text{ ft/ft}$

Fudge Factor

$$v = \frac{K i}{\phi} = \frac{1.5 \times 10^{-4} \text{ cm/s} \cdot 0.001 \text{ ft/ft}}{.35} \times 1.0348 \times 10^6 \frac{\text{ft/yr}}{\text{cm/s}}$$

$$v = 0.44 \text{ ft/yr}$$

For $i = 0.022 \text{ ft/ft}$

$$v = 9.75 \text{ ft/yr}$$

Assumptions Let $K = 2.7 \times 10^{-3} \text{ cm/s}$ slug test in MW-3
 $\phi = 35\%$ porosity

For $i = 0.001 \text{ ft/ft}$

$$v = 7.98 \text{ ft/yr}$$

For $i = 0.022 \text{ ft/ft}$

$$v = 175.6 \text{ ft/yr}$$

TEXAS WATER COMMISSION
 District No.

ATTACHMENT I CALCULATIONS OF
 LINEAR VELOCITY




TABLE 7

Monitor Well Data
Webster Generating Station

<u>Measurement</u>	<u>Monitor Well No. 1</u>	<u>Monitor Well No. 2</u>	<u>Monitor Well No. 3</u>	<u>Monitor Well No. 4</u>
Location (Local Flow)	Updip	Downdip	Downdip	Downdip
Top of Casing Elevation (ft. MSL)	19.48	21.11	21.94	21.43
Total Depth (ft.)	21	28	29	28
Total Depth (ft. MSL)	-1.52	-6.89	-7.06	-6.57
Screened Interval (ft. below ground level)	15 - 20	22 - 27	23 - 28	22 - 27
Screened Interval (ft. MSL)	4.48--0.52	-0.89--5.89	-1.06--6.06	-0.57--5.57
Static Water Level (12/17/83) (ft. below casing point)	8.95	10.84	16.34	11.92
Static Water Level (12/17/83) (ft. MSL)	10.53	10.27	5.6	9.51
Associated Surface Impoundments*	Discharge Channel	SI-2	SI-1	SI-1, SI-2, and SI-3
Surface Impoundment Water Levels (12/14/83) (ft. MSL)	12.82	11.19	10.02	10.02/11.29/10.41

*See Figure 13 for Surface Impoundment Location

These may not be correct.

File IIIA

TWC Reg. No. 31653TEXAS WATER COMMISSION
Solid Waste Compliance Monitoring Inspection Report

C.O. Use Only

INSPECTION COVER SHEET

JAN 05 1987

01-87

LLS

TWC Dist. 7EPA ID No. TXD000371COMMERCIAL WASTE Facility GOVT. Facility NAME OF COMPANY Houston Lighting & Power Webster StationMAILING ADDRESS P.O. Box 1700 Houston 77001 Tel. (713) 922-2217SITE LOCATION 19301 Old Galveston Rd Tel. COUNTY Harris TYPE OF INDUSTRY electrical generating stationGENERATOR CLASSIFICATION: Industrial ☒ Municipal

Part A Application submitted to the State? Yes ☒ No To EPA? Yes ☒ No
 Affidavit of Exclusion submitted to the State? Yes ☒ No
 Was a written exclusion granted by TWC? Yes No ☒ If yes, Date
 Will this facility require a RCRA permit? Yes No ☒

CURRENT WASTE MANAGEMENT (Haz.-"H", Class I NonHaz.-"NH", Class II-"II", Class III-"III")

Generator H, NH, II Treatment Storage Disposal Transporter HW Exemptions: 90-Day Storage ☒ Other WWTSQG : Total HW Generation Per Month: <100 kg. 100-1000 kg.

H W Facilities (circle appropriate codes): (C) T (SI) WP LT LF I TT TR WDW O

N H Facilities (circle appropriate codes): (C) T (SI) WP LT LF I TT TR WDW O

Anomalies in the above information will be addressed by: (a) Enforcement in progress ,
 (b) Central Office , (c) District Office ☒, (d) Owner/Operator .

Type of Inspection (circle): EV ER EC CL GW (SA) CD FO OT FE SQ SW

Inspector's Name and Title Paula Thetford, Hazardous & Solid Waste SpecialistInspection Participants Barbara Dery - HLC/PDate(s) of Inspection 7-1-86

Approved: Andrew A. Parker for Signed: Paula R. Thetford 10-21-86
 District Manager Tent/Kearns Inspector Date

TEXAS WATER COMMISSION
Solid Waste Inspection Report
CONTENTS SHEET

TWC Reg. No. _____

COMPANY NAME Waste Management, Inc. - Houston

- ☒ 1. Code Sheet (0814)
- ☒ 2. Inspection Cover Sheet _____ 2b. Special Insp. Cover Sheet (HB.2358)
- _____ 3. Generators Checklist _____ 3b. Small Quantity Gen. Checklist
- _____ 4. General Facilities Checklist
- _____ 5. Transporters Checklist
- *6. Component Facility Checklists
- _____ A. Containers (C)
 - _____ B. Tanks (T)
 - _____ C. Surface Impoundments (SI)
 - _____ D. Waste Piles (WP)
 - _____ E. Land Treatment (LT)
 - _____ F. Landfills (LF)
 - _____ G. Incinerators (I)
 - _____ H. Thermal Treatment (TT)
 - _____ I. Chemical, Physical, or Biological Treatment (TR)
 - _____ J. Other (O)

- _____ 7. Closure/Post-Closure Checklist _____ 7b. Closure-In-Progress Checklist
- _____ 8. Groundwater Monitoring Checklist Group
- _____ 9. Notice of Violation (NOV) Letter
- _____ 10. Interoffice Memorandum (IOM)
- _____ 11. Registration
- _____ 12. Maps, Plans, Sketches
- _____ 13. Photographs/Slides

- ☒ 14. Other (describe) sample results from closure of
surface impoundment
- * If a required Checklist is omitted, explain: Closure-In-Progress Checklist
has been previously submitted.

Texas Water Commission

INTEROFFICE MEMORANDUM

TO : Russ Kimble, Chief, Reports and Management Section, Hazardous and Solid Waste Division
THRU *cc* Luis Campos, Hazardous & Solid Waste Coordinator, Field Operations Division
FROM : Paula Thetford, Hazardous and Solid Waste Specialist, Deer Park Office
SUBJECT: Houston Lighting & Power - Webster Station
ISW Reg. No. 31633

On July 1, 1986, a closure inspection was conducted at a surface impoundment at HL&P - Webster Station. Two composite samples were taken; the results of which are tabulated below:

SW 12329: pH=7.0

EP-tox metals (ug/l)	
Arsenic	11.5
Barium	326
Cadmium	18
Chromium	<8
Lead	<10
Mercury	0.2
Selenium	20.1
Silver	2

SW 12328: pH=7.6

EP-tox metals (ug/l)	
Arsenic	5.4
Barium	390
Cadmium	10
Chromium	16
Lead	12
Mercury	<0.2
Selenium	22.4
Silver	6

This information is provided for file data.

Signed: *Paula R. Thetford*

Approved: *Russ Kimble*

TK/PRT/amh

NO. SW 12329
 Site Name HL of P Webster Station
 Site Location 19301 Old Galveston Rd
Webster 77001
 County Harris Basin 1101
 Method of Collection The 3-part composite was ~~not~~ taken
using a clean metal scoop to place the sample
in an untreated glass jar w/a teflon liner

District 7Org. No. 331Work No. 9091Lab TRA

Point of Collection Demineralizer Regenerant /
Boiler Blowdown Surface Impound-
ment - clay liner 18" beneath surface

Type facility: ☐ Drum; ☐ Tank; ☒ Impoundment; ☐ Landfill
☐ Waste pile; ☐ Landfarm; ☐ Other

Time Collected 11:30 (0 pm) Date Shipped

Add. COC #

ODOR: ☐ Yes; ☒ No; Describe

S.W. Registration				Permit Number				Page No.				Date				Collector's Signature							
1				9 10				18 19 20 21				22 23 24 25 26 27 28 29				Paula R. [Signature]							
31633				N/A				3070186				E											
30 Code				35 Parameter Value				44 Code				49 Parameter Value				58 Code				63 Parameter Value			
																ID OPEN							

NO. SW 12329
 District 7 Org. No. 331 Work No. 9091 Lab TRA
 Material Sampled: ☐ Solid waste (W); ☐ Liquid waste (L); ☒ Soil (E); ☐ Well (M);
☐ Stream (S); ☐ Other (O)
 Comments The sample was taken 18" beneath the surface
is a 3-part composite

(continued on back)

Lab Only	Date	rec'd: <u>7-3-86</u>	86-3818-02 (Lab No)
		cr. dt: <u>5-28-86</u>	
Analyst sign: <u>[Signature]</u>		Preservation: <input type="checkbox"/> None; <input type="checkbox"/> Ice; <input checked="" type="checkbox"/> H ₂ SO ₄ ; <input type="checkbox"/> HNO ₃	
Auxiliary Tags		Other	
<input checked="" type="checkbox"/> LEACHATE		<input checked="" type="checkbox"/> EP Toxicity Series; TDWR	

30 Code				35 Parameter Value				44 Code				49 Parameter Value				58 Code				63 Parameter Value				71			
pH				7.0				EP-tox series																			
0 0 4 0 3																											
COD								ARSENIC EP TOX ug/L				LEAD EP TOX ug/L															
0 0 3 4 0								0 1 0 0 2				1 1 . 5				0 1 0 5 1				< 1 C							
TOC								BARIUM EP TOX ug/L				MERCURY EP TOX ug/L															
0 0 6 8 0								0 1 0 0 7				3 2 6 7 1 9 0 0								0 . 2							
GC/MS								CADMIUM EP TOX ug/L				SELENIUM EP TOX ug/L															
								0 1 0 2 7				1 8				0 1 1 4 7				2 0 . 1							
								CHROMIUM EP TOX ug/L				SILVER EP TOX ug/L															
								0 1 0 3 4				< 8				0 1 0 7 7				2							

District 7

Org. No. 331

Work No. 9091

Lab TRA

4207 - Webster Station

19.301 Old Galveston Pol

Webster 77001

Harris

Basin 1101

Method of Collection The 4-part composite sample was taken

using a clean metal scoop to place the clay in an untreated glass jar with a teflon lined lid.

Demineralizer Regenerant /

Boiler Blowdown Surface Impoundment

Clay Liner - 2-4" beneath surface

Type facility: ☐ Drum; ☐ Tank; ☒ Impoundment; ☐ Landfill☐ Waste pile: ☐ Landfarm: ☐ Other: _____

Time Collected 11:30 (4. pm) Date Shipped

Add. COC 75

ODOR: ☐ Yes: ☒ No: Describe

Paula R. McGee

12328

District _____

7

Org. No. 331

Work No. 9091

Lab TRA

Material Sampled: ☐ Solid waste (W); ☐ Liquid waste (L); ☒ Soil (E); ☐ Well (M);

☐ Stream (S); ☐ Other (O)

Comments: The sample was taken 2-4" from surface & is a 4-part composite

(continued on back)

Lab Only	Date	rec'd: 7-3-86	86-3817-02 (Lab No)
		cm: 8-28-86	
Analyst sign: <i>W. B. Cyro</i>			
Preservation: <input type="checkbox"/> None; <input checked="" type="checkbox"/> Ice; <input type="checkbox"/> H ₂ SO ₄ ; <input type="checkbox"/> HNO ₃ , Other _____			
Auxiliary Tags <input checked="" type="checkbox"/> LEACHATE <input checked="" type="checkbox"/> EP Toxicity Series: — TDWR			

30	Code	35	Parameter Value	44	Code	49	Parameter Value	58	Code	63	Parameter Value	71	
pH				EP-TOX series				LEAD EP TOX ug/L					
0	0	4	0	3			7.6	0	1	0	5	1	2
COD				BARIUM EP TOX ug/L				MERCURY EP TOX ug/L					
0	0	3	4	0				0	1	0	0	7	3
TOC				ARSENIC EP TOX ug/L				SELENIUM EP TOX ug/L					
0	0	6	8	0				0	1	1	4	7	2
GC/MS				CADMIUM EP TOX ug/L				SILVER EP TOX ug/L					
								0	1	0	2	7	1
				CHROMIUM EP TOX ug/L									
								0	1	0	3	4	1

112912000

Reference 7

File III A
TWC Reg. No. 5116-53

JUL 21 1986

TEXAS WATER COMMISSION
Solid Waste Compliance Monitoring Inspection Report

C.O. Use Only

DEPARTMENT AND FIELD OFFICE

INSPECTION COVER SHEET

TWC Dist. 7

0786 Gr 13

EPA ID No. TXD000837369 COMMERCIAL WASTE Facility GOVT. Facility

NAME OF COMPANY Houston Lighting & Power - Webster Station

MAILING ADDRESS PO Box 1700 - W.F. McGuffee Houston TX 77001 Tel. (713) 922-2186

SITE LOCATION 19301 Old Galveston Rd, Webster Tel.

COUNTY Harris TYPE OF INDUSTRY electrical generating station

GENERATOR CLASSIFICATION: Industrial ☒ Municipal

Part A Application submitted to the State? Yes ☒ No To EPA? Yes ☒ No
Affidavit of Exclusion submitted to the State? Yes No ☒
Was a written exclusion granted by TWC? Yes No ☒ If yes, Date
Will this facility require a permit? Yes No ☒

CURRENT WASTE MANAGEMENT (Haz.-"H", Class I NonHaz.-"NH", Class II-"II", Class III-"III")

Generator H, NH, II Treatment II Storage II, NH, II Disposal Transporter

HW Exemptions (check): 90-Day Storage ☒ Other WWT Treatment
(when facility closure is complete)
*SQG : Total HW Generation Per Month: <1000 kg. 1000-10000 kg.

H W Facilities (circle appropriate codes): (C) (T) (SI) WP LT LF I TT TR WDW O
N H Facilities (circle appropriate codes): (C) (T) (SI) WP LT LF I TT TR WDW O

Anomalies in the above information will be addressed by: (a) Enforcement in progress
(b) Central Office , (c) District Office , (d) Owner/Operator .

Type of Inspection (circle): (EV) EB EC CL GW SA CD FO OT FE SQ SW

Inspector's Name and Title Paula Thetford, Hazardous & Solid Waste Specialist

Inspection Participants Richard Byr, Barbara Dorf, Debbie Peters, Richard Parham - HLC & F

Date(s) of Inspection 7/9/86

Approved: [Signature]
District Manager

Signed: Paula R Thetford 7/14/86
Inspector (SA) Date

* SQG- Small quantity generator, <10000 kg. of hazardous waste per month.

TEXAS WATER COMMISSION
Solid Waste Inspection Report
CONTENTS SHEETCOMPANY NAME Houston Lighting & Power Webster

- ☒ 1. Code Sheet (0811)
- ☒ 2. Inspection Cover Sheet
- ☐ 3. Special Inspection Cover Sheet (HB.2358)
- ☒ 4. Generators Checklist
- ☐ 5. Small Quantity Generator Checklist
- ☒ 6. General Facilities Checklist
- *7. Component Facility Checklists
- ☒ A. Containers (C)
- ☐ B. Tanks (T) - part of the WWT Treatment System
- ☐ C. Surface Impoundments (SI)
- ☐ D. Waste Piles (WP)
- ☐ E. Land Treatment (LT)
- ☐ F. Landfills (LF)
- ☐ G. Incinerators (I)
- ☐ H. Thermal Treatment (TT)
- ☐ I. Chemical, Physical, or Biological Treatment (TR)
- ☐ J. Other (O)
- ☐ 8. Closure and Post-Closure Checklist ☐ Closure-In-Progress Checklist
- ☐ 9. Groundwater Monitoring Checklist _____
- ☒ 10. Notice of Violation (NOV) Letter
- ☐ 11. Interoffice Memorandum (IOM)
- ☐ 12. Registration
- ☒ 13. Maps, Plans, Sketches
- ☐ 14. Photographs/Slides
- ☐ 15. Other (describe) _____

* If a required Checklist is omitted, explain: The groundwater monitoring checklist is omitted because groundwater monitoring will cease (upon facility closure in 2-3 weeks), as stated and approved in the facility closure plan.

GENERATORS CHECKLIST**Section A - Notification and Waste Determination (335.6, .62, .63)**

1. Has generator completed an appropriate hazardous waste determination for each solid waste produced? YES ☒ NO ☐
2. Check the method used for determination :
- a. Listed as a hazardous waste in 40 CFR Part 261, Subpart D. ☐
- b. Process or materials knowledge. ☒
- c. Tested for characteristics as identified in 40 CFR Part 261, Subpart C (If equivalent test method is used, attach a copy). ☐

NOTE: If a hazardous determination has not been made or appears to be incorrect, the inspector should obtain a sample of the waste for analysis and explain in comments.

3. Has the facility received an EPA ID number? N/A ☐ YES ☒ NO ☐
4. Is notification of waste streams generated correct? YES ☒ NO ☐
5. Do all waste management (TSD) methods in use agree with Registration? YES ☐ NO ☒
6. Does this facility generate, treat, store, or dispose of PCB wastes? YES ☐ NO ☒
If yes, describe storage and disposition:

7. Does this facility generate **used oils** ? YES ☒ NO ☐
If yes, describe storage and disposition:
Waste oils (Class I and II) are stored in a 500 gallon tank located in the container storage area.

8. Does this facility generate **spent solvents** ? YES ☒ NO ☐
If yes, describe storage and disposition:
Spent solvents are drummed and shipped to Rollins.

9. Does this facility utilize **sumps** in the management of hazardous waste? If yes, describe use: YES ☐ NO ☒

*** An entry in this column indicates corrective action/response is needed

Section B - Special Conditions (335.75)

1. If generator has received from or transported to a **foreign** entity any hazardous waste, has the appropriate notice been filed with the EPA Regional Administrator? N/A ☒ YES ☐ NO ☐
2. Was the waste manifested and signed by the foreign consignee? N/A ☒ YES ☐ NO ☐
3. Has confirmation of waste transport out of the country been received by the generator? N/A ☒ YES ☐ NO ☐

Section C - Recordkeeping and Reporting (335.9, .10, .13, .70-71)

1. Does the generator maintain the following records and reports (if applicable) for the necessary three years?
 - a. Shipping Manifests N/A ☐ YES ☒ NO ☐
 - b. Monthly off-site shipment summaries N/A ☐ YES ☒ NO ☐
 - c. Monthly on-site land disposal summaries N/A ☒ YES ☐ NO ☐
 - d. Monthly waste receipt summaries N/A ☒ YES ☐ NO ☐
 - e. Tests and analyses N/A ☐ YES ☒ NO ☐
 - f. Annual reports N/A ☐ YES ☒ NO ☐
2. Has generator submitted **exception reports** to TWC for any original (white) copies of manifests not received back? N/A ☒ YES ☐ NO ☐
3. Have any spills, unauthorized discharges or threats of such discharges occurred? YES ☒ NO ☐
If yes, have they been reported?(335.4, .453) N/A ☐ YES ☐ NO ☒
Have they been remedied?(335.453) Explain. N/A ☐ YES ☒ NO ☐
see comments

+++ IF GENERATOR DISPOSES OF WASTES ON-SITE ONLY, WRITE N/A IN SECTION D+++

Section D - Pretransport and Manifest Requirements (335.61-68)

1. Identify primary off-site disposal facilities:
BFI, Rollins
2. Are off-site disposal facilities permitted or operating under interim status standards? N/A ☐ YES ☒ NO ☐
3. Are TWC manifests properly completed? N/A ☐ YES ☒ NO ☐

+++ STOP & SIGN HERE IF FACILITY QUALIFIES AS A SMALL QUANTITY GENERATOR +++

Signed: _____

Section D - (Continued)

4. Do containers used to hold waste(s) meet DOT packaging requirements (49 CFR Parts 173, 178, 179) before being offered for transport (if circumstances observed)? N/A ☒ YES ___ NO ___
5. Does generator label and mark each package in accordance with 49 CFR Part 172 (if circumstances observed)? N/A ☒ YES ___ NO ___
6. Is each container of 110 gallons or less marked with the required hazardous waste warning label? *There were no drums containing waste at the time of inspection.* N/A ☒ YES ___ NO ___
7. Does generator placard off-site waste shipments in accordance with DOT regulations (49 CFR Part 172, Subpart F)? (if circumstances observed) N/A ☒ YES ___ NO ___

Section E - Accumulation Time Exemption (335.69)

Note: A facility may accumulate and store hazardous wastes in containers or tanks for up to 90 days without a permit.

1. Is the beginning date of Accumulation Time clearly indicated on each container? N/A ☒ YES ___ NO ___
2. Is each container or tank clearly labeled or marked with the words "Hazardous Waste"? *There were no drums containing wastes at the time of inspection.* N/A ☒ YES ___ NO ___

Note: Attach a Container Storage Area Checklist for each container storage area.

Note: Attach a Tanks Checklist for each tank or each group of similar tanks.

Note: If this is a T/S/D Facility, proceed to General Facilities Checklist.

COMMENTS SHEET

Section A 15: The boiler or industrial furnace (Facility No. 03) is not being used to dispose of any wastes; and according to plant personnel, will not be used in the future. Also, two surface impoundments (Facilities No. 01 and 02) are in the process of being closed.

Section C 13: During inspection of the manifests, it was found that approximately 150 cubic yards of sodium hydroxide contaminated material was removed from the plant site. According to plant personnel, a caustic line broke, spilling approximately 100 lbs. of sodium hydroxide on the plant site. The sodium hydroxide contaminated material was soil removed from the area. This spill was not reported.

Section 1

GENERAL FACILITIES CHECKLISTSection A - General Site Information

1. Are any solid waste facilities located in the 100-year floodplain? NO ☒ YES ☐ ***
2. Describe land use within one mile residential, commercial, rural
3. Are there any closed or abandoned solid waste facilities? NO ☒ YES ☐
Two surface impoundments and the container storage area are in the process of being closed.
4. Has proof of deed recordation of all on-site solid waste Land Disposal facilities been provided to TWC? N/A ☒ YES ☐ NO ☐
5. Are all solid waste facilities compliant with TAC general prohibitions? YES ☐ NO ☐

NOTE: Attach Plant Map showing site orientation, waste management facilities, and major topographic features. Each facility component checklist should have a map or sketch attached.

+++ STOP & SIGN HERE IF THERE ARE NO RCRA FACILITIES ON-SITE +++
 Signed: _____

Section B - Personnel Training

1. Does the owner/operator maintain proper personnel training records at the facility? N/A ☐ YES ☒ NO ☐
2. Do personnel training records include:
- a. Job title and written job description of each position N/A ☐ YES ☒ NO ☐
 - b. Description of type and amount of training N/A ☐ YES ☒ NO ☐
 - c. Records of training given to facility personnel N/A ☐ YES ☒ NO ☐
3. Are personnel training records maintained for the appropriate length of time? N/A ☐ YES ☒ NO ☐
4. Is the training program adequate for response to emergencies? N/A ☐ YES ☒ NO ☐
A more detailed training program is being revised to include more emphasis on the container storage area.

*** An entry in this column indicates explanation/response is needed.

Section C - Preparedness and Prevention

1. Describe any evidence of fire, explosion, or contamination of the environment in the comments sheet.
2. Is the facility equipped with: ***
- a. Internal communication or alarm system within easy access YES ☒ NO ☐
 - b. Communication system to call off-side emergency assistance YES ☒ NO ☐
 - c. Fire, spill control, and decontamination equipment YES ☒ NO ☐
 - d. Adequate fire-water supply (volume and pressure)
located around transformers and electrical equipment YES ☒ NO ☐
3. Is the above-noted emergency equipment regularly tested? YES ☒ NO ☐
Fire extinguishers checked monthly
sprinkler system checked annually
4. Is aisle space sufficient to allow unobstructed movement of personnel and equipment? YES ☒ NO ☐
5. Has the owner/operator attempted to familiarize local response authorities with the facility layout, entrances and evacuation routes, hazardous waste properties and hazards, and the work location of facility personnel? N/A ☐ YES ☐ NO ☒
6. If more than one law enforcement or fire department responds, has a primary authority been designated? N/A ☐ YES ☒ NO ☐
The plant is located in the city limits of Webster.
7. Has the owner/operator attempted to reach agreements with State emergency response teams, emergency response contractors and equipment suppliers? N/A ☐ YES ☒ NO ☐
8. Has the owner/operator attempted to make arrangements with local hospitals to familiarize them with the hazardous wastes handled and the injuries that could result from fires, explosions, or releases from the facility? N/A ☐ YES ☐ NO ☒
9. If State or local authorities have declined to enter into the above-noted agreements, has the owner/operator documented this? N/A ☒ YES ☐ NO ☒

Section D - Contingency Plan and Emergency Procedures

1. Is a contingency plan to minimize dangers from accidental releases from hazardous waste facilities maintained on site? *See comments* YES ☒ NO ☐
2. Does the contingency plan contain:
- a. Description of emergency response actions YES ☒ NO ☐
 - b. Names of emergency coordinators on-site or on-call YES ☒ NO ☐
 - c. Location of emergency equipment YES ☒ NO ☐
 - d. Evacuation plans YES ☒ NO ☐

+++ STOP & SIGN HERE IF FACILITY QUALIFIES FOR THE 90-DAY STORAGE EXEMPTION +++

Signed: _____

The facility will be a 90-day storage exempt facility in 2-3 weeks upon certification of closure.

Section E - Waste Analysis

1. Is a **written waste analysis plan** maintained at the facility? YES ___ NO ___
2. Does the plan include the following:
 - a. Detailed physical and chemical analysis of all haz. wastes YES ___ NO ___
 - b. Rationale for selection of analytical parameters YES ___ NO ___
 - c. Test methods used YES ___ NO ___
 - d. Sampling methods used YES ___ NO ___
 - e. Frequency the initial analysis will be reviewed or repeated YES ___ NO ___
 - f. Waste analyses that generators have agreed to provide N/A ___ YES ___ NO ___
3. For disposal facilities receiving wastes from off-site, is each incoming waste shipment inspected and, if necessary, analyzed to check it against the manifest? N/A ___ YES ___ NO ___

Section F - Security

1. Does the facility provide adequate security to minimize the possibility of unauthorized entry by persons or livestock? YES ___ NO ___
2. Is security of the active portion of the facility provided through:
 - a. 24 Hr surveillance
or
 - b. Perimeter barriers and means to control entry YES ___ NO ___
3. Does facility post a "Danger-Unauthorized Personnel Keep Out" sign at approaches to active portions of the facility? YES ___ NO ___

Section G - General Inspection Requirements

1. Is a **written inspection schedule** maintained at the facility? N/A ☐ YES ☐ NO ☐
2. Does the schedule provide for inspection of the following:
 - a. Monitoring equipment YES ☐ NO ☐
 - b. Safety and emergency equipment YES ☐ NO ☐
 - c. Security devices YES ☐ NO ☐
 - d. Operating and structural equipment YES ☐ NO ☐
3. Does the schedule identify the following **types of problems** to be looked for during the inspection:
 - a. Malfunction and deterioration YES ☐ NO ☐
 - b. Operator error YES ☐ NO ☐
 - c. Discharge or threat of discharge YES ☐ NO ☐
4. Does owner/operator maintain **inspection logs** which include:
 - a. Date and time of inspection YES ☐ NO ☐
 - b. Name of inspector YES ☐ NO ☐
 - c. Notation of observation YES ☐ NO ☐
 - d. Date and nature of repairs and remedial action YES ☐ NO ☐
5. Have malfunctions or other deficiencies noted in the inspection log been corrected? N/A ☐ YES ☐ NO ☐
6. Are **inspection log records** maintained for three years? YES ☐ NO ☐

Section H - Requirements for Ignitable, Reactive or Incompatible Wastes

1. Does owner/operator take precautions to prevent accidental ignition or reaction of ignitable or reactive wastes? N/A ☐ YES ☐ NO ☐
2. Are smoking and open flame confined to designated smoking areas? N/A ☐ YES ☐ NO ☐
3. Are "No Smoking" signs posted in areas with ignitable or reactive wastes? N/A ☐ YES ☐ NO ☐

Section I - Manifest System, Recordkeeping and Reporting

1. Does owner/operator comply with manifesting requirements? N/A ☐ YES ☐ NO ☐
2. For wastes received from off-site:
 - a. Is waste transported by rail or water (bulk) accompanied by a properly executed shipping papers? N/A ☐ YES ☐ NO ☐
 - b. Have all shipments been consistent with the manifests? N/A ☐ YES ☐ NO ☐
 - c. Are unmanifested wastes reported to TWC? N/A ☐ YES ☐ NO ☐
 - d. Have manifest discrepancies been reconciled with the generator and transporter? N/A ☐ YES ☐ NO ☐

Section J Operating Record

1. Is a written operating record maintained at the facility? N/A ☐ YES ☐ NO ☐
2. Does the operating record reflects the following:
 - a. Description and quantity of each hazardous waste received and methods and date of treatment/storage/disposal at the facility. N/A ☐ YES ☐ NO ☐
 - b. Location and quantity of each hazardous waste within the facility. N/A ☐ YES ☐ NO ☐
 - c. Records and results of waste analyses and trial tests N/A ☐ YES ☐ NO ☐
 - d. Summary reports of all incidents requiring implementation of the Emergency Contingency Plan. N/A ☐ YES ☐ NO ☐
 - e. Closure Cost estimates for all facilities. N/A ☐ YES ☐ NO ☐
 - f. Post-Closure cost estimates for all disposal facilities. N/A ☐ YES ☐ NO ☐

Section K - Financial Assurance

1. Did preinspection call to Central Office confirm that facility has submitted current financial assurance documentation? N/A ☐ YES ☐ NO ☐
2. If Yes, indicate the documents submitted and their respective values:

_____ Sudden Liability-	Amount: \$ _____	per occurrence,	\$ _____	annual
_____ Non-sudden Liability-	Amount: \$ _____	per occurrence,	\$ _____	annual
_____ Closure Assurance-	Amount: \$ _____			
_____ Post-Closure Assurance-	Amount: \$ _____			
_____ Corrective Action-	Amount: \$ _____			
3. Did Financial Assurance Officer report that documentation is adequate? N/A ☐ YES ☐ NO ☐

COMMENTS SHEET

Section C 15.8, c 9 : HLP personnel have not formally contacted local response authorities for the purpose of familiarizing them with the power plant. Arrangements have not been made to familiarize local hospitals with the hazardous wastes handled at the plant and possible injuries associated with the waste.

Section /

Section /

Section /

TWC Solid Waste Inspection Report
(TAC 335.241-247)
CONTAINER STORAGE AREA CHECKLIST

TWC Reg. No. 41633

Reg. Facility No. 05

Class of Wastes (H, A, H...)

NOTE: TAC rules 335.241-247 apply to interim status and 90-Day Storage exempt facilities.

1. Are containers in good condition? YES ☒ NO ☐
2. Are the containers compatible with the wastes being stored? YES ☒ NO ☐
3. Are containers kept closed and stored in a safe manner? YES ☒ NO ☐
4. Are containers inspected weekly for leakage and deterioration? YES ☒ NO ☐
5. Are containers holding **ignitable** or **reactive** wastes kept at least 15 meters (50 ft.) from the facility's property line? N/A ☐ YES ☒ NO ☐
6. Are containers holding **incompatible** wastes separated by a physical barrier or sufficient distance? N/A ☒ YES ☐ NO ☐
7. Does the storage area have containment protection? YES ☐ NO ☒
8. Describe the Container Storage Area using comments sheet and/or photos:

The container storage area recently underwent closure as a storage facility certification by a registered PE is pending. A 500-gallon tank containing the waste oils (Class I & II) is located in the container storage area, and is about 1/2 full. Also located in the area are 2 empty 55-gallon drums, one marked "waste solvent", and another to be removed from the area. Labeling and inspection requirements for containers to be held there in the future were discussed with HLP personnel.

*** An entry in this column indicates corrective action/response is needed.

TEXAS WATER COMMISSION

Lee ^{RWL}
Coloton *SA*

34599

Paul Hopkins, Chairman
Lee B. M. Biggart, Commissioner
Ralph Roming, Commissioner



Larry R. Soward, Executive Director
Mary Ann Hefner, Chief Clerk
James K. Rourke, Jr., General Counsel

April 4, 1986

14 July 86

Implementation Date

Mr. Melvin G. Warthan
Manufacturing, Supply and Distribution
Chemical Enterprises, Inc.
8582 Katy Freeway, Suite 202
Houston, Texas 77024

Dear Mr. Warthan:

Re: The assessment of pesticide contamination at the
Chemical Enterprises, Inc., Odessa Facility
Solid Waste Registration No. 34599

The staff of the Enforcement Unit has reviewed the subject pesticide contamination assessment submitted with your letter of November 22, 1985. We note that this assessment satisfactorily sets out to measure the known area of contamination at the facility. The Texas Water Commission (TWC) approves the immediate implementation of the assessment with the following additions:

1. Section I.B. of the assessment states that "a surface soil sample will be collected at each intersection of the grid lines." The Commission recommends that the first six inches of soil be removed prior to collecting a surface soil sample at each intersection of the grid lines.
2. Section I.C. of the assessment states that "two subsurface samples will be collected at depths of three feet and six feet at selected stations at each of the two landfills." The Commission recommends that Chemical Enterprises take subsurface samples at depths of one foot and two feet and take any additional deeper subsurface samples that may be necessary to adequately determine the extent of contamination.
3. In addition to collecting subsurface samples at a depth of one foot at selected stations from the Playa Lake area on the plant side and from the Playa Lake east of the plant area, the TWC recommends that surface samples be collected at each grid point. If contamination is found at a depth of one foot, Chemical Enterprises should continue to collect deeper samples until background concentrations are reached.

Mr. Melvin G. Warthan
Page 2

4. Submit an updated schedule for completion of the cleanup. In addition, submit monthly status reports to the TWC outlining the cleanup progress.

The Commission request that Chemical Enterprises, Inc., immediately implement the subject plan. Please notify the TWC Central Office and TWC District Office of the implementation date.

Should you have any questions or comments please do not hesitate to contact Ms. Nancy J. Bolz of my staff at 512/463-8564.

Sincerely,

Merton J. Coloton, P.E., Chief
Hazardous and Solid Waste Enforcement Section
Hazardous and Solid Waste Division

NJB/da

cc: Texas Water Commission District 10 Office
Dallas Cantwell, President, Chemical Enterprises
James Baker, Ph.D., Rollins Environmental Services Inc.
Darless Goolsby, Chemical Enterprises, Inc.

TEXAS WATER COMMISSION



Paul Hopkins, Chairman
Ralph Roming, Commissioner
John O. Houchins, Commissioner

Larry R. Soward, Executive Director
Mary Ann Hefner, Chief Clerk
James K. Rourke, Jr., General Counsel

July 16, 1986

Mr. W. F. McGuire
Manager
Environmental Protection Department
Houston Lighting and Power
P.O. Box 1700
Houston, Texas 77001

Dear Mr. McGuire:

RE: Registration No. 31633-Webster Station Industrial Solid Waste Compliance
Inspection

On July 9, 1986, Paula Thetford of this office conducted an industrial solid waste inspection of your facility. The following deficiencies were noted:

1. Texas Administrative Code (TAC), Section 335.6(c) - Notification Requirements

As discussed with your personnel, the Registration will need to be updated upon certification of closure of your waste management facilities. At this time please include any additional changes that should be made in order to accurately reflect current waste handling practices. A request to amend the registration should be sent to:

Texas Water Commission
Attention: Mr. Dick Martin
P.O. Box 13087
Austin, Texas 78711

2. TAC Section 335.112 - Preparedness and Prevention


Arrangements should be made to familiarize police and fire departments with the layout of the facility. Also, local hospitals should be made familiar with the hazardous wastes handled at the facility and the related injuries which could occur.

In addition, during inspection of your shipping manifests, it was found that 150 cubic yards of sodium hydroxide contaminated material was removed from your facility. Further discussion revealed that the contaminated material was soil contaminated by a recent spill of sodium hydroxide. Please be advised that the State of Texas Oil and Hazardous Substances Spill Contingency Plan, Section 2.2 requires immediate reporting of any spill of a hazardous substance to the TWC.

Mr. W. F. McGuire
Houston Lighting & Power
Page 2,
July 16, 1986

Please respond to this office in writing by August 15, 1986 with your plans and implementation schedule which will ensure corrective action of the above listed deficiencies by September 15, 1986. If you have any questions, please contact Paula Thetford of this office.

Sincerely,

A handwritten signature in cursive script, appearing to read "Tom Kearns", written in dark ink.

Tom Kearns
Manager
Hazardous and Solid Waste
Southeast Region

TK/PT/np

DW0550

TEXAS WATER COMMISSION
NOTICE OF REGISTRATION
INDUSTRIAL SOLID WASTE GENERATION/DISPOSAL

05-08-86

THIS IS NOT A PERMIT AND DOES NOT CONSTITUTE AUTHORIZATION OF ANY WASTE MANAGEMENT ACTIVITIES OR FACILITIES LISTED BELOW. REQUIREMENTS FOR SOLID WASTE MANAGEMENT ARE PROVIDED BY TEXAS ADMINISTRATIVE CODE SECTION 335 OF THE RULES OF THE TEXAS WATER COMMISSION (TWC). CHANGES OR ADDITIONS TO WASTE MANAGEMENT METHODS REFERRED TO IN THIS NOTICE REQUIRE WRITTEN NOTIFICATION TO THE TWC.

DATE OF NOTICE: 05-09-86

REGISTRATION DATE: 12-14-79

REGISTRATION NUMBER: 31633

EPA I.D. NUMBER: TX0000837369

THE REGISTRATION NUMBER PROVIDES ACCESS TO STORED INFORMATION PERTAINING TO YOUR OPERATION. PLEASE REFER TO THAT NUMBER IN ANY CORRESPONDENCE.

COMPANY NAME: HOUSTON LIGHTING & POWER CO.

MAILING ADDRESS: WEBSTER GENERATING STATION

P O BOX 1700 - W.F.MCGUIRE

HOUSTON, TEXAS

77001

GENERATING SITE LOCATION:

19301 OLD GALVESTON RD, WEBSTER, TX

CONTACT PERSON: W F MCGUIRE

PHONE: (713) 922-2186

NUMBER OF EMPLOYEES: LESS THAN 100

TWC DISTRICT: 07

REGISTRATION STATUS: ACTIVE

REGISTRATION TYPE: GENERATOR

HAZARDOUS WASTE STATUS: GENERATOR/TSD FACILITY

I. WASTE GENERATED:

WASTE NUMBER	DESCRIPTION	CLASS	CODE	DISPOSITION
001	OILS, WASTE	I	110450	ON-SITE / SOLD FOR RECOVERY/SECONDARY USE
002	MISC. INORGANIC SLUDGES	II	240540	OFF-SITE
003	ASBESTOS	I	170750	ON-SITE/OFF-SITE
004	BRICK, REFRACTORY (SPENT)	I	170300	ON-SITE/OFF-SITE
005	SOLVENTS, SPENT	IH	910100	ON-SITE / SOLD FOR RECOVERY/SECONDARY USE

NOTICE OF REGISTRATION (CONTINUED)

PAGE 2

REGISTRATION NUMBER: 31633

COMPANY NAME: HOUSTON LIGHTING & POWER CO.

E

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): D001

006 PAINT THINNER IH 910110 OFF-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): F003, F005

007 WASTEWATER, DEMINERALIZER ACID REGENERATION IH 902570 ON-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): D002

008 WASTEWATER, DEMINERALIZER BASE REGENERATION IH 902560 ON-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): D002

009 DEMINERALIZER REGENERANT SLUDGE II 241470 OFF-SITE

010 METAL CLEANING WASTE, INORGANIC C IH 903070 ON-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): D002

011 SLUDGE CONTAINING INORGANICS II 241210 OFF-SITE

012 METAL CLEANING WASTE, ORGANIC II 215290 ON-SITE/OFF-SITE

013 SLUDGE CONTAINING ORGANICS II 248990 OFF-SITE

014 OILS, WASTE II 210450 ON-SITE / SOLD FOR RECOVERY/SECONDARY USE

015 OILY WASTE, MISCELLANEOUS II 283230 ON-SITE/OFF-SITE

016 OILY WASTE, MISCELLANEOUS I 183230 ON-SITE/OFF-SITE

017 SODIUM HYDROXIDE CONTAMINATED MATERIAL IH 976330 OFF-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): D002

018 SANDBLASTING GRIT IH 973280 OFF-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): D008

REGISTRATION NUMBER: 31633

COMPANY NAME: HOUSTON LIGHTING & POWER CO.

019 MERCURY CONTAMINATED WASTE IH 978850 OFF-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): 0009

020 TANK BOTTOMS, FULL OIL I 152920 OFF-SITE/SECONDARY USE

021 SANDBLASTING GRIT II 273280 OFF-SITE

022 DEMINERALIZER RESIN BEADS, SPENT
T II 270131 OFF-SITE

023 FLUE DUST II 271430 OFF-SITE

024 ACID CONTAMINATED MATERIAL IH 979290 OFF-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS):

II. SHIPPING/REPORTING: NOT APPLICABLE

III. ON-SITE WASTE MANAGEMENT FACILITIES:

FAC NO.	FACILITY	STATUS
01	SURFACE IMPOUNDMENT STORAGE OF WASTE NUMBER(S) 007, 008	ACTIVE Closure-in-progress
02	SURFACE IMPOUNDMENT STORAGE OF WASTE NUMBER(S) 010	ACTIVE Closure-in-progress
03	BOILER OR INDUSTRIAL FURNACE (ENERGY PRODUCT PROCESSING/DISPOSAL) OF WASTE NUMBER(S) 001, 005, 014	ACTIVE → none used
04	SURFACE IMPOUNDMENT STORAGE OF WASTE NUMBER(S) 012 - <i>Class II waste</i>	ACTIVE
05	MISCELLANEOUS STORAGE CONTAINERS STORAGE OF WASTE NUMBER(S) 001, 003, 004, 005, 006, 014, 015, 016	ACTIVE

UNLESS OTHERWISE STATED ABOVE, FACILITIES ARE LOCATED
AT 19301 OLD GALVESTON RD, WEBSTER, TX
COUNTY OF HARRIS

REGISTRATION NUMBER: 31633

COMPANY NAME: HOUSTON LIGHTING & POWER CO.

IV. RECORDS.

- A. FOR PURPOSES OF FILING ANNUAL REPORTS PURSUANT TO TEXAS ADMINISTRATIVE CODE SECTION 335 OF THE RULES OF THE TWC PERTAINING TO INDUSTRIAL SOLID WASTE MANAGEMENT, RECORDS SHOULD BE MAINTAINED FOR STORAGE, PROCESSING AND/OR DISPOSAL OF THE FOLLOWING WASTE(S) LISTED IN PART I:

C01 110450 OILS, WASTE


C03 170750 ASBESTOS

C04 170300 BRICK, REFRACTORY (SPENT)

C05 910100 SOLVENTS, SPENT

C07 902570 WASTEWATER, DEMINERALIZER ACID
REGENERATIONC08 902560 WASTEWATER, DEMINERALIZER BASE
REGENERATIONC10 903070 METAL CLEANING WASTE, INORGANI
C

C16 183230 OILY WASTE, MISCELLANEOUS




REVISED BY : ENGINEERING-SCIENCE 5-13-83

ENGINEERING-SCIENCE

DESIGN • RESEARCH • PLANNING

18915 EL CAMINO REAL, HOUSTON, TEXAS 77058 • 713/488-2944

OFFICES IN PRINCIPAL CITIES



The Light company

Houston Lighting & Power P.O. Box 1700 Houston, Texas 77001 (713) 228-9211

May 6, 1985

Mr. Jay Snow, P.E.
Chief, Solid Waste Section
Texas Department of Water Resources
P. O. Box 13087, Capitol Station
Austin, Texas 78711

Dear Mr. Snow:

**SUBJECT: WEBSTER GENERATING STATION - TDWR NO. 31633
Supplement to Closure Plan for Hazardous Waste
Surface Impoundments**

A closure plan for hazardous waste surface impoundments at this facility was submitted on February 11, 1985. Your letter of April 15, 1985, discussed deficiencies in the closure plan and requested additional information for use in your evaluation. Attached is a supplement to the closure plan which addresses the comments in your letter.

Your expeditious review and response to the enclosed material will be appreciated since, as stated in the closure plan, HL&P intends to initiate closure on or about June 1, 1985, pending TDWR review and approval.

Please contact Dr. R. D. Groover, 713/922-2195, if you have any questions.

Sincerely,



for W. F. McGuire, Manager
Environmental Protection Dept.

BAD/rmg
Attachment

TEXAS DEPARTMENT OF WATER RESOURCES

1700 N. Congress Avenue

Austin, Texas



Charles E. Nemir
Executive Director

TEXAS WATER DEVELOPMENT BOARD

Louis A. Beecherl, Jr., Chairman
George W. McCleskey, Vice Chairman
Glen E. Roney
Lonnie A. "Bo" Pilgrim
Louie Welch
Stuart S. Coleman

TEXAS WATER COMMISSION

Paul Hopkins, Chairman
Lee B. M. Biggart
Ralph Roming

May 16, 1985

Mr. W. F. McGuire, Manager
Environmental Protection Dept.
Houston Lighting and Power
P. O. Box 1700
Houston, Texas 77001

Dear Mr. McGuire:

Re: Proposed Wastewater Treatment Tank
Solid Waste Registration No. 31633
Webster, Texas Facility

This is in response to your correspondence received April 22, 1985 which transmitted the plans and specifications for the proposed fiberglass-lined concrete storage tank. As indicated in your letter, this tank will temporarily store demineralizer regenerant wastewater and boiler blowdown prior to treatment in the existing wastewater treatment facility.

The plans were reviewed for conformance with American Concrete Institute (ACI) and American Society of Testing and Materials (ASTM) Standards relating to the materials of construction and the requirements for reinforcing steel. Our review indicates that the proposed tank meets the definition of a "Wastewater Treatment Unit" pursuant to Texas Administrative Code (TAC) 335.42 and appears to be exempt from hazardous waste permitting requirements. We anticipate this decision will expedite your construction plans.

Should you require any additional assistance, please contact Ms. Kathleen DeMarinis at AC512/463-8184.

Sincerely,

A handwritten signature in cursive script that reads "Ray Henry Austin".

Ray Henry Austin, Head
Storage and Processing Facilities Unit
Solid Waste Section

KMD:lab

cc: TDWR District 7 - Deer Park



The Light company

Houston Lighting & Power P.O. Box 1700 Houston, Texas 77001 (713) 228-9211

May 13, 1985

Mr. Jay Snow, P.E.
Chief, Solid Waste Section
Texas Department of Water Resources
P. O. Box 13087, Capitol Station
Austin, Texas 78711

SUBJECT: CLOSURE PLANS FOR CONTAINER STORAGE AREAS

S. R. Bertron Generating Station	TDWR No. 31637
H. O. Clarke Generating Station	TDWR No. 31635
Greens Bayou Generating Station	TDWR No. 31634
P. H. Robinson Generating Station	TDWR No. 31638
Webster Generating Station	TDWR No. 31633
T. H. Wharton Generating Station	TDWR No. 31636

Dear Mr. Snow:

Discussions between Mr. Ray Austin, Mr. Jim Feeley (TDWR) and Dr. R. D. Groover (HL&P) indicate that, to achieve full-facility closure and generator-only status for the above-referenced facilities, closure plans for container storage areas are required even though the storage areas will continue in use under the "Accumulation Time" storage exclusion (31 TAC, Section 335.69). Transmitted herewith are three (3) copies of closure plans for the container storage areas. The current status of each generating station is briefly summarized below:

S. R. Bertron

All hazardous waste surface impoundments have been closed under TDWR-approved closure plans; an affidavit for exclusion from hazardous waste permitting is in preparation.

H. O. Clarke

All hazardous waste surface impoundments have been closed under TDWR-approved closure plans, and an affidavit of exclusion from hazardous waste permitting was submitted on March 12, 1985.

Greens Bayou

The demineralizer regenerant impoundment has been closed under a TDWR-approved closure plan. After completion of a fiberglass-lined concrete tank, the inorganic impoundment will be closed and an affidavit of exclusion from hazardous waste permitting will be submitted.

Houston Lighting & Power Company

Mr. Jay Snow
May 13, 1985
Page 2

P. H. Robinson

Closure plans for three hazardous waste surface impoundments have been submitted to TDWR. Upon final approval, closure activities are scheduled to begin in the summer of 1985.

Webster

Closure plans for two hazardous waste surface impoundments have been submitted to TDWR. Upon final approval, closure activities are scheduled to begin in the summer of 1985.

T. H. Wharton

The inorganic metal cleaning impoundment has been closed under a TDWR-approved closure plan. After completion of a fiberglass-lined concrete tank, the demineralizer regenerant impoundment will be closed and an affidavit of exclusion from hazardous waste permitting will be submitted.

Should you have any questions pursuant to these container storage area closure plans, please contact Mr. R. T. Bye at 922-2201.

Sincerely,



for

W. F. McGuire, Manager
Environmental Protection Dept.

RDG/rmr
Attachments

CLOSURE PLAN
FOR
S. R. BERTRON HAZARDOUS WASTE CONTAINER STORAGE AREA

1.0 INTRODUCTION

Background - Houston Lighting & Power Company (HL&P) operates a hazardous waste container storage area at the S. R. Bertron Electric Generating Station. The drum storage area is located in the north side of the Construction Warehouse in one tenth of a metal storage building. The remainder of the building is used for construction storage. The area is clearly identified as a hazardous waste storage area by signs on the building.

In accordance with the requirements of 31 TAC, Section 335, Subchapter J, and 40 CFR 264.178, this closure plan identifies the

[REDACTED]

facility. Accumulation time after closure for hazardous waste will be less than 90 days.

This facility currently stores bagged asbestos and 55 gallon drums of liquid and solid hazardous and nonhazardous wastes. These wastes include refractory brick, spent solvents, paint thinner, waste oils, miscellaneous oily wastes, and sandblasting grit.

All spills and leaks are cleaned up promptly using absorbants and surfactants when necessary.

2.0 MIGRATION ASSESSMENT

Surface Water - There is little potential for surface water contamination resulting from operation of the container storage

55 gallon drum and disposed of at an off-site Class 1 disposal facility.

5.0 NOTIFICATION

Mr. Merton J. Coloton, Supervisor, TDWR, District 7, will be notified ten (10) days prior to the commencement of closure in the event that TDWR District 7 personnel desire to observe closure activities.

6.0 CLOSURE CERTIFICATION

Following completion of all closure activities, a registered professional engineer will provide a written certification documenting that closure has been completed in accordance with this plan. This written certification will be submitted to the TDWR.

7.0 POST-CLOSURE ACTIVITIES

The storage area will continue to be used for containerized hazardous and nonhazardous wastes. An inventory of accumulation dates will be maintained to insure that hazardous wastes remain on-site for less than 90 days.

CLOSURE PLAN
FOR
WEBSTER HAZARDOUS WASTE CONTAINER STORAGE AREA

1.0 INTRODUCTION

Background - Houston Lighting & Power Company (HL&P) operates a hazardous waste container storage area at the Webster Electric Generating Station. The container storage area is located adjacent to the waste oil tank at the east end of the gas turbine building.

In accordance with the requirements of 31 TAC, Section 335, Subchapter J, and 40 CFR 264.178, this closure plan identifies the steps necessary to close the container storage facility. Following closure, the area will continue to be used as a container storage facility. Accumulation time after closure for hazardous waste will be less than 90 days.

This facility currently stores 55 gallon drums of liquid and solid hazardous and nonhazardous wastes. These wastes include refractory brick, spent solvents, paint thinner, waste oils, miscellaneous oily wastes, and sandblasting grit.

All spills and leaks are cleaned up promptly using absorbants and surfactants when necessary.

2.0 MIGRATION ASSESSMENT

Surface Water - There is little potential for surface water contamination resulting from operation of the container storage area. The area is housed on a concrete pad and all spills or leaks are cleaned up promptly.

Subsurface Migration - The floor of the area is reinforced concrete. Any material spilled or leaked onto the floor is cleaned up promptly. Potential for subsurface migration of wastes from this facility is nil.

3.0 CLOSURE PROCEDURE AND SCHEDULE

Closure of the container storage area will begin on or about August 1, 1985, (pending TDWR approval) and will consist of the following steps:

1. Prior to closure all wastes stored in the facility will be transferred off-site to a Class I disposal facility.
2. The floor will be cleaned using brushes, solvents and an all purpose surfactant.
3. Absorbent material will be used to pick up the surfactant.
4. The cleaned area will then be rinsed three times with water. All water will be picked up by wet-vacuum or with sponge mops.
5. All materials and liquids will be placed in a 55 gallon drum for off-site disposal.

4.0 MISCELLANEOUS PROCEDURES

Safety - Protective clothing will be worn during cleaning to provide worker protection.

Material Disposal - All materials, liquids, and protective clothing used during closure of the storage area will be placed in a 55 gallon drum and disposed of at an off-site Class I disposal facility.

5.0 NOTIFICATION

Mr. Merton J. Coloton, Supervisor, TDWR, District 7, will be notified ten (10) days prior to the commencement of closure in the event that TDWR District 7 personnel desire to observe closure activities.

6.0 CLOSURE CERTIFICATION

Following completion of all closure activities, a registered professional engineer will provide a written certification documenting that closure has been completed in accordance with this plan. This written certification will be submitted to the TDWR.

7.0 POST-CLOSURE ACTIVITIES

The storage area will continue to be used for containerized hazardous and nonhazardous wastes. An inventory of accumulation dates will be maintained to insure that hazardous wastes remain on-site for less than 90 days.

SUPPLEMENT TO
CLOSURE PLAN FOR TWO HAZARDOUS WASTE IMPOUNDMENTS
AT THE WEBSTER GENERATING STATION
TDWR NO. 31633

HOUSTON LIGHTING & POWER COMPANY
HOUSTON, TEXAS

JULY 1985

SEQUENCE OF SAMPLING

For purposes of waste classification prior to disposal as outlined in Sec. 3.3, Sludge Thickness and Analysis and Clay Liner Testing, a composite sample of the sludge and first foot of clay liner will be collected and analyzed for pH and the EP Toxicity metals. All the sludge and one (1) foot of clay material from the surface of the clay liner will be removed and disposed prior to further sampling the clay liner.

ADDITIONAL ANALYTICAL COMPARISONS AND ANALYSES

In addition to the pH and EP metals toxicity analyses specified in Section 3.3 and the supplement submitted May 6, 1985, seven surface samples of the exposed clay liner and sidewalls will be collected and an analysis for total metals will be performed for the eight EP toxicity metals to demonstrate absence of hazardous waste constituents. Sample collection points will be as described in the May 6 supplement.

These results will be compared to three (3) background samples taken in the vicinity of the impoundments and known literature values for soil samples. These background samples will be composites of the top two feet of soil. If the liner total metals concentrations are within the range of these background samples and known natural soil variations, the impoundments will be considered decontaminated of hazardous waste constituents.

In addition, a 24-hour modification of the TDWR leachate test will be performed on the liner samples from the inorganic metal cleaning impoundment. These samples will be analyzed for sulfate and chloride. These results will be compared to values for background soil samples and to groundwater monitoring data available from the groundwater monitoring program at the power plant. If the leachate concentrations are not significantly different from the background soil and groundwater data, the impoundments will be considered free of Class II waste.

ADDITIONAL SOIL BORINGS

In addition to the four shallow borings in the demineralizer impoundment as specified in Section 4.0, POST-CLOSURE ACTIVITIES, two (2) additional borings will be placed in the sidewall of the impoundment near the sampling locations identified in the May 6 supplement. All six borings will be used to verify the liner characteristics as specified in TDWR Technical Guideline No. 4. If the liner characteristics are not in accordance with TDWR Guideline No. 4, the clay liner will be reworked and recompactd or additional clay will be placed as necessary to meet guideline recommendations.

TEXAS DEPARTMENT OF WATER RESOURCES

1700 N. Congress Avenue
Austin, Texas

TEXAS WATER DEVELOPMENT BOARD

Louis A. Beecherl, Jr., Chairman
George W. McCleskey, Vice Chairman
Glen E. Roney
Lonnie A. "Bo" Pilgrim
Louie Welch
Stuart S. Coleman



Charles E. Nemir
Executive Director
MAY 17 1985

TEXAS WATER COMMISSION

Paul Hopkins, Chairman
Lee B. M. Biggart
Ralph Roming

Mr. W. F. McGuire, Manager
Environmental Protection Dept.
Houston Lighting and Power
P. O. Box 1700
Houston, Texas 77001

KMD DeMarinis
RHA Austin
RHS Snow
for

Dear Mr. McGuire:

Re: Proposed Wastewater Treatment Tank
Solid Waste Registration No. 31633
Webster, Texas Facility

This is in response to your correspondence received April 22, 1985 which transmitted the plans and specifications for the proposed fiberglass-lined concrete storage tank. As indicated in your letter, this tank will temporarily store demineralizer regenerant wastewater and boiler blowdown prior to treatment in the existing wastewater treatment facility.

The plans were reviewed for conformance with American Concrete Institute (ACI) and American Society of Testing and Materials (ASTM) Standards relating to the materials of construction and the requirements for reinforcing steel. Our review indicates that the proposed tank meets the definition of a "Wastewater Treatment Unit" pursuant to Texas Administrative Code (TAC) 335.42 and appears to be exempt from hazardous waste permitting requirements. We anticipate this decision will expedite your construction plans.

Should you require any additional assistance, please contact Ms. Kathleen DeMarinis at AC512/463-8184.

Sincerely,

Ray Henry Austin, Head
Storage and Processing Facilities Unit
Solid Waste Section

KMD:lab
cc: TDWR District 7 - Deer Park

TWC Reg. No. 31633TEXAS WATER COMMISSION
Solid Waste Compliance Monitoring Inspection Report

INSPECTION COVER SHEET

C.O. Use Only

~~31633~~ 86

LLS

31/36 KAR

EPA ID No. TXD000237349 Commercial Waste Facility _____ Govt. Facility _____
 NAME OF COMPANY Houston Lighting & Power Co. - Webster Station
 MAILING ADDRESS PO Box 1700 - WFM McGuire, Houston, TX 77001 Tel. (713) 922-8216
 SITE LOCATION 19301 Old Galveston Rd., Webster Tel. "
 COUNTY Harris TYPE OF INDUSTRY Electric Power Generation

Part A Application submitted to the State ? Yes ☒ No _____ To EPA ? Yes ☒ No _____
 Affidavit of Exclusion submitted to the State ? Yes ☒ No _____
 Was a written exclusion granted by TWC? Yes _____ No ☒ If yes, Date _____
 Will this facility require a permit ? Yes _____ No ☒

Current Waste Management (Haz.-H, Class I NonHaz.-NH, Class II, III or check as appropriate)

Generator H, NH, II Treatment H Storage H, NH, II Disposal _____ Transporter _____

HW Exemptions: SQG _____ 90-Day Storage ☒ Other WWT Treatment
Once closure activities are complete

EW Facilities (circle appropriate codes): (C) T (SI) WP LT LF I TT TR WDW ONH Facilities (circle appropriate codes): C T (SI) WP LT LF I TT TR WDW O

Anomalies in the above information will be addressed by : (a) Enforcement in progress _____,
 (b) Central Office ☒, (c) District Office _____, (d) Owner/Operator _____.

Inspection Information :Type of Inspection (circle): EV FB EC (CL) GN SA CD FO OT FE SWInspector's Name and Title Karen L. Blum - Hazardous & Solid Waste SpecialistInspection Participants Richard ByeInspection Date(s) October 13, 1985

Approved :

Douglas
District Manager

Signed :

Karen L. Blum
InspectorDate: 12-12-85

TEXAS WATER COMMISSION
Solid Waste Compliance Monitoring Inspection Report DEC 20 1985
CONTENTS SHEETFACILITY NAME Houston Lighting & Power Co. - Webster Station

- ✓ 1. Code Sheet (0814)
- ✓ 2. Inspection Cover Sheet
- 3. Generators Checklist
- 4. Small Quantity Generator Checklist
- 5. General Facilities Checklist
- 6. Component Facility Checklists*
 - A. Containers (C)
 - B. Tanks (T)
 - C. Surface Impoundments (SI)
 - D. Waste Piles (WP)
 - E. Land Treatment (LT)
 - F. Landfills (LF)
 - G. Incinerators (I)
 - H. Thermal Treatment (TT)
 - I. Chemical, Physical, or Biological Treatment (TR)
 - J. Other (O) _____
- ✓ 6. Closure ^{- In Progress} and Post Closure Checklist
- 7. Groundwater Monitoring Checklist
- 8. Notice of Violation (NOV) Letter
- 9. Interoffice Memorandum (ICM)
- ✓ 10. Registration
- 11. Maps, Plans, Sketches
- 12. Photographs/Slides
- ✓ 13. Other (describe) correspondence regarding closure

* If a required Checklist is omitted, explain: _____

TWC Solid Waste Inspection Report
(40 CFR Part 264 Subpart G; Part 265 Subpart G)
CLOSURE-In-PROGRESS CHECKLIST

TWC Reg. No. 31633
Reg. Facility No. 05

Note: This checklist is to be completed if company is in the process of closing a hazardous waste management facility.

1. Type of facility: Container Storage Area
2. Has the closure plan received TWC approval or final modification? N/A ☐ YES ☒ NO ☐
Date of approval: 09 / 23 / 85
3. Identify the type of closure: Final Closure ☐
Partial Closure ☒
4. If this is a partial closure, is this the last facility to be closed requiring RCRA ground water monitoring? N/A ☐ YES ☐ NO ☒
5. If this is an interim status facility:
 - a. Has an approved public notice of closure been published? N/A ☐ YES ☒ NO ☐
Date published: 07 / 26 / 85
 - b. Is a public hearing required? N/A ☐ YES ☐ NO ☒
Date of hearing: / /
6. Has on-site closure work started? N/A ☐ YES ☐ NO ☐
Date work initiated: 10 / 18 / 85
7. Is the on-site closure work proceeding in accordance with the work schedule established in the approved closure plan? N/A ☐ YES ☒ NO ☐
8. Have 180 days elapsed since TWC approval of the closure plan? N/A ☐ YES ☐ NO ☒
 - a. If yes, has the Executive Director approved a closure period of greater than 180 days? N/A ☒ YES ☐ NO ☐
9. Was District office notified of sampling event when complete removal of land facility was to have been accomplished? (not a land facility) N/A ☒ YES ☐ NO ☐
10. Were TWC samples taken during the inspection to verify completion of closure? N/A ☒ YES ☐ NO ☐

NOTE: List chain-of-custody tag numbers in comments section.

Checklist Closure-in-Progress

Date 12-12-85

Reg./~~Permit~~ No. 316.33

COMMENTS SHEET

Section _____ / Paragraph _____ : The hazardous waste container storage area was closed according to the outlined closure plan. All containers in storage were disposed of at Rollins and the resulting cleaning materials and contaminated equipment were disposed of at BFI as class II wastes. HL&P will reopen the facility as a less-than-90-day storage facility. One hazardous waste impoundment has been closed, leaving one impoundment to be closed before. HL&P-Webster will be exempt from needing a permit under the 90 day storage and wastewater treatment exemptions.

REGISTRATION NUMBER: 31633

COMPANY NAME: HOUSTON LIGHTING & POWER CO.

DA0550

TEXAS WATER COMMISSION

08-20-85

NOTICE OF REGISTRATION

INDUSTRIAL SOLID WASTE GENERATION/DISPOSAL

THIS IS NOT A PERMIT AND DOES NOT CONSTITUTE AUTHORIZATION OF ANY WASTE MANAGEMENT ACTIVITIES OR FACILITIES LISTED BELOW. REQUIREMENTS FOR SOLID WASTE MANAGEMENT ARE PROVIDED BY TEXAS ADMINISTRATIVE CODE SECTION 335 OF THE RULES OF THE TEXAS WATER COMMISSION (TWC). CHANGES OR ADDITIONS TO WASTE MANAGEMENT METHODS REFERRED TO IN THIS NOTICE REQUIRE WRITTEN NOTIFICATION TO THE TWC.

DATE OF NOTICE: 08-30-85

REGISTRATION DATE: 12-14-79

REGISTRATION NUMBER: 31633

EPA I.D. NUMBER: TXD000837369

THE REGISTRATION NUMBER PROVIDES ACCESS TO STORED INFORMATION PERTAINING TO YOUR OPERATION. PLEASE REFER TO THAT NUMBER IN ANY CORRESPONDENCE.

COMPANY NAME: HOUSTON LIGHTING & POWER CO.

MAILING ADDRESS: WEBSTER GENERATING STATION

P O BOX 1700 - W.F.MCGUIRE

HOUSTON, TEXAS 77001

GENERATING SITE LOCATION:

19301 OLD GALVESTON RD, WEBSTER, TX

CONTACT PERSON: W F MCGUIRE

PHONE: (713) 922-2186

NUMBER OF EMPLOYEES: 50 - 99

TWC DISTRICT: 07

REGISTRATION STATUS: ACTIVE

REGISTRATION TYPE: GENERATOR

HAZARDOUS WASTE STATUS: GENERATOR/TSD FACILITY

I. WASTE GENERATED:

WASTE NUMBER	DESCRIPTION	CLASS	CODE	DISPOSITION
001	OILS, WASTE	I	110450	ON-SITE / SOLD FOR RECOVERY/SECONDARY USE
002	MISC. INORGANIC SLUDGES	II	240540	OFF-SITE
003	ASBESTOS	I	170750	ON-SITE/OFF-SITE
004	BRICK, REFRACTORY (SPENT)	I	170300	ON-SITE/OFF-SITE
005	SOLVENTS, SPENT	II	910100	ON-SITE / SOLD FOR RECOVERY/SECONDARY USE

REGISTRATION NUMBER: 31607

COMPANY NAME: HOUSTON LIGHTING & POWER CO.

L

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): 0001

006 PAINT THINNER IH 910110 OFF-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): F003, F005

007 WASTEWATER, DEMINERALIZER ACID REGENERATION IH 902570 ON-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): 0002

008 WASTEWATER, DEMINERALIZER BASE REGENERATION IH 902560 ON-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): 0002

009 DEMINERALIZER REGENERANT SLUDGE II 241470 OFF-SITE

010 METAL CLEANING WASTE, INORGANIC C IH 903070 ON-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): 0002

011 SLUDGE CONTAINING INORGANICS II 241210 OFF-SITE

012 METAL CLEANING WASTE, ORGANIC II 215290 ON-SITE/OFF-SITE

013 SLUDGE CONTAINING ORGANICS II 248990 OFF-SITE

014 OILS, WASTE II 210450 ON-SITE / SOLD FOR RECOVERY/SECONDARY USE

015 OILY WASTE, MISCELLANEOUS II 283230 ON-SITE/OFF-SITE

016 OILY WASTE, MISCELLANEOUS I 183230 ON-SITE/OFF-SITE

017 SODIUM HYDROXIDE CONTAMINATED MATERIAL IH 976330 NO LONGER GENERATED

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): 0002

018 SANDBLASTING GRIT IH 973280 OFF-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): 0008

REGISTRATION (CONTINUED)

PAGE 3

REGISTRATION NUMBER: 51937

COMPANY NAME: HOUSTON LIGHTING & POWER CO.

019 MERCURY CONTAMINATED WASTE IH 978850 OFF-SITE

EPA HAZARDOUS WASTE NOS. (REFER TO 40 CFR PART 261 FOR DESCRIPTIONS): 0009


020 TANK BOTTOMS, FUEL OIL I 152920 OFF-SITE/SECONDARY USE

021 SANDBLASTING GRIT II 273280 OFF-SITE

II. SHIPPING/REPORTING: PURSUANT TO TEXAS ADMINISTRATIVE CODE SECTION 335 OF THE RULES OF THE TWC PERTAINING TO INDUSTRIAL SOLID WASTE MANAGEMENT, ISSUANCE OF MANIFESTS AND MONTHLY REPORTING ARE REQUIRED FOR OFF-SITE STORAGE/PROCESSING/DISPOSAL OF THE FOLLOWING CLASS I WASTES LISTED IN PART I.

PREPARE A MONTHLY WASTE SHIPMENT SUMMARY AND SUBMIT IT ALONG WITH THE GREEN COPY OF THE MANIFEST(S) FOR EACH MONTH THAT SHIPMENTS OF THE FOLLOWING WASTE(S) ARE MADE. NO MONTHLY WASTE SHIPMENT SUMMARY IS REQUIRED FOR MONTHS WHEN SHIPMENTS ARE NOT MADE.

003 170750 ASBESTOS
004 170300 BRICK, REFRACTORY (SPENT)
006 910110 PAINT THINNER
016 183230 OILY WASTE, MISCELLANEOUS
018 973280 SANDBLASTING GRIT
019 978850 MERCURY CONTAMINATED WASTE
020 152920 TANK BOTTOMS, FUEL OIL



III. ON-SITE WASTE MANAGEMENT FACILITIES:

FAC NO.	FACILITY	STATUS
01	SURFACE IMPOUNDMENT STORAGE OF WASTE NUMBER(S) 007, 008	ACTIVE
02	SURFACE IMPOUNDMENT STORAGE OF WASTE NUMBER(S) 010	ACTIVE
03	BOILER OR INDUSTRIAL FURNACE (ENERGY PRODUCTION) PROCESSING/DISPOSAL OF WASTE NUMBER(S) 001, 005, 014	ACTIVE

04	SURFACE IMPOUNDMENT STORAGE OF WASTE NUMBER(S) 012	ACTIVE
05	MISCELLANEOUS STORAGE CONTAINERS STORAGE OF WASTE NUMBER(S) 001, 003, 004, 005, 006, 014, 015, 016	ACTIVE

UNLESS OTHERWISE STATED ABOVE, FACILITIES ARE LOCATED
AT 19301 OLD GALVESTON RD, WEBSTER, TX
COUNTY OF HARRIS

IV. RECORDS.

- A. FOR PURPOSES OF FILING ANNUAL REPORTS PURSUANT TO TEXAS
ADMINISTRATIVE CODE SECTION 335 OF THE RULES OF THE TWC
PERTAINING TO INDUSTRIAL SOLID WASTE MANAGEMENT, RECORDS
SHOULD BE MAINTAINED FOR STORAGE, PROCESSING AND/OR DISPOSAL
OF THE FOLLOWING WASTE(S) LISTED IN PART I:

001 110450 OILS, WASTE

003 170750 ASBESTOS

004 170300 BRICK, REFRACTORY (SPENT)

005 910100 SOLVENTS, SPENT

007 902570 WASTEWATER, DEMINERALIZER ACID
REGENERATION

008 902560 WASTEWATER, DEMINERALIZER BASE
REGENERATION

010 903070 METAL CLEANING WASTE, INORGANIC

016 183230 OILY WASTE, MISCELLANEOUS



The Light company

Houston Lighting & Power, P.O. Box 1700, Houston, Texas 77001 (713) 228-9211

REC:

5/20/85
mwa

May 13, 1985

Mr. Jay Snow, P.E.
Chief, Solid Waste Section
Texas Department of Water Resources
P. O. Box 13087, Capitol Station
Austin, Texas 78711

*Since we are about to file this
with the State*

SUBJECT: CLOSURE PLANS FOR CONTAINER STORAGE AREAS

S. R. Bertron Generating Station	TDWR No. 31637
H. O. Clarke Generating Station	TDWR No. 31635
Greens Bayou Generating Station	TDWR No. 31634
P. H. Robinson Generating Station	TDWR No. 31638
Webster Generating Station	<u>TDWR No. 31633</u>
T. H. Wharton Generating Station	TDWR No. 31636

Dear Mr. Snow:

Discussions between Mr. Ray Austin, Mr. Jim Feeley (TDWR) and Dr. R. D. Groover (HL&F) indicate that, to achieve full-facility closure and generator-only status for the above-referenced facilities, closure plans for container storage areas are required even though the storage areas will continue in use under the "Accumulation Time" storage exclusion (31 TAC, Section 335.69). Transmitted herewith are three (3) copies of closure plans for the container storage areas. The current status of each generating station is briefly summarized below:

S. R. Bertron

All hazardous waste surface impoundments have been closed under TDWR-approved closure plans; an affidavit for exclusion from hazardous waste permitting is in preparation.

H. O. Clarke

All hazardous waste surface impoundments have been closed under TDWR-approved closure plans, and an affidavit of exclusion from hazardous waste permitting was submitted on March 12, 1985.

Greens Bayou

The demineralizer regenerant impoundment has been closed under a TDWR-approved closure plan. After completion of a fiberglass-lined concrete tank, the inorganic impoundment will be closed and an affidavit of exclusion from hazardous waste permitting will be submitted.

RECEIVED

JUN 17 1985

Mr. Jay Snow
May 13, 1985
Page 2

P. H. Robinson

Closure plans for three hazardous waste surface impoundments have been submitted to TDWR. Upon final approval, closure activities are scheduled to begin in the summer of 1985.

Webster


Closure plans for two hazardous waste surface impoundments have been submitted to TDWR. Upon final approval, closure activities are scheduled to begin in the summer of 1985.

T. H. Wharton

The inorganic metal cleaning impoundment has been closed under a TDWR-approved closure plan. After completion of a fiberglass-lined concrete tank, the demineralizer regenerant impoundment will be closed and an affidavit of exclusion from hazardous waste permitting will be submitted.

Should you have any questions pursuant to these container storage area closure plans, please contact Mr. R. T. Bye at 922-2201.

Sincerely,



for

W. F. McGuire, Manager
Environmental Protection Dept.

RDG/rmr
Attachments

CLOSURE PLAN
FOR
WEBSTER HAZARDOUS WASTE CONTAINER STORAGE AREA 31633

1.0 INTRODUCTION

Background - Houston Lighting & Power Company (HL&P) operates a hazardous waste container storage area at the Webster Electric Generating Station. The container storage area is located adjacent to the waste oil tank at the east end of the gas turbine building.

In accordance with the requirements of 31 TAC, Section 335, Subchapter J, and 40 CFR 264.178, this closure plan identifies the steps necessary to close the container storage facility. Following closure, the area will continue to be used as a container storage facility. Accumulation time after closure for hazardous waste will be less than 90 days.

This facility currently stores 55 gallon drums of liquid and solid hazardous and nonhazardous wastes. These wastes include refractory brick, spent solvents, paint thinner, waste oils, miscellaneous oily wastes, and sandblasting grit.

All spills and leaks are cleaned up promptly using absorbants and surfactants when necessary.

2.0 MIGRATION ASSESSMENT

Surface Water - There is little potential for surface water contamination resulting from operation of the container storage area. The area is housed on a concrete pad and all spills or leaks are cleaned up promptly.

Subsurface Migration - The floor of the area is reinforced concrete. Any material spilled or leaked onto the floor is cleaned up promptly. Potential for subsurface migration of wastes from this facility is nil.

3.0 CLOSURE PROCEDURE AND SCHEDULE

Closure of the container storage area will begin on or about August 1, 1985, (pending TDWR approval) and will consist of the following steps:

1. Prior to closure all wastes stored in the facility will be transferred off-site to a Class I disposal facility.
2. The floor will be cleaned using brushes, solvents and an 'all purpose surfactant.
3. Absorbent material will be used to pick up the surfactant.
4. The cleaned area will then be rinsed three times with water. All water will be picked up by wet-vacuum or with sponge mops.
5. All materials and liquids will be placed in a 55 gallon drum for off-site disposal.

4.0 MISCELLANEOUS PROCEDURES

Safety - Protective clothing will be worn during cleaning to provide worker protection.

Material Disposal - All materials, liquids, and protective clothing used during closure of the storage area will be placed in a 55 gallon drum and disposed of at an off-site Class I disposal facility.

5.0 NOTIFICATION

Mr. Merton J. Coloton, Supervisor, TDWR, District 7, will be notified ten (10) days prior to the commencement of closure in the event that TDWR District 7 personnel desire to observe closure activities.

6.0 CLOSURE CERTIFICATION

Following completion of all closure activities, a registered professional engineer will provide a written certification documenting that closure has been completed in accordance with this plan. This written certification will be submitted to the TDWR.

7.0 POST-CLOSURE ACTIVITIES

The storage area will continue to be used for containerized hazardous and nonhazardous wastes. An inventory of accumulation dates will be maintained to insure that hazardous wastes remain on-site for less than 90 days.

TEXAS WATER COMMISSION

Paul Hopkins, Chairman
Ralph Roming, Commissioner
John O. Houchins, Commissioner



Larry R. Soward, Executive Director
Mary Ann Hefner, Chief Clerk
James K. Rourke, Jr., General Counsel

September 23, 1985

Mr. W. F. McGuire, Manager
Environmental Protection Department
Houston Lighting and Power
P. O. Box 1700
Houston, Texas 77001

Dear Mr. McGuire:

Re: Solid Waste Registration No. 31633
Webster Generating Station
Full Facility Closure

We have completed a review of the hazardous waste facility closure plan, as detailed in your submittal of May 13, 1985. The subject closure plan describes the proposed method of closure for one drum storage area. The closure activities described in the plan have been evaluated pursuant to Title 31 of Texas Administrative Code (TAC) Sections 335.211-335.216, including the closure performance standard of 31 TAC 335.212.

This letter constitutes approval by the Executive Director of the hazardous waste facility closure plan, as described in your referenced submittal. Upon completion of the closure activities, certifications should be submitted by the owner or operator of the subject facility and by an independent Registered Professional Engineer that the hazardous waste management facility has been closed in accordance with the approved closure plan. Once the aforementioned certifications are received, we will resume processing of your Affidavit of Exclusion.

Should you have any questions regarding this evaluation, please contact Joe Gingerich of the Hazardous and Solid Waste Permits Section at AC512/463-8187 or AC512/463-8505.

Sincerely,

Larry R. Soward
Executive Director

JG:bb

cc: Bill Brown, Field Operations Liaison
TWC District 7 Office - Deer Park

SEP 27 1985

**The Light
company**

Houston Lighting & Power P.O. Box 1700 Houston, Texas 77001 (713) 228-9211

LOIS

November 8, 1985



Mr. William N. Rhea
Hazardous Waste Management
Division (GH-HO)
Environmental Protection Agency
Region 6
1201 Elm Street
Interfirst II Building - 28th Floor
Dallas, Texas 75270

SUBJECT: RCRA SECTION 3007 INFORMATION REQUEST
HOUSTON LIGHTING & POWER COMPANY FACILITIES
Cedar Bayou Generating Station #TXD000761841
Deepwater Generating Station #TXD000837427
P. H. Robinson Generating Station #TXD000837401
Webster Generating Station #TXD000837369

Dear Mr. Rhea:

Pursuant to your letter requesting additional information as required by authority of Section 3007 of RCRA, 42 U.S.C. Section 6927, we are submitting information required in Enclosure 2, Item 1, for the subject Houston Lighting & Power Company (HL&P) facilities. Part B Hazardous Waste Permit Applications and certifications of compliance with groundwater monitoring and financial assurance were submitted to the Texas Water Commission (TWC) for the subject facilities on November 6, 1985. Please note that for the remaining HL&P facilities that received your information request, hazardous waste units at the facilities have been closed and certified as per TWC approved closure plans. Additionally, for those facilities, Affidavits of Exclusion from hazardous waste permitting requirements have been submitted to the Texas Water Commission. Therefore, the information provided in this response is limited to the subject facilities.

CEDAR BAYOU GENERATING STATION

FM 1405 Near Baytown
TXD000761841

Hazardous waste land disposal units located at this facility consist of the following:

Mr. William N. Rhea
November 8, 1985
Page 2

- One clay lined earthen surface impoundment identified as the Demineralizer Regenerant Surface Impoundment utilized for the storage/equalization of demineralizer regenerant wastewater prior to treatment in a concrete wastewater treatment system and discharged under an existing NPDES/TWC permit.
- One clay lined earthen surface impoundment identified as the West Organic Metal Cleaning Impoundment utilized for the storage of demineralizer regenerant wastewater and occasional organic metal cleaning wastes generated during boiler cleaning operations.

DEEPWATER GENERATING STATION

Light Company Road at the Ship Channel
Pasadena, Texas
TXD000837427

Hazardous waste land disposal units located at this facility consist of the following:

- Two clay lined above grade surface impoundments identified as the Demineralizer Regenerant/Boiler Blowdown Surface Impoundments utilized for the storage/equalization of demineralizer regenerant and boiler blowdown wastewaters prior to treatment in a concrete wastewater treatment system and discharged under an existing NPDES/TWC permit.

P. H. ROBINSON GENERATING STATION

Highway 146
Baycliff, Texas
TXD000837401

Hazardous waste land disposal units located at this facility consist of the following:

- One clay lined earthen surface impoundment identified as the Demineralizer Regenerant Surface Impoundment utilized for the storage/equalization of demineralizer regenerant wastewater prior to being pumped to the Demineralizer Regenerant/Non-Oily Floor Drain Mixing Surface Impoundment discussed below.
- One clay lined earthen surface impoundment identified as the Demineralizer Regenerant/Non-Oily Floor Drain Mixing Impoundment utilized for the storage/equalization of demineralizer regenerant wastewater and non-oily floor

Mr. William N. Rhea

November 8, 1985

Page 3

drainage prior to treatment in a concrete wastewater treatment system and discharged under an existing NPDES/TWC permit.

- One clay lined earthen surface impoundment identified as the Inorganic Metal Cleaning Surface Impoundment utilized for the occasional storage/equalization of inorganic metal cleaning waste associated with boiler cleaning operations. This wastewater is then pumped to a concrete wastewater treatment system where it is treated and discharged under an existing NPDES/TWC permit.

WEBSTER GENERATING STATION
19301 Old Galveston Road
Webster, Texas 77598
TXD0008377369

Hazardous waste land disposal units located at this facility consist of the following:

- One clay lined earthen surface impoundment identified as the Demineralizer Regenerant Surface Impoundment utilized for the storage/equalization of demineralizer regenerant wastewater prior to treatment in a concrete wastewater treatment system and discharged under an existing NPDES/TWC permit.
- One clay lined earthen surface impoundment identified as the Inorganic Metal Cleaning Surface Impoundment utilized for the occasional storage/equalization of inorganic metal cleaning wastewater associated with boiler cleaning operations. This wastewater is then pumped to a concrete wastewater treatment system where it is treated and discharged under an existing NPDES/TWC permit.


Closure plans for hazardous waste surface impoundments at Webster and P. H. Robinson were approved by the TWC on August 6, 1985. Closure plans for Cedar Bayou and Deepwater were submitted to the TWC on August 2, 1985, and approval is expected shortly. Of the hazardous waste disposal units discussed above, one surface impoundment at the Webster station (inorganic metal cleaning surface impoundment) has been closed and certified (November 4, 1985), and one surface impoundment at the P. H. Robinson station (inorganic metal cleaning surface impoundment), is currently undergoing closure. The remaining surface impoundments will undergo closure in 1986.

Houston Lighting & Power Company

Mr. William N. Rhea
November 8, 1985
Page 4

Should you have any questions pursuant to this matter,
please contact Mr. R. T. Bye at 713/922-2201.

Sincerely,

A handwritten signature in black ink, appearing to read 'W. B. McGuire', written over a horizontal line.

W. B. McGuire
Manager, Environmental Protection
Department

RTB/rmr
Attachments - 4 site topographic maps

cc: Mr. Minor Hibbs; Hazardous & Solid Waste Division, TWC

The Light company

Houston Lighting & Power P.O. Box 1700 Houston, Texas 77001 (713) 228-9211

February 8, 1985

Mr. Ray Henry Austin, Head
Storage and Processing Facilities Unit
Solid Waste Section
Texas Department of Water Resources
P.O. Box 13087, Capitol Station
Austin, Texas 78711


Dear Mr. Austin:

SUBJECT: REVISED PART A APPLICATION
WEBSTER GENERATING STATION - TDWR 31633

The August 1980 Part A application for Houston Lighting & Power Company's Webster Generating Station has been updated. The attached revisions reflect current hazardous waste management practices at this facility.

Please call R. D. Groover at (713) 922-2195 if you have any questions concerning these revisions.

Sincerely,



W. F. McGuire, Manager
Environmental Protection Department

BAD/pm/L2

Attachments

cc: M. J. Coloton, TDWR District 7

Webster Generating Station Revised Part A Application

Appropriate tables/pages (attached) of the Part A application have been revised to reflect current hazardous waste management practices at Webster Generating Station.

The Part A application prepared in August 1980 listed several wastes/facility components which have been removed in the revised Part A. These wastes/components are discussed below:

1. Demineralizer Regenerant Inorganic Sludge

This sludge accumulates at the bottom of the demineralizer impoundment from storage of demineralizer regenerant. Based on EP toxicity analyses submitted to your office on April 8, 1981 (letter attached), this waste has been declassified to a Class II waste (TWC 241470).

2. Metal Cleaning and Other Inorganic Sludge

This sludge accumulates at the bottom of the inorganic impoundment from storage of hydrochloric acid boiler and equipment cleanings, and boiler blowdown. Based on EP toxicity analyses submitted to your office on April 8, 1981 (letter attached), this waste has been declassified to a Class II waste (TWC 241210).

3. Metal Cleaning Organic Acids/Metal Cleaning Organic Acids Collection Pond

This waste is generated from ammoniated citric acid or hydroxyacetic-formic acid boiler and equipment cleanings. It is stored in an impoundment prior to being injected in an energy-producing boiler for incineration. Based on EP toxicity analyses submitted to your office on April 8, 1981 (letter attached), this waste has been declassified to a Class II waste (TWC 215290). The organic impoundment has, therefore, never received hazardous waste.

4. Metal Cleaning Organic Sludge

This sludge accumulates at the bottom of the organic impoundment. Based on EP toxicity analyses submitted to your office on April 8, 1981 (letter attached), this waste has been declassified to a Class II waste (TWC 248990).

5. Chemical Waste Treatment System Sludge/Chemical Waste Treatment System & Sand Drying Beds


A concrete chemical waste treatment system is used to treat demineralizer regenerant, inorganic metal cleaning waste (when produced), and boiler blowdown prior to NPDES discharge. The sludge which accumulates in the settling chamber of the treatment system is pumped to sand drying beds for dewatering and periodic off-site disposal. Based on EP toxicity analyses submitted to your office on February 23, 1981 (letter attached), this sludge has been declassified to a Class II waste (TWC 240540).

6. Waste Oil and Sludge/Waste Oil and Sludge Collection Facility

Oily sludge generated from the oily waste treatment system is classified as a Class I nonhazardous or Class II waste, depending on the amount of oil present in the sludge. The attached EP toxicity analyses of oily waste treatment system sludge indicate that no hazardous constituents are present.

7. Asbestos in Insulation

Insulation containing asbestos is classified as a Class I non-hazardous waste (TWC 170750). Asbestos, originally listed on the Part A application, has been delisted from the hazardous waste list (CFR 40.261).



WEBSTER GENERATING STATION

Table III-I Hazardous Wastes and Management Activities

Verbal Description of Waste	TDWR Sequence Number	TDWR Waste Code Number	EPA Hazard Code	EPA Hazardous Waste No.	Waste Management Activities (Check applicable items)				Estimated 1984 Annual Quantity Generated (lbs)	SIC Code and Process
					Off-Site Disposal	On-Site				
						Storage ¹	Processing ²	Disposal		
Demineralizer Acid and Base Regeneration Wastewater	007 008	902570 902560	C	D002		X	X		7.93X10 ^{7a}	4911 - Treatment Boiler & Cor
Inorganic Metal Cleaning Waste	010	903070	C	D002		X	X		0 ^b	4911 - denser C'
Spent Solvents	005	910100	I	D001 D001	X	X			0	4911 - Degreasing
Paint Thinner	006	910110	I,T	F003,F005	X	X			0.79X10 ³	4911 - Painting
Sandblast Grit		973280	E	D008	X	X			0	4911 - Painting
Liquid Paint Waste		910650	E	D008	X	X			0.89X10 ³	4911 - Painting

a Total quantity discharged from demineralizer impoundment under NPDES permit (includes boiler blowdown).

b Inorganic metal cleaning waste is generated infrequently. Quantity generated in 1980 was approximately 1.25X10⁶ lbs.

c Projected quantity to be generated in 1985 is approximately 1X10⁴ lbs.

¹ "Storage" means the holding of solid waste for a temporary period, at the end of which the waste is processed, disposed of, or stored elsewhere.

² "Processing" means the extraction of materials, transfer, volume reduction, conversion to energy, or other separation and preparation of solid waste for reuse or disposal, including the treatment or neutralization of hazardous waste, designed to change the physical, chemical, or biological character or composition of any hazardous waste so as to neutralize such waste, or so as to recover energy or material from the waste or so as to render such waste non-hazardous or less hazardous; safer for transport, store or dispose of; or amenable for recovery, amenable for storage, or reduced in volume. The "transfer" of solid waste for reuse or disposal as used above, does not include the actions of a transporter in conveying or transporting solid waste by truck, ship, pipeline, or other means. Unless the Executive Director determines that regulation of such activity is necessary to protect human health or the environment, the definition of "processing" does not include activities relating to those materials exempted by the Administrator of the EPA pursuant to the federal Solid Waste Disposal Act, as amended by the Resource Conservation and Recovery Act, 42 U.S.C. 6901 et seq., as amended.

WEBSTER GENERATING STATION

Table III-2 Hazardous Waste Management Facility Component Summary Sheet

Verbal Description of Waste

Spent Solvents

Process (see last column in Table III-1)

Degreasing

TDWR Sequence Number of Waste (if assigned)

005

Indicate the facility components used for storage/processing/disposal of the above-specified waste by entering the number of such facility components by which this waste is managed.

☐ Lagoon/Pond (unlined)

☐ Landfarm

☐ Lagoon/Pond (lined)

☐ Landspreading Area

☐ Basin (earthen, above-grade lined)

☐ Spray Irrigation Area

☐ Basin (earthen, above-grade unlined)

☐ Flood Irrigation Area

☐ Basin (earthen, below-grade lined)

☐ Septic Tank/Drain Field

☐ Basin (earthen, below-grade unlined)

☐ Injection Well

☐ Basin (concrete, above-grade lined)

☐ Tank (surface storage)

☐ Basin (concrete, above-grade unlined)

☐ Tank (sub-surface storage)

☐ Basin (concrete, below-grade lined)

☐ Tank (surface processing)

☐ Basin (concrete, below-grade unlined)

☐ Tank (sub-surface processing)

☐ Basin (other)

☐ Tank (other)

☐ Pit (lined)

1 Drum Storage Area (open)

☐ Pit (unlined)

☐ Other Container Storage Area

☐ Incinerator

☐ Other Container Storage Area

☐ Open Controlled Incineration Area

☐ Other Container Storage Area (specify type of
of container_____

☐ Boiler (energy-producing)

_____)

☐ Landfill (sanitary)

☐ Waste Pile Storage Area

☐ Landfill (surface, open)

1 Other (specify Mixed with

☐ Landfill (other)

waste oil for pickup by a
waste oil recycling firm

Table III-2 Hazardous Waste Management Facility Component Summary Sheet

Verbal Description of Waste

Paint Thinner

Process (see last column in Table III-1)

Painting

TDWR Sequence Number of Waste (if assigned) 006

Indicate the facility components used for storage/processing/disposal of the above-specified waste by entering the number of such facility components by which this waste is managed.

- | | |
|--|--|
| <input type="checkbox"/> Lagoon/Pond (unlined) | <input type="checkbox"/> Landfarm |
| <input type="checkbox"/> Lagoon/Pond (lined) | <input type="checkbox"/> Landspreading Area |
| <input type="checkbox"/> Basin (earthen, above-grade lined) | <input type="checkbox"/> Spray Irrigation Area |
| <input type="checkbox"/> Basin (earthen, above-grade unlined) | <input type="checkbox"/> Flood Irrigation Area |
| <input type="checkbox"/> Basin (earthen, below-grade lined) | <input type="checkbox"/> Septic Tank/Drain Field |
| <input type="checkbox"/> Basin (earthen, below-grade unlined) | <input type="checkbox"/> Injection Well |
| <input type="checkbox"/> Basin (concrete, above-grade lined) | <input type="checkbox"/> Tank (surface storage) |
| <input type="checkbox"/> Basin (concrete, above-grade unlined) | <input type="checkbox"/> Tank (sub-surface storage) |
| <input type="checkbox"/> Basin (concrete, below-grade lined) | <input type="checkbox"/> Tank (surface processing) |
| <input type="checkbox"/> Basin (concrete, below-grade unlined) | <input type="checkbox"/> Tank (sub-surface processing) |
| <input type="checkbox"/> Basin (other) | <input type="checkbox"/> Tank (other) |
| <input type="checkbox"/> Pit (lined) | <input checked="" type="checkbox"/> 1 Drum Storage Area (open) |
| <input type="checkbox"/> Pit (unlined) | <input type="checkbox"/> Other Container Storage Area |
| <input type="checkbox"/> Incinerator | <input type="checkbox"/> Other Container Storage Area |
| <input type="checkbox"/> Open Controlled Incineration Area | <input type="checkbox"/> Other Container Storage Area (specify type of container _____) |
| <input type="checkbox"/> Boiler (energy-producing) | _____) |
| <input type="checkbox"/> Landfill (sanitary) | <input type="checkbox"/> Waste Pile Storage Area |
| <input type="checkbox"/> Landfill (surface, open) | <input type="checkbox"/> Other (specify _____) |
| <input type="checkbox"/> Landfill (other) | _____) |

WEBSTER GENERATING STATION

Table III-2 Hazardous Waste Management Facility Component Summary Sheet

Verbal Description of Waste

Demineralizer Acid and Base Regeneration Wastewater

Process (see last column in Table III-1)

Water Treatment

 TDWR Sequence Number of Waste (if assigned) | |

007, 008

Indicate the facility components used for storage/processing/disposal of the above-specified waste by entering the number of such facility components by which this waste is managed.

___ Lagoon/Pond (unlined)

Landfarm

1 Lagoon/Pond (lined)

— Landspredding Area

___ Basin (earthen, above-grade lined)

— Spray Irrigation Area

____ Basin (earthen, above-grade unlined)

____ Flood Irrigation Area

___ Basin (earthen, below-grade lined)

____ Septic Tank/Drain Field

___ Basin (earthen, below-grade unlined)

___ Injection Well

___ Basin (concrete, above-grade lined)

 Tank (surface storage)

____ Basin (concrete, above-grade unlined)

____ Tank (sub-surface storage)

___ Basin (concrete, below-grade lined)

____ Tank (surface processing)

____ Basin (concrete, below-grade unlined)

___ Tank (sub-surface processing)

___ Basin (other)

___ Tank (other)

____ Pit (lined)

 Drum Storage Area

___ Pit (unlined)

 Other Container Storage Area

___ Incinerator

___ Other Container Storage Area

___ Open Controlled Incineration Area

____ Other Container Storage Area (specify type of
of container_____)

___ **Boiler (energy-producing)**

_____)

___ Landfill (sanitary)

___ Waste Pile Storage Area

___ Landfill (surface, open)

____ Other (specify _____)

____ Landfill (other)

_____)

WEBSTER GENERATING STATION

Table III-2 Hazardous Waste Management Facility Component Summary Sheet

Verbal Description of Waste Inorganic Metal
Cleaning Waste
Process (see last column in Table III-1) Boiler & Condenser Cleaning
TDWR Sequence Number of Waste (if assigned) 010

Indicate the facility components used for storage/processing/disposal of the above-specified waste by entering the number of such facility components by which this waste is managed.

- | | |
|--|--|
| <input type="checkbox"/> Lagoon/Pond (unlined) | <input type="checkbox"/> Landfarm |
| <input checked="" type="checkbox"/> Lagoon/Pond (lined) | <input type="checkbox"/> Landspreading Area |
| <input type="checkbox"/> Basin (earthen, above-grade lined) | <input type="checkbox"/> Spray Irrigation Area |
| <input type="checkbox"/> Basin (earthen, above-grade unlined) | <input type="checkbox"/> Flood Irrigation Area |
| <input type="checkbox"/> Basin (earthen, below-grade lined) | <input type="checkbox"/> Septic Tank/Drain Field |
| <input type="checkbox"/> Basin (earthen, below-grade unlined) | <input type="checkbox"/> Injection Well |
| <input type="checkbox"/> Basin (concrete, above-grade lined) | <input type="checkbox"/> Tank (surface storage) |
| <input type="checkbox"/> Basin (concrete, above-grade unlined) | <input type="checkbox"/> Tank (sub-surface storage) |
| <input type="checkbox"/> Basin (concrete, below-grade lined) | <input type="checkbox"/> Tank (surface processing) |
| <input type="checkbox"/> Basin (concrete, below-grade unlined) | <input type="checkbox"/> Tank (sub-surface processing) |
| <input type="checkbox"/> Basin (other) | <input type="checkbox"/> Tank (other) |
| <input type="checkbox"/> Pit (lined) | <input type="checkbox"/> Drum Storage Area |
| <input type="checkbox"/> Pit (unlined) | <input type="checkbox"/> Other Container Storage Area |
| <input type="checkbox"/> Incinerator | <input type="checkbox"/> Other Container Storage Area |
| <input type="checkbox"/> Open Controlled Incineration Area | <input type="checkbox"/> Other Container Storage Area (specify type of
of container _____) |
| <input type="checkbox"/> Boiler (energy-producing) | _____) |
| <input type="checkbox"/> Landfill (sanitary) | <input type="checkbox"/> Waste Pile Storage Area |
| <input type="checkbox"/> Landfill (surface, open) | <input type="checkbox"/> Other (specify _____) |
| <input type="checkbox"/> Landfill (other) | _____) |

Table III-2 Hazardous Waste Management Facility Component Summary Sheet

Verbal Description of Waste

Sandblast Grit

Process (see last column in Table III-1)

Painting

TDWR Sequence Number of Waste (if assigned)

Indicate the facility components used for storage/processing/disposal of the above-specified waste by entering the number of such facility components by which this waste is managed.

- | | |
|--|---|
| <input type="checkbox"/> Lagoon/Pond (unlined) | <input type="checkbox"/> Landfarm |
| <input type="checkbox"/> Lagoon/Pond (lined) | <input type="checkbox"/> Landspreading Area |
| <input type="checkbox"/> Basin (earthen, above-grade lined) | <input type="checkbox"/> Spray Irrigation Area |
| <input type="checkbox"/> Basin (earthen, above-grade unlined) | <input type="checkbox"/> Flood Irrigation Area |
| <input type="checkbox"/> Basin (earthen, below-grade lined) | <input type="checkbox"/> Septic Tank/Drain Field |
| <input type="checkbox"/> Basin (earthen, below-grade unlined) | <input type="checkbox"/> Injection Well |
| <input type="checkbox"/> Basin (concrete, above-grade lined) | <input type="checkbox"/> Tank (surface storage) |
| <input type="checkbox"/> Basin (concrete, above-grade unlined) | <input type="checkbox"/> Tank (sub-surface storage) |
| <input type="checkbox"/> Basin (concrete, below-grade lined) | <input type="checkbox"/> Tank (surface processing) |
| <input type="checkbox"/> Basin (concrete, below-grade unlined) | <input type="checkbox"/> Tank (sub-surface processing) |
| <input type="checkbox"/> Basin (other) | <input type="checkbox"/> Tank (other) |
| <input type="checkbox"/> Pit (lined) | <input type="checkbox"/> Drum Storage Area |
| <input type="checkbox"/> Pit (unlined) | <input type="checkbox"/> Other Container Storage Area |
| <input type="checkbox"/> Incinerator | <input type="checkbox"/> Other Container Storage Area |
| <input type="checkbox"/> Open Controlled Incineration Area | <input checked="" type="checkbox"/> Other Container Storage Area (specify type of
of container <u>(covered bins)</u>) |
| <input type="checkbox"/> Boiler (energy-producing) | <input type="checkbox"/> _____) |
| <input type="checkbox"/> Landfill (sanitary) | <input type="checkbox"/> Waste Pile Storage Area |
| <input type="checkbox"/> Landfill (surface, open) | <input type="checkbox"/> Other (specify _____) |
| <input type="checkbox"/> Landfill (other) | <input type="checkbox"/> _____) |

WEBSTER GENERATING STATION

Table III-2 Hazardous Waste Management Facility Component Summary Sheet

Verbal Description of Waste

Liquid Paint Wastes

Process (see last column in Table III-1)

Painting

TDWR Sequence Number of Waste (if assigned)

Indicate the facility components used for storage/processing/disposal of the above-specified waste by entering the number of such facility components by which this waste is managed.

<input type="checkbox"/> Lagoon/Pond (unlined)	<input type="checkbox"/> Landfarm
<input type="checkbox"/> Lagoon/Pond (lined)	<input type="checkbox"/> Landspreading Area
<input type="checkbox"/> Basin (earthen, above-grade lined)	<input type="checkbox"/> Spray Irrigation Area
<input type="checkbox"/> Basin (earthen, above-grade unlined)	<input type="checkbox"/> Flood Irrigation Area
<input type="checkbox"/> Basin (earthen, below-grade lined)	<input type="checkbox"/> Septic Tank/Drain Field
<input type="checkbox"/> Basin (earthen, below-grade unlined)	<input type="checkbox"/> Injection Well
<input type="checkbox"/> Basin (concrete, above-grade lined)	<input type="checkbox"/> Tank (surface storage)
<input type="checkbox"/> Basin (concrete, above-grade unlined)	<input type="checkbox"/> Tank (sub-surface storage)
<input type="checkbox"/> Basin (concrete, below-grade lined)	<input type="checkbox"/> Tank (surface processing)
<input type="checkbox"/> Basin (concrete, below-grade unlined)	<input type="checkbox"/> Tank (sub-surface processing)
<input type="checkbox"/> Basin (other)	<input type="checkbox"/> Tank (other)
<input type="checkbox"/> Pit (lined)	<input checked="" type="checkbox"/> 1 Drum Storage Area (open)
<input type="checkbox"/> Pit (unlined)	<input type="checkbox"/> Other Container Storage Area
<input type="checkbox"/> Incinerator	<input type="checkbox"/> Other Container Storage Area
<input type="checkbox"/> Open Controlled Incineration Area	<input type="checkbox"/> Other Container Storage Area (specify type of of container _____)
<input type="checkbox"/> Boiler (energy-producing)	_____)
<input type="checkbox"/> Landfill (sanitary)	<input type="checkbox"/> Waste Pile Storage Area
<input type="checkbox"/> Landfill (surface, open)	<input type="checkbox"/> Other (specify _____)
<input type="checkbox"/> Landfill (other)	_____)

Webster Generating Station
Table III-4 Hazardous Waste Facility Components List

Facility Component Name	TDWR Seq. No.	Status			Design Capacity			Number of Years Utilized	Date in Service
		Inactive	Active	Proposed	(cu yds)	(gal)	(lbs)		
Lagoon/Pond (lined)	01		X			372,000		14	1970
Verbal Description: Clay lined pond for the collection of demineralizer regeneration wastes prior to treatment Treated wastewater is discharged via NPDES permit.									
Lagoon/Pond (lined)	02		X			270,000		7	1977
Verbal Description: Clay lined pond for the collection of metal cleaning inorganic acid wastes from boiler and equipment cleaning operations prior to treatment. Treated wastewater is discharged via NPDES permit.									
Verbal Description:									
Drum Storage Area (open)	05		X			NA		4	1980
Verbal Description: Drum storage area for the collection of waste solvents, waste paint thinners, and liquid paint prior to off-site disposal.									
Other Container Storage Area			X			NA		NA	NA
Verbal Description: Covered bins for storage of blasting material prior to off-site disposal									
Verbal Description:									

Attachment G

Webster Generating Station

Process Description for Hazardous Waste Streams

1. Demineralizer Acid and Base Regenerant Wastewater (EPA Hazard Code C)

Demineralizer regenerant waste is collected in the demineralizer impoundment. The waste is then pumped to the chemical waste treatment system for pH adjustment and suspended solids removal. Treated wastewater is discharged in accordance with the NPDES permit.

2. Inorganic Metal Cleaning Waste (EPA Hazard Code C)

Inorganic metal cleaning waste is collected in the inorganic impoundment. The waste is then pumped to the chemical waste treatment system for pH adjustment, suspended solids and metals removal. Treated wastewater is discharged in accordance with the NPDES permit.

3. Spent Solvents (EPA Hazard Code I)

Spent solvents are collected in drums or mixed with waste oil for recycling.

4. Paint Thinner (EPA Hazard Code I, T)

Paint thinner waste is collected in drums. These drums are temporarily stored prior to off-site disposal.

5. Sandblast Grit (EPA Hazard Code E)

Waste blasting material is collected in bins for temporary storage prior to off-site disposal.

6. Liquid Paint Wastes (EPA Hazard Code E)

Liquid paint waste is collected in drums. These drums are temporarily stored prior to off-site disposal.



**ANALYTICAL
PETROLEUM
RESEARCH**

Laboratories

HOUSTON LIGHTING & POWER
P. O. BOX 1700
HOUSTON, TEXAS 77001
ATTENTION: MS. ELLEN ZAMPELLO
=====

DATE: SEPTEMBER 25, 1984
INVOICE NO.: 10582
CERTIFICATE NO.: 14438
=====

SAMPLE DESCRIPTION: WEB FLOOR DRAIN OIL SUMP (Waste Oil)

SAMPLE DATE: SEPTEMBER 7, 1984
DATE RECEIVED: SEPTEMBER 7, 1984

IGNITABILITY (FLASH POINT) > 212 OF
CORROSIVITY pH = 6.48
REACTIVITY NONE

E P TOXICITY:

<u>ANALYSIS</u> =====	<u>RESULTS MG/L</u> =====
ARSENIC	<0.02
BARIUM	<0.3
CADMIUM	<0.01
CHROMIUM	<0.1

<u>ANALYSIS</u> =====	<u>RESULTS MG/L</u> =====
LEAD	<0.1
MERCURY	<0.005
SELENIUM	<0.01
SILVER	<0.01

A P R LABORATORIES

Sammy Russo
Sammy Russo

RECEIVED

SEP 28 1984

DATE RECEIVED



Laboratories

**ANALYTICAL
PETROLEUM
RESEARCH**

HOUSTON LIGHTING & POWER
P. O. BOX 1700
HOUSTON, TEXAS 77001
ATTENTION: MS. ELLEN ZAMPELLO

DATE: SEPTEMBER 25, 1984
INVOICE NO.: 10582
CERTIFICATE NO.: 14439

SAMPLE DESCRIPTION: WEB GAS TURBINE OIL TRAP (Waste Oil)

SAMPLE DATE: SEPT. 7, 1984

DATE RECEIVED: SEPT. 7, 1984

IGNITABILITY (FLASH POINT)

> 212 °F

CORROSIVITY

pH = 5.15

REACTIVITY

NONE

E P TOXICITY:

ANALYSIS =====	RESULTS MG/L =====
ARSENIC	<0.02
BARIUM	<0.3
CADMIUM	<0.01
CHROMIUM	<0.1

ANALYSIS =====	RESULTS MG/L =====
LEAD	<0.1
MERCURY	<0.005
SELENIUM	<0.01
SILVER	<0.01

ENDRIN <0.02

LINDANE <0.4

METHOXYCHLOR <2

TOXAPHENE <0.2

2,4 -DICHLOROPHENOXYACETIC ACID (2, 4-D) <1

2,4,5-TP (SILVEX) <1

RECEIVED

SEP 28 1984

WATER ANALYSIS DIV.

A P R LABORATORIES

Sammy Russo
Sammy Russo
4324 Highway 3

Suite 129

Dickinson, Texas 77539

Phone (713) 337-6700

31633

TEXAS DEPARTMENT OF WATER RESOURCES

1700 N. Congress Avenue
Austin, Texas

TEXAS WATER DEVELOPMENT BOARD

Louis A. Beecherl, Jr., Chairman
George W. McCleskey, Vice Chairman
Glen E. Roney
W. O. Bankston
Lonnie A. "Bo" Pilgrim
Louie Welch



Charles E. Nemir
Executive Director
June 12, 1984

TEXAS WATER COMMISSION

Paul Hopkins, Chairman
Lee B. M. Biggart
Ralph Roming

Kimble *rk*
Ferguson *SE*
Barker *EB*
Dixon *for*

Mr. W.F. McGuire, Manager
Environmental Protection Department
Houston Lighting & Power
P.O. Box 1700
Houston, Texas 77001

Dear Mr. McGuire:

Re: RCRA Financial Assurance
TDWR Registration Numbers 31632, 31633, 31634, 31635, 31636, 31637
31638, and 31639

The documents submitted for financial assurance of the above referenced facility(ies) have been reviewed and determined to be complete and in accordance with the applicable regulations. Any revisions or adjustments involving financial assurance of the facility(ies) should be submitted in writing to the attention of Mr. Russell Kimble of our Enforcement and Field Operations Division.

Sincerely,

Bryan W. Dixon, P.E., Chief
Solid Waste and Spill Response Section
Enforcement and Field Operations Division

RSK:jr

ccs: Jay Snow, Permits Division, Industrial Solid Waste Section
Texas Department of Water Resources District 7 Office



The Light company

Houston Lighting & Power P.O. Box 1700 Houston, Texas 77001 (713) 228-9211

May 29, 1984

Mr. Paul S. Lewis, Geologist
Enforcement & Field Operations Division
Texas Department of Water Resources
P. O. Box 13087, Capitol Station
Austin, Texas 78711

SUBJECT: GROUND-WATER QUALITY ASSESSMENT PLAN, IMPLEMENTATION STUDIES
S. R. Bertron Generating Station, TDWR Reg. No. 31637
H. O. Clarke Generating Station, TDWR Reg. No. 31635
Deepwater Generating Station, TDWR Reg. No. 31632
Greens Bayou Generating Station, TDWR Reg. No. 31634
P. H. Robinson Generating Station, TDWR Reg. No. 31638
Webster Generating Station, TDWR Reg. No. [REDACTED]
T. H. Wharton Generating Station, TDWR Reg. No. 31636

Dear Mr. Lewis:

Enclosed are two (2) copies each of the ground-water quality plan implementation studies for the above-referenced facilities. Please contact E. A. Feith (922-2205) or R. D. Groover (922-2195) if you have any questions concerning this material. As discussed with you previously, Mr. Feith and Mr. Groover as well as representatives of Underground Resource Management, Inc. plan to meet to discuss the reports with you on Thursday, May 31, 1984 at 10:00 a.m.

Sincerely,



W. F. McGuire, Manager
Environmental Protection Department

RDG/bwt

Enclosures

31633

PS Form 3811, July 1

• **SENDER:** Complete Items 1, 2, 3, and 4.
Add your address in the "RETURN TO" space on reverse.

(CONSULT POSTMASTER FOR FEES)

1. The following service is requested (check one).

☐ Show to whom and date delivered

HOUSTON LIGHTING & POWER CO. 316
WEBSTER GENERATING STATION
P O BOX 1700 - W.F.MCGUIRE
HOUSTON, TEXAS 77001
ATTN: W F MCGUIRE

4. TYPE OF SERVICE: ☐ REGISTERED ☐ INSURED ☐ CERTIFIED ☐ COD ☐ EXPRESS MAIL

ARTICLE NUMBER: 12281

(Always obtain signature of addressee or agent)

I have received the article described above.

SIGNATURE ☐ Addressee ☒ Agent *L. J. Seppala*

5. DATE OF DELIVERY: MAR 29 1984

6. POSTMARK (only for registered mail)

6. ADDRESSEE'S ADDRESS (only if requested)

7. UNABLE TO DELIVER BECAUSE:

7a. EMPLOYEE'S INITIALS

RETURN RECEIPT

• GPO: 1982-379-583

**McClelland engineers, inc. / geotechnical consultants**6100 HILLCROFT / HOUSTON, TEXAS 77081
TEL 713 / 772-3701 / TELEX 762-447

SUBJECT: Monitor Well Installation
Webster Electric Generating Station
Webster, Texas

DATE: July 22, 1982

REPORT NO.: 0182-0119-1

TO: Houston Lighting & Power Company
12301 Kurland Drive
Houston, Texas 77034

Attention: Mr. E. A. Feith

Introduction

Presented here is the report of our installation of monitor wells at your Webster Electric Generating Station in Webster, Texas. This work was performed in general accordance with our proposal dated June 1, 1982 and was verbally authorized by Mr. James Mertink on May 4, 1982.

Field Services

Four monitor wells were installed in the Webster Generating Station at the locations shown on Plate 1. The locations were selected by HL&P and were confirmed by the Texas Department of Water Resources as being acceptable. Holes for the wells were drilled with a medium-duty truck-mounted rig using wet rotary techniques. A geotechnical engineer logged the well holes based on soil cuttings and drilling characteristics. A description of the soils encountered is included in the next section of this report.

As shown on Plate 2, a monitor well consists of a 4-in.-diameter PVC riser pipe installed in a 7-in.-diameter hole. The PVC riser pipe is provided with 0.02-in.-wide slots and is surrounded by filter sand in the monitoring zone. A 1-ft-thick layer of bentonite is placed on top of the sand filter. Soil cuttings from the boring are backfilled in the annulus from the top of the bentonite to about 4 ft below ground surface. Cement grout is placed to fill the remaining annulus to the ground surface. The well is developed by blowing the water and any sediment out of the riser pipe with compressed air.

General Soil Conditions

The general soil stratigraphy at each well location as determined by logging the soil cuttings in the returning wash water and by observing the drilling characteristics is given below.

Monitor Well W-1. Clay was observed to a depth of 25 ft. Underlying the clay, silty clay with seams and thin layers of sandy silt and clayey silt was found to the bottom of the hole to 29-ft depth.

Monitor Well W-2. Fill consisting of clay and silty clay with calcareous deposits was observed to a depth of 12 ft. Circulation of drilling fluid was lost at 7-ft depth due to a thin layer of highly permeable organic silt. Natural clay is present from 12-ft to the 30-ft depth drilled; the drilling indicates silt seams from 24-ft to 27-ft depth.

Monitor Well W-3. A clay profile was observed from the ground surface to the 30-ft depth of the hole. The clay was interbedded with silt from 21-ft to 22-ft depth.

Monitor Well W-4. Clay was observed to a depth of 17.5 ft and from

17.5 ft depth.

*

*

*

The following illustrations are attached and complete this report:

Plate 1

Site Plan

Plate 2


Monitor Well Installation Data


McCLELLAND ENGINEERS, INC.

Edward J. Ulrich, Jr.
Edward J. Ulrich, Jr., P.E.
Engineer Manager

JAM/EJU/dka


Copies Submitted: (6)






LEGEND:

② Monitor Wells



SITE PLAN
Webster Generating Station



Well No.	Installation Date	L_1 , Ft	L_2 , Ft	Granular Layer		
				Description	From, Ft	To, Ft
4 A	5-20-82	18	28	Clayey Silt Seams	25	29
2	5-18-82	18	29	Silt Seams	24	27
3	5-17-82	18	28	Silt Seams	21	22
1 A	5-18-82	10	21	Sandy Silt	17.5	19.5

MONITOR WELL INSTALLATION DATA
Webster Generating Station

FORM SUBMITTED

By: _____

Date: _____

MAJOR FACILITIES STATUS SHEET
Initial _____ Update _____

0484 ✓

4/84/212

ID No.: TxDOW 837349 Registration/Permit No.: 31633

Facility Name: HL+P Webster Station District No.: Dist 7

1. Ground Water Monitoring Status

Detection Assessment _____ Waiver NA _____

2. Ground Water Monitoring Well System

a. Evaluated? NA _____ NE _____ DATE EVAL'D _____
b. Adequate? YES ✓ _____ NO _____

3. Ground Water Sampling, Analysis and Evaluation Program

a. Evaluated? NA _____ NE _____ DATE EVAL'D _____
b. Adequate? YES ✓ _____ NO _____

4. Notice of Significant Increase in Parameter Concentrations

Submitted? NA _____ NO _____ DATE SUB'D Oct 1984

5. Ground Water Quality Assessment Report

will submit May 84

a. Submitted? NA _____ NO _____ DATE SUB'D _____
b. Evaluated? NE _____ DATE EVAL'D _____
c. Adequate? YES _____ NO _____
d. Showed hazardous waste constituents in ground water?
YES _____ NO _____

6. Waiver Demonstration

a. Evaluated? NA ✓ _____ NE _____ DATE EVAL'D _____
b. Adequate? YES _____ NO _____

7. Ground Water Monitoring Records

a. Evaluated? NA _____ NE _____ DATE EVAL'D _____
b. Adequate? YES ✓ _____ NP _____

ID # _____

8. Activities Subject to Closure/Post-Closure

Landfill _____	Incinerator _____
Surface Impoundment <u>✓</u>	Waste Pile _____
Land Treatment/Application _____	Other (Specify) _____

9. Closure Plan

a. Evaluated? NE _____ DATE EVAL'D _____
 b. Adequate? YES ✓ NO _____

10. Closure Cost Estimate

a. Evaluated? NA _____ NE _____ DATE EVAL'D _____
 b. Adequate? YES ✓ NO _____
 c. Amount: \$ _____ UNKNOWN _____

11. Closure Assurance Instrument(s)

a. Evaluated? NA _____ NE ✓ DATE EVAL'D _____
 b. Adequate? YES _____ NO _____ NO INSTRUMENT ✓
 c. Type(s):

TRUST FUND _____
 FINANCIAL BOND _____
 PERFORMANCE BOND _____
 LETTER OF CREDIT _____

INSURANCE _____
 FINANCIAL TEST _____
 CORPORATE GUARANTEE _____
 STATE GUARANTEE _____
 OTHER STATE MECHANISM _____

12. Post-Closure Plan

a. Evaluated? NA ✓ NE _____ DATE EVAL'D _____
 b. Adequate? YES _____ NO _____

13. Post-Closure Cost Estimate

a. Evaluated? NA ✓ NE _____ DATE EVAL'D _____
 b. Adequate? YES _____ NO _____
 c. Amount: \$ _____ UNKNOWN _____

14. Post-Closure Assurance Instrument(s)

a. Evaluated? NA ✓ NE _____ DATE EVAL'D _____
 b. Adequate? YES _____ NO _____ NO INSTRUMENT _____
 c. Type(s):

TRUST FUND _____
 FINANCIAL BOND _____
 PERFORMANCE BOND _____
 LETTER OF CREDIT _____

INSURANCE _____
 FINANCIAL TEST _____
 CORPORATE GUARANTEE _____
 STATE GUARANTEE _____
 OTHER STATE MECHANISM _____

ID : _____

15. Sudden Liability Instrument(s)

- a. Evaluated? NA ☐ NE ☐ DATE EVAL'D July 82
 b. Adequate? YES ☐ NO ☐ NO INSTRUMENT ☐
 c. Amount: \$ _____ per occurrence, \$ _____ annual aggregate
 d. Type(s):
 INSURANCE POLICY _____ STATE GUARANTEE _____
 FINANCIAL TEST _____ OTHER STATE MECHANISM _____

16. Nonsudden Liability Instrument(s)

- a. Evaluated? NA ☐ NE ☐ DATE EVAL'D July 82
 b. Adequate? YES ☐ NO ☐ NO INSTRUMENT ☐
 c. Amount: \$ _____ per occurrence, \$ _____ annual aggregate
 d. Type(s):
 INSURANCE POLICY _____ STATE GUARANTEE _____
 FINANCIAL TEST _____ OTHER STATE MECHANISM _____

17. Closure Process

- a. Process Begun? NO ☒ DATE BEGUN _____
 b. In accordance with approved plan and required procedures? YES ☐ NO ☐
 c. Closure certifications received? NO ☐ DATE REC'D _____
 d. Facility released from closure assurance and liability requirements? NA ☐ NO ☐ DATE RELEASED July 82

18. Post-Closure Process

- a. Process Begun? NA ☒ NO ☐ DATE BEGUN - _____
 b. In accordance with approved plan and required procedures? YES ☐ NO ☐
 c. Survey plat/Record of wastes received? NO ☐ DATE REC'D _____
 d. Post-closure period completed? NO ☐ DATE COMPLETED _____
 e. Facility released from post-closure assurance requirements? NA ☐ NO ☐ DATE RELEASED _____

19. Permit Application

- a. Called? NO ☒ DATE CALLED _____
 b. Reason? GROUND WATER _____ FINANCIAL ASSURANCE _____
 CLOSURE _____ LIABILITY COVERAGE _____
 OTHER _____

MEMORANDUM REPORT



McClelland engineers, inc. / geotechnical consultants

6100 HILLCROFT / HOUSTON, TEXAS 77081
TEL 713 / 772-3701 / TELEX 762-447

SUBJECT: Geotechnical Investigation
Class I Disposal Ponds
Webster Generating Station
Webster, Texas

DATE: November 16, 1981

REPORT NO.: 0181-0318-4

TO: Houston Lighting & Power Company
12301 Kurland Drive
Houston, Texas 77034

Attention: Mr. James R. Mertink

Introduction

Presented here are the results of our investigation of soil conditions at the site of two Class I disposal ponds at your Webster Generating Station in Webster, Texas. This study was performed in general accordance with our proposal dated August 12, 1981 and was authorized by your Purchase Order No. M-76559 dated October 9, 1981.

A Demineralizer Regenerant Collection (D.R.C.) pond and an Inorganic Metal Cleaning (I.M.C.) collection pond are presently in use at the plant site. The ponds are about 5 ft deep and were constructed at grade as open-cut excavations.

We understand that the Texas Department of Water Resources indicated that by November 19, 1981, the owners of hazardous waste impoundments must have a ground-water monitoring program. This requirement may be waived if there is a low potential for migration of hazardous waste from the facility. The purposes of this investigation were to obtain information on the soil conditions at the site and evaluate the potential for migration of waste from the ponds to the uppermost aquifer.

To accomplish our objectives, the study included the following phases:

- . review of previous geotechnical work performed in the Webster Plant
- . field investigation
- . laboratory investigation
- . engineering analyses

Principal Findings

The principal findings of this study, based on our soil borings and laboratory tests, are presented below.

- (1) The ponds are located in clay to a depth of about 20 ft.
- (2) The clay is highly plastic and relatively impermeable with average coefficients of permeability of about 5.2×10^{-9} , 5.6×10^{-9} , and 2.2×10^{-9} cm/sec for deionized water, demineralizer regenerant, and inorganic metal cleanser, respectively.

- (3) The soil environment for the ponds is considered acceptable for Class I disposal ponds in accordance with the Texas Department of Water Resources Guidelines (Revised March 1, 1978) for unlined ponds. We therefore believe that the pond environments present a low potential for migration of waste.

Field Investigation

Information on soil conditions at the site was obtained by reviewing previous geotechnical work performed in the Webster Plant and by drilling two 30-ft and three 25-ft depth undisturbed-sample borings to supplement the available data. The borings are numbered 1 through 6 and are shown on Plate 1. The borings were drilled with a medium-duty truck-mounted rotary rig. Individual boring logs are presented on Plates 2 through 7. Most of the symbols and terms used on the logs are identified on Plate 8.

Undisturbed samples were obtained in the boring at 2-ft intervals from the ground surface to a depth of about 12 ft, at 15 ft, and at 5-ft intervals thereafter. Samples were obtained with a 3-in.-diameter thin-walled tube hydraulically pushed into the soil.

The samples recovered from the boreholes were removed from the sampling devices, examined, and classified by our soil technician. Representative portions of each sample obtained were sealed in appropriate containers and transported to our laboratory. The boreholes were sealed with a cement grout upon completion of drilling.

Laboratory Investigation

The laboratory soil tests were directed primarily toward evaluating soil classification and permeability. The following tabulation gives the type and number of tests performed.

<u>Type of Test</u>	<u>Number of Tests</u>
Penetrometer	55
Liquid and Plastic Limits	2
pH	2
Falling Head Permeability	6

Water content and unit dry weight determinations were made routinely on each permeability test specimen. The results of the pH and permeability tests are presented on Plate 9. All other test results are presented graphically on the boring logs.

Site Conditions

The site is relatively flat at about El +14. Soft to very stiff clay and silty clay is present over the site to a depth of about 20 ft. This clay is highly plastic and is classified as CH in the Unified Classification System. Between about 20 and 26-ft-depth, sandy to clayey silt was encountered. This silt is underlain by stiff clay to the maximum depth explored, 30 ft.

Conclusions

Our borings indicate that clays are present at the site to a depth of about 20 ft, which is 15 ft below the bottoms of the ponds. This satisfies the requirements of the Texas Department of Water Resources Guidelines (Revised March 1, 1978) for unlined Class I disposal ponds. We therefore believe that the pond environments present a low potential for migration of waste.

*

*

*

The following illustrations are attached and complete this report.


Plate 1	Site Plan
Plates 2 through 7	Logs of Borings
Plate 8	Terms and Symbols Used on Boring Logs
Plate 9	Permeability Test Results

McCLELLAND ENGINEERS, INC.



Edward J. Ulrich, Jr., P.E.
Engineer Manager

JAM/EJU/dka
Copies Submitted: (6)



5

6

D.R.C. Pond

3

4

I.M.C. Pond

1

2

Note:
Locations are approximate

PLAN OF BORINGS
Webster Generating Station

0 50 100 Feet

LOG OF BORING NO. 1
CLASS I DISPOSAL PONDS
WEBSTER GENERATING STATION
WEBSTER, TEXAS

DEPTH, FT	SYMBOL	SAMPLES	LOCATION : See Plate 1	BLOWS PER FT	% PASSING NO 200 SIEVE	UNIT DRY WT LB PER CU FT	WATER CONTENT, %			UNDRAINED SHEAR STRENGTH					DEPTH, M		
							Plastic Limit	Natural	Liquid Limit	KIPS PER SQ FT							
										0.5	1.0	1.5	2.0	2.5			
																KILOPASCALS	
							20	40	60	25	50	75	100	125			
			Soft brown clay with roots			106		+	-----	+							1
5			Stiff brown silty clay with roots														2
			-firm to 6'														3
			-dark gray, 5' to 9'														4
			-light gray below 9'														5
10			Stiff reddish brown clay with calcareous nodules														6
			-brownish yellow and light gray below 13'														7
15																	8
																	9
20																	10
			Reddish brown sandy silt														11
25																	12
			Stiff brown clay with calcareous nodules														13
30																	14
																	15
35																	16
40																	17
																	18
45																	19
50																	20

JOB NO.: 0181-0318

COMPLETION DEPTH: 29.5'

DATE: October 12, 1981




SAMPLER: 3" thin-walled tube

DRILLING METHOD: Wet Rotary

STRENGTH LEGEND

- Unconfined Compression
- ▲ Unconsolidated-Undrained Triaxial Compression
- ◆ Miniature Vane
- (open symbols above indicate remolded tests)
- ◆ Torvane
- ⊠ Hand Penetrometer

LOG OF BORING NO. 2
CLASS I DISPOSAL PONDS
WEBSTER GENERATING STATION
WEBSTER, TEXAS

DEPTH, FT	SYMBOL	SAMPLES	LOCATION . See Plate 1	BLOWS PER FT	% PASSING NO. 200 SIEVE	UNIT DRY WT LB PER CU FT	WATER CONTENT, %			UNDRAINED SHEAR STRENGTH					DEPTH, M		
							Plastic Limit	Natural	Liquid Limit	KIPS PER SQ FT							
										+-----●-----+	0.5	1.0	1.5	2.0		2.5	
																	20
5			Very stiff brown clay -with ferrous and calcareous nodules and roots to 13'													1	
			-dark brown, 6' to 9'														2
10			-light gray, 10' to 13'														3
			-stiff tan and light gray below 13'														4
15																	5
20																	6
																	7
25			Reddish brown clayey silt with sand pockets													8	
																	9
30			Stiff tan clay with ferrous nodules													10	
																	11
35																	12
																	13
40																	14
																	15
45																	16
50																	17

JOB NO. : 0181-0318
 COMPLETION DEPTH : 29.5'
 DATE : October 12, 1981


SAMPLER : 3" thin-walled tube

DRILLING METHOD : Wet Rotary

STRENGTH LEGEND

- Unconfined Compression
- ▲ Unconsolidated-Undrained Triaxial Compression
- ◆ Miniature Vane
(open symbols above indicate remolded tests)
- ◆ Torvane
- ⊠ Hand Penetrometer

LOG OF BORING NO. 3 **CLASS I DISPOSAL PONDS** **WEBSTER GENERATING STATION** **WEBSTER, TEXAS**

DEPTH, FT	SYMBOL	SAMPLES	LOCATION : See Plate 1	BLOWS PER FT	% PASSING NO. 200 SIEVE	UNIT DRY WT LB PER CU FT	WATER CONTENT %			UNDRAINED SHEAR STRENGTH					DEPTH, M
							Plastic Limit +	Natural -----●-----	Liquid Limit +	KIPS PER SQ FT					
										0.5	1.0	1.5	2.0	2.5	
										KILOPASCALS					
20	40	60	25	50	75	100	125								
5		Stiff dark brown clay -with gravel to 3' -reddish brown sand with roots, 1' to 2' -silty 2' to 3' -very stiff to 13' to 19' and below 22' -brownish yellow, 5' to 6' -tan and reddish brown, slickensided with calcareous and ferrous nodules, 6' to 10'											1		
10		-brownish yellow and light gray, slickensided, 10' to 13'											2		
15													3		
20													4		
25		-tan with sand pockets below 23'											5		
30		Reddish brown clayey silt											6		
35													7		
40													8		
45													9		
50													10		
													11		
													12		
													13		
													14		
													15		
													16		

JOB NO. : 0181-0318
 COMPLETION DEPTH : 24.5'
 DATE : October 12, 1981

SAMPLER : 3" thin-walled tube

DRILLING METHOD : Wet Rotary

STRENGTH LEGEND

- Unconfined Compression
- ▲ Unconsolidated-Undrained Triaxial Compression
- ◆ Miniature Vane
- (open symbols above indicate remolded tests)
- ◆ Torvane
- ⊠ Hand Penetrometer

LOG OF BORING NO. 4
CLASS I DISPOSAL PONDS
WEBSTER GENERATING STATION
WEBSTER, TEXAS

DEPTH, FT	SYMBOL	SAMPLES	LOCATION : See Plate 1	BLOWS PER FT	% PASSING NO. 200 SIEVE	UNIT DRY WT LB PER CU FT	WATER CONTENT, %			UNDRAINED SHEAR STRENGTH					DEPTH, M	
							Plastic Limit +	Natural -----●----- +	Liquid Limit +	KIPS PER SQ FT						
										0.5	1.0	1.5	2.0	2.5		
										KILOPASCALS						
20	40	60	25	50	75	100	125									
			Very stiff dark brown clay with calcareous nodules and roots -with silt pockets below 2.5'												1	
5			Stiff dark gray silty clay with ferrous and calcareous nodules and roots -brownish yellow, 6' to 8' -very stiff reddish brown, 8' to 10' -tan and light gray below 10'			109	●	-----	+							2
10																3
15																4
20																5
25			Reddish brown clayey silt													6
30																7
35																8
40																9
45																10
50																11
																12
																13
																14
																15
																16

JOB NO. : 0181-0318

COMPLETION DEPTH : 24.5'

DATE : October 13, 1981

SAMPLER : 3" thin-walled tube

DRILLING METHOD : Wet Rotary

STRENGTH LEGEND

- Unconfined Compression
- ▲ Unconsolidated-Undrained Triaxial Compression
- ◆ Miniature Vane
- (open symbols above indicate remolded tests)
- ◆ Torvane
- Hand Penetrometer

LOG OF BORING NO. 5
CLASS I DISPOSAL PONDS
WEBSTER GENERATING STATION
WEBSTER, TEXAS

DEPTH, FT	SYMBOL	SAMPLES	LOCATION : See Plate I	BLOWS PER FT	% PASSING NO 200 SIEVE	UNIT DRY WT LB PER CU FT	WATER CONTENT, %			UNDRAINED SHEAR STRENGTH					DEPTH, M
							Plastic Limit	Natural	Liquid Limit	KIPS PER SQ FT					
										0.5	1.0	1.5	2.0	2.5	
										KILOPASCALS					
20	40	60	25	50	75	100	125								

			Very stiff tan and brown clay with calcareous nodules and roots -dark brown with ferrous nodules, 2.5' to 4'																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																</
--	--	--	---	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	----

JOB NO. : 0181-0318
 COMPLETION DEPTH : 24.5'
 DATE : October 13, 1961

SAMPLER : 3" thin-walled tube

DRILLING METHOD : Wet Rotary

STRENGTH LEGEND

- Unconfined Compression
- ▲ Unconsolidated-Undrained Triaxial Compression
- ◆ Miniature Vane
- (open symbols above indicate remolded tests)
- ◆ Torvane
- ⊠ Hand Penetrometer

LOG OF BORING NO. 6
CLASS I DISPOSAL PONDS
WEBSTER GENERATING STATION
WEBSTER, TEXAS

DEPTH, FT	SYMBOL	SAMPLES	LOCATION . See Plate 1	BLOWS PER FT	% PASSING NO 200 SIEVE	UNIT DRY WT LB PER CU FT	WATER CONTENT %			UNDRAINED SHEAR STRENGTH					DEPTH, M	
							Plastic Limit	Natural	Liquid Limit	KIPS PER SQ FT						
										+-----+ 204060	0.5	1.0	1.5	2.0		2.5
5			Stiff dark brown clay with calcareous nodules and roots -yellowish brown intermixed with gravel and shells, 3' to 4' -tan and light gray -slickensided with ferrous nodules below 8'												1	
10																2
15																3
20																4
25			Reddish brown clayey silt Stiff tan clay with calcareous and ferrous nodules													5
30																6
35																7
40																8
45																9
50																10
																11
																12
																13
																14
																15
																16

JOB NO. : 0181-0318

COMPLETION DEPTH : 25.0'

DATE : October 13, 1981

SAMPLER : 3" thin-walled tube

DRILLING METHOD : Wet Rotary

STRENGTH LEGEND

- Unconfined Compression
- ▲ Unconsolidated-Undrained Triaxial Compression
- ◆ Miniature Vane
- (open symbols above indicate remolded tests)
- ◆ Torvane
- ⊠ Hand Penetrometer

ATTACHMENT K

Table of Well Construction Details

Well Number	MW-1	MW-2	MW-3	MW-4
Hole Diameter	7 in.	7 in.	7 in.	7 in.
Total Depth	21 ft.?	28 ft.?	29 ft.?	28 ft.?
Drill Method	Wet Rotary	Wet Rotary	Wet Rotary	Wet Rotary
Date Drilled	5-20-82	5-18-82	5-17-82	5-18-82
Casing I.D.	4 in.	4 in.	4 in.	4 in.
Casing Type	PVC	PVC	PVC	PVC
How Joined	N.P	N.P	N.P	N.P
Stick-up Length	N.P	N.P	N.P	N.P
T.O.C. (MSL)	19.48 ft.	21.11 ft.	21.94 ft.	21.43 ft.
Ground Level (MSL)	N.P	N.P	N.P	N.P
Capped/Lockable	Yes/No	Yes/No	Yes/No	Yes/No
Surface Pad Size	3 ft.	3 ft.	3 ft.	3 ft.
Depth Surface Seal	0- 4 ft. Cement	0-4 ft. Cement	0-4 ft. Cement	0-4 ft. Cement
Annulus Fill	Soil Cuttings	Soil Cuttings	Soil Cuttings	Soil Cuttings
Depth Annulus Seal	9 ft.	17 ft.	17 ft.	17 ft.
Depth Gravel Pack	10 ft.	18 ft.	18 ft.	18 ft.
Length Gravel Pack	11 ft.	10 ft.	11 ft.	10 ft.
Size of Gravel Pack	Clemtex No.2	Clemtex No.2	Clemtex No.2	Clemtex No.2
Depth Screen	15-20	22-27	23-28	22-27
Screen I.D./Slot	0.02 in.	0.02 in.	0.02 in.	0.02 in.
Screen Type	PVC	PVC	PVC	PVC
Screen Length	5 ft.	5 ft.	5 ft.	5 ft.
Blank Length	1 ft.	1 ft.	1 ft.	1 ft.

Development Method	Compressed Air	Compressed Air	Compressed Air	Compressed Air
-----------------------	-------------------	-------------------	-------------------	-------------------

N.P = Not Provided in Well Construction Details.

Note that depth of well and depth to screen are based on Table 7 in GWQA Report dated 5-29-84 which is in disagreement with Original construction data dated 7-22-82.

	<u>Sample 1</u>	<u>Sample 2</u>
Boring	1	4
Depth, Ft	3	7
Plastic Limit	18	19
Liquid Limit	55	66

Deionized Water

Coefficient of Permeability (cm/sec)	6.3×10^{-9}	4.0×10^{-9}
pH	7.5	7.5

Demineralizer Regenerant

Coefficient of Permeability (cm/sec)	1.2×10^{-9}	1.0×10^{-8}
pH	2.3	2.3

Inorganic Metal Cleanser

Coefficient of Permeability (cm/sec)	2.9×10^{-9}	1.4×10^{-9}
pH	10.4	10.4

PERMEABILITY TEST RESULTS
Webster Generating Station

ATTACHMENT

TEXAS DEPARTMENT OF WATER RESOURCES

PERMIT APPLICATION
FOR
INDUSTRIAL SOLID WASTE STORAGE/PROCESSING/DISPOSAL FACILITY

PART A - FACILITY BACKGROUND INFORMATION

APPL. NO.	10502
COUNTY-DIST.	Harris
RECEIVED BY CASED DATED	
ADM. REVIEW BY	
ADMINISTRATIVE COMPLETE	
COPIES SENT:	(CHECK)
DIST 7	

I. GENERAL INFORMATION

A. Applicant: Houston Lighting & Power, Webster Generating Station
(Individual, Corporation, or Other Legal Entity Name)

Address: P.O. Box 1700

City: Houston, State: Texas Zip Code: 77001

Telephone Number: (713) 481-7145

B. Authorized Agents

- List those persons or firms authorized to act for the applicant during the processing of the permit application. Also indicate the capacity in which each person may represent the applicant (engineering, legal, etc.). The person listed first will be the primary recipient of correspondence regarding this application. Include the complete mailing addresses and phone numbers.

W. F. McGuire, Manager, Environmental Protection Department
Houston Lighting & Power Company
P.O. Box 1700, Houston, Texas 77001
(713) 481-7145

R. M. McCuiston, Vice-President, Power System Development
Houston Lighting & Power Company
P.O. Box 1700
Houston, Texas 77001
(713) 228-9211

- List the individual and his/her mailing address that will be responsible for causing any necessary public notices to be published in the newspaper.

Name: W. F. McGuire

Address: P.O. Box 1700

City: Houston, State: Texas Zip Code: 77001

Telephone Number: (713) 481-7145

RECEIVED

AUG 18 1980

PERMIT CONTROL
TDWR

3. List the applicant's authorized agent for service.

Name: J. R. Johnston

Address: 611 Walker, P.O. Box 1700

City: Houston, State: Texas Zip Code: 77001

Telephone Number: (713) 228-9211

C. Operator: Identify the entity who will conduct facility operations.
If same as applicant, state "same as applicant."

Name: Same as applicant.

Address: _____

City: _____ State: _____ Zip Code: _____

Telephone Number: _____

D. Ownership

- (1) Corporation _____
(2) Partnership _____
(3) Proprietorship _____
(4) Non-profit organization _____

b. Public _____

- (1) Federal _____
(2) Military _____
(3) State _____
(4) Regional _____
(5) County _____
(6) Municipal _____

c. Other (specify) _____

2. Is facility and site property owned by applicant?

X Yes No

If you checked "no",

RECEIVED
AUG 18 1980
PERMIT CONTROL
TDWR

- a. Submit as an attachment a copy of the lease for use of said facility and/or site property, as appropriate; and
- b. Identify the facility owner. If same as applicant in Part A above, state "same as applicant." If different from the applicant, please note that the owner is required to sign the application on page 5.

Name: Same as applicant.

Address: _____

City: _____ State: _____ Zip Code: _____

Telephone Number: _____

E. Type of Permit Application:

1. New X
2. Amendment (TDWR Permit Number: _____)

F. Registration and Permit Information

1. Denote your TDWR Solid Waste Registration Number. If none, state "none."

31633

2. Indicate (by listing the permit number(s) in the appropriate column below) all existing or pending State and/or Federal permits or construction approvals which pertain to pollution control or industrial solid waste management activities conducted by your plant or at your location. Complete each blank by entering the permit number, or the date of application, or "none".

Relevant Program and/or Law

	<u>Permit No.</u>	<u>Government Agency*</u>
a. Texas Solid Waste Disposal Act	<u>8-15-80</u>	<u>TDWR</u>
b. Wastewater disposal under the Texas Water Code	<u>01044</u>	<u>TDWR</u>
c. Underground injection under the Texas Water Code	<u>None</u>	<u> </u>
d. Texas Clean Air Act	<u>None</u>	<u> </u>
e. Texas Uranium Surface Mining & Reclamation Act	<u>None</u>	<u> </u>
f. Texas Surface Coal Mining & Reclamation Act	<u>None</u>	<u> </u>
g. Hazardous Waste Management program under the Resource Conservation and Recovery Act	<u>8-15-80</u>	<u>EPA</u>

h. UIC program under the Safe Drinking Water Act	<u>None</u>	<u></u>
i. NPDES program under the Clean Water Act	<u>TX0006432</u>	<u>EPA</u>
j. PSD program under the Clean Air Act	<u>None</u>	<u></u>
k. Nonattainment program under the Clean Air Act	<u>None</u>	<u></u>
l. National Emission Standards for Hazardous Pollutants (NESHAPS) preconstruction approval under the Clean Air Act	<u>None</u>	<u></u>
m. Ocean dumping permits under the Marine Protection Research and Sanctuaries Act	<u>None</u>	<u></u>
n. Dredge or fill permits under section 404 of the Clean Water Act	<u>None</u>	<u></u>
o. Other relevant environmental permits	<u>None</u>	<u></u>

* Use the following acronyms for each agency as shown below:

TDWR = Texas Department of Water Resources
TACB = Texas Air Control Board
TRC = Texas Railroad Commission
TDH = Texas Department of Health
TDA = Texas Department of Agriculture
EPA = U. S. Environmental Protection Agency
CORPS = U. S. Army Corps of Engineers

G. Description of Business

1. Give a brief description of the nature of your business.

Electrical Power Generation

2. List the principal products and/or services which are provided by your plant. Please itemize by Standard Industrial Classification (SIC) codes.

4911 Electrical Power Services

I, R. M. McCuiston, Vice-President
(Name) (Title)
I, _____, _____
(Name) (Title)

Certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete.

Signature: R M McCuiston, Date: 8-15-80
Signature: _____, Date: _____

SUBSCRIBED AND SWORN to before me by the said R. M. McCuiston
_____ on this 15th day of August, 19 80.
My commission expires on the 7th day of March, 19 84.

Debra R. Blackburn
Notary Public in and for

Harris County, Texas

FEE PAID

II. SITE BACKGROUND INFORMATION

A. Location of Site

1. Facility Name: Webster Generating Station

Street Address, if available: 19301 State Hwy 3

Webster, Texas County: Harris

2. Are your waste management operations within the extraterritorial jurisdiction of a municipality?

X Yes No

If you checked "yes," what municipality? City of Webster

3. Give a verbal description of the location of the facility site with respect to known or easily identifiable landmarks.

Located approximately 25 miles southeast of Houston, immediately outside the town of Webster, along US Highway 3.

4. Detail the access routes from the nearest U.S. or State Highway to the facility site.

S.H.3 South of Webster, Texas.

5. Submit as "Attachment A" a United States Geological Survey (USGS), $7\frac{1}{2}$ minute quadrangle map. Indicate on this map the location of the site and the land use patterns of the areas within 1 mile (1.6 km) of the site boundaries (e.g., residential, commercial, recreational, agricultural, undeveloped, etc.). Each area of land use should be labeled on the map. (Note: if such a map is not available, submit a substitute map such as a State Department of Highways and Public Transportation county map with sufficient scale to adequately show the site location and surrounding land use patterns.

6. a. Submit as "Attachment B" a map indicating the boundaries of all adjacent parcels of land, and a list of the names and mailing addresses of all adjacent landowners and other nearby landowners who might consider themselves affected by the activities described by this application. Cross-reference this list to the map through the use of appropriate keying techniques. The map should be a USGS map, a city or county plat, or another map or drawing with a scale adequate enough to show the cross-referenced affected landowners.

- b. Indicate from what source(s) the names and addresses of persons identified as affected were obtained.

City _____
County X _____
School District _____
Water District _____
Abstract Co. _____
Other (specify) _____

7. Enter the geographical coordinates of the site:

Latitude: N29 deg 31 min 47 sec

Longitude: W95 deg 06 min 10 sec

8. Is the facility located on Indian lands? Check one:

 Yes X No

B. Legal Description of Site

Submit as "Attachment C" a legal description of the entire tract of land upon which the waste management operations referred to in this permit application occur or will occur.

C. Site Environmental and Technical Information

1. Climatic and Hydrologic

- a. Is any portion of your waste management facility site (including proposed, active, and inactive portions) subject to flooding from adjacent or nearby surface water bodies under the following conditions?

<u>24-hr Rainfall Event</u>	<u>Yes</u>	<u>No</u>
5-year	<u> </u>	<u>X</u>
50-year	<u> </u>	<u>X</u>
100-year	<u>X</u>	<u> </u>

- b. Are there any producing groundwater wells on your site property?

X Yes No

If you checked "yes,"

(1) Indicate the number of such wells: two (2), and

(2) Indicate the corresponding water uses below:

(a) Industrial uses:

Cooling water _____
Process water X
Fire-control water _____

(b) Potable (drinking) water _____

(c) Agricultural uses:

Irrigation water for livestock food crops or grazing
land _____
Livestock watering _____
Irrigation water for human food crops _____

c. Are any adjacent or nearby surface waters utilized by the applicant?

X Yes _____ No

If you checked "yes," indicate the corresponding water uses below:

(1) Industrial uses:

Cooling water X
Process water _____
Fire-control water X

(2) Potable (drinking) water _____

(3) Agricultural uses:

Irrigation water for livestock food crops or grazing
land _____
Livestock watering _____
Irrigation water for human food crops _____

2. Site Land Use and Subsidence Information

a. Is any portion of the overall site property utilized for agricultural purposes?

_____ Yes X No

If you checked "yes," indicate the corresponding uses below:

(1) Grazing _____
(2) Livestock food crop _____
(3) Human food crop _____

If you checked no. (2) or (3), specify the types of crops grown. _____

b. Is any portion of the overall site property subject to land subsidence?

X Yes _____ No

If you checked "yes," estimate the magnitude of the greatest subsidence that has occurred (in units of feet). 0.8 ft. (1973-1978)

III. WASTES AND WASTE MANAGEMENT

A. Waste Generation and Management Activities

Is any hazardous industrial solid waste (see Title 40, Code of Federal Regulations, Part 261) presently or proposed to be generated at your facility?

☒ Yes ☐ No

If you checked "no," go to Section III.B.2. below.

If you checked "yes," answer the following question.

1. Are you presently registered with TDWR as a solid waste generator?

☒ Yes ☐ No

If you checked "no," contact the Solid Waste Section of TDWR in Austin, Texas to obtain registration information. Also, continue with the application form (go to Number 2 below).

If you checked "yes," go to Section I of your Notice of Registration, determine which of your wastes are hazardous, and list these wastes (and mixtures) in Table III-1 (see Number 2 below).

2. Complete Table III-1 below, listing all hazardous wastes and all mixtures containing any hazardous waste which are presently or proposed to be generated at your facility. (see 40 CFR 261.31-33), attaching additional copies as necessary.

In this table, "TDWR Sequence Number" refers to the number in the left-hand column in Section I of your Notice of Registration (Note: if you are not registered with TDWR, enter "NA" for TDWR Sequence Number and TDWR Waste Code Number).

For the EPA Hazard Code and EPA Hazardous Waste Numbers, see 40 CFR 261.30-33. For annual quantity, provide the amount in units of pounds (as generated) for each waste and/or waste mixture.

Please group the listings of wastes by SIC code, insofar as your processes are designated by SIC codings. Also, within the general SIC code groups, give a brief description of the specific process or operation from which the waste has been generated.

B. Waste Management Facilities Summary

1. For each waste and waste mixture listed in Table III-1 that is presently or proposed to be managed on-site, provide the summary sheet shown in Table III-2 (Note: you must make copies of Table III-2 and submit the completed set of tables as "Attachment D").

Webster Generating Station

Table III Generated Hazardous Wastes and Management Activities

Verbal Description of Waste	TOWH Sequence Number	TOWH Waste Code Number	EPA Hazard Code	EPA Hazardous Waste No.	Off Site Disposal	Waste Management Activities (Check applicable items)			Annual Quantity Generated (lbs)	SIC Code and Process
						Storage ¹	On Site Processing ²	Disposal		
Demineralizer Regenerant	NA	NA	C	D002		X	X		81,532,000*	
Demineralizer Regenerant Inorganic Sludge	2	140540	E		X	X			**	
Metal Cleaning Organic Acids	NA	NA	E, C	D007, D002		X	X		18,287,000*	
Metal Cleaning & Other Inorganic Sludge	2	140540	E		X	X			**	
Metal Cleaning Organic Acids	NA	NA	E		X	X	X		2,752,500*	
Metal Cleaning Organic Sludge	NA	148990	E		X	X			**	
Chemical Waste Treatment System Sludge	NA	NA	E	D007	X	X	X		243,000	
Waste Oil & Sludge	✓	110450	T, O		X	X	X		12,000	
Degreasing and Paint Solvents	NA	NA	I, T	F003, F005	X	X			9,700	
Asbestos in insulation	NA	170750	T	U013	X	X	X		3,600***	

*Untreated amounts, normally treated and discharged under wastewater permits

**Unknown small amount

*** Actual percent asbestos content is variable but small

¹ "Storage" means the interim containment or control of waste after generation and prior to ultimate disposal.

² "Processing" means the extraction of materials, transfer, volume reduction, conversion to energy, or other separation and preparation of solid waste for reuse or disposal, including the treatment or neutralization of hazardous waste so as to render such waste nonhazardous, safer for transport, amenable for recovery, amenable for storage, or reduced volume. The "transfer" of solid waste for reuse or disposal as used above, does not include the actions of a carrier in conveying or transporting solid waste by truck, ship, pipeline, or other means.

2. Has the applicant at any time conducted the on-site storage, processing, or disposal of industrial solid waste now identified or listed as hazardous waste?

☒ Yes ☐ No

If you checked "yes," complete Table III-3 indicating the hazardous industrial solid waste management facility components which were once utilized at your plant site but are no longer in service (i.e., inactive facility components).

If you checked "no," and if no hazardous industrial solid waste is presently or proposed to be generated or managed at your facility, then you need not file this permit application. Otherwise, proceed with application form.

3. For each facility component indicated in Table III-2 (Attachment D) and Table III-3, complete the following Table III-4 attaching additional copies as necessary. Enter the name of each facility component as specified in the earlier tables.

Give the design capacity of each facility component in any of the units shown. In the case of inactive facilities for which design details are unavailable, an estimate of the design capacity is sufficient.

Please note that each facility component should be described in your own words on the line provided for "verbal description."

4. Provide an estimate of the total weight (lbs) of hazardous industrial solid waste material that has been disposed of and/or stored within your site boundaries and not removed to another site.

C. Location of Waste Management Facilities and Components

1. Submit as "Attachment E" a drawn-to-scale topographic map (or other map if a topographic map is unavailable) extending one mile (and only one mile) beyond the property boundaries of the overall plant site, depicting the following:

- a. The approximate boundaries of the site (described in Section II B) and within these boundaries, the location and boundaries of the areas occupied by each active, inactive, and proposed facility component (see Tables III-2 and III-3 for facility components). Each depicted area should be labeled to identify the facility component(s), component status (i.e., active, inactive, or proposed), and area size in acres.

Table III-4 Hazardous Waste Facility Components List

Facility Component		Status			Design Capacity			Number of	Date
Name	TDWR Seq. No.	Inactive	Active	Proposed	(cu yds)	(gal)	(lbs)	Years Utilized	in Service
Lagoon/ Pond (lined)			X			372,000		10	1970
Verbal Description: Clay lined pond for the collection & equalization of demineralizer regeneration wastes prior to treatment. Sludge accumulated at pond bottom periodically removed for off-site disposal.									
*Tank (Surface Processing)			X			8,600		3	1977
Verbal Description: Treatment system (Surface processing) for neutralization consists of one (1) mixing chamber (300 gallon), one (1) flocculation chamber (1100 gallon), one (1) settling chamber (6900 gallon) and one (1) pH readjustment chamber (300 gallon).									
Lagoon/Pond (lined)			X			270,000		3	1977
Verbal Description: Clay lined pond for the collection of metal cleaning inorganic acid wastes from boiler & equipment cleaning operations prior to treatment. Sludge accumulated at pond bottom periodically removed for off-site disposal.									
Lagoon/Pond (lined)			X			270,000		10	1970
Verbal Description: Clay lined pond for the collection of metal cleaning organic acids from boiler cleaning operations prior to off-site treatment. Sludge accumulated at pond bottom periodically removed for off-site disposal.									
Basin (earthen, below-grade lined)			X			1790 (ea)		3	1977
Verbal Description: Two clay lined sand drying beds for the collection & processing of sludge from the chemical waste treatment system and oily waste treatment system. Dried sludge is periodically removed for off-site disposal.									
Tank (surface storage)			X			3,000		3	1977
Verbal Description: Chamber used for the collection of waste oil & sludge which is accumulated from the oily waste treatment system. This waste is periodically trucked off-site for disposal or is transferred to the sludge drying beds.									

*Chemical Waste Treatment System

Table 11.11.10 - Waste Facility Components List

Facility Component Name	IDWR Seq. No.	Status			Design Capacity			Number of Years Utilized	Date in Service
		Inactive	Active	Proposed	(cu yds)	(gal)	(lbs)		
Other			X		NA	NA	NA	NA	NA
Verbal Description: Asbestos used for insulation will be placed in bags and wet down prior to off-site disposal.									
Actual percent asbestos content is variable but small.									
Drum Storage Area (other)			X		NA	NA	NA	NA	NA
Verbal Description: Drum storage area for the collection of waste solvents used in degreasing and painting operations prior to off-site disposal.									
Verbal Description:									
Verbal Description:									
Verbal Description:									
Verbal Description:									
Verbal Description:									
Verbal Description:									
Verbal Description:									

EPA U.S. ENVIRONMENTAL PROTECTION AGENCY GENERAL INFORMATION (Read the "General Instructions" before starting.)		EPA ID NUMBER: FTXD000837369
TABLE/TYPE EPA ID NUMBER FACILITY NAME FACILITY ADDRESS MAILING ADDRESS FACILITY LOCATION	PLEASE PLACE LABEL IN THIS SPACE	

B. POLLUTANT CHARACTERISTICS			
INSTRUCTIONS: Complete A through F depending whether you are submitting any permit application to the EPA. If you are not submitting a permit application, you must submit the following information to the EPA. If the supplemental form is attached to your answer, "no" to each question, you must not submit any of these forms. If an answer is included from permit requirements, see Section C of the instructions. See also Section D of the instructions for additional information.			
1. Is this facility a publicly owned treatment works (POTW)? (FORM 201)	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	2. Does or will this facility, before existing or proposed, include a concentrated animal feeding operation (CAFO) or a slaughterhouse, poultry processing facility, or other animal production facility which results in discharges to waters of the U.S.? (FORM 202)	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>
3. Is this a facility which currently results in discharges to waters of the U.S. other than those described in A or B above? (FORM 203)	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	4. Is this a proposed facility (other than those described in A or B above) which will result in discharges to waters of the U.S.? (FORM 204)	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>
5. Does or will this facility treat, store, or dispose of hazardous waste? (FORM 205)	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	6. Do you or will you inject or will you inject a pollutant into or on the land surface of the U.S. from a well, pit, or other underground source of pollution? (FORM 206)	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>
7. Do you or will you inject or will you inject any product, water, or other fluid which is brought to the surface in connection with conventional oil or natural gas production, geothermal production, or other production, into or on the land surface of the U.S. from a well, pit, or other underground source of pollution? (FORM 207)	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	8. Is this facility a proposed stationary source which is one of the 20 industrial categories listed in the instructions and which will, in any calendar year, emit or may be expected to emit pollutants regulated under the Clean Air Act and covered by the National Emission Inventory? (FORM 208)	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>

III. NAME OF FACILITY 1. NAME: WEBSTER GENERATING STATION	
---	--

IV. FACILITY CONTACT 2. NAME & TITLE: MCGUIRE, W.F. MANAGER ENVIRON		3. PHONE (Area Code) / Number: 713 481 7145
---	--	---

V. FACILITY MAILING ADDRESS 3. P.O. BOX 1700		4. CITY OR TOWN: HOUSTON	5. STATE & ZIP CODE: TX 77001
--	--	--------------------------	-------------------------------

VI. FACILITY LOCATION 6. STREET, ROUTE NO. OR OTHER SPECIFIC IDENTIFIER: 19301 OLD GAVESTON ROAD		7. COUNTY NAME: HARRIS
8. CITY OR TOWN: WEBSTER		9. STATE & ZIP CODE: TX 77598

4.9.1.1 (specify) STEAM ELECTRIC POWER

(specify)

(specify)

(specify)

HOUSTON LIGHTING & POWER COMPANY

P (specify)

713 481 7145

P O BOX 1700

HOUSTON

TX 77001

TX 0006432

01044

(specify)
TEXAS DEPT. OF WATER RESOURCES

(specify)

STEAM ELECTRIC POWER PRODUCTION

A. NAME & OFFICIAL TITLE (type or print)

R. M. McCUISTION
VICE PRESIDENT

B. SIGNATURE

R. M. McCuistion

C. DATE SIGNED

11-18-80

FORM 3
RCRA
EPA
ENVIRONMENTAL PROTECTION AGENCY
HAZARDOUS WASTE PERMIT APPLICATION
Consolidated Permit Program
(This information is required under Section 3005 of RCRA.)

EPA I.D. NUMBER
FTX D 000 837369

FOR OFFICIAL USE ONLY

APPLICATION APPROVED	DATE RECEIVED (Yr., Mo., & Day)	COMMENTS

II. FIRST OR REVISED APPLICATION

Place an "X" in the appropriate box in A or B below (mark one box only) to indicate whether this is the first application you are submitting for your facility or a revised application. If this is your first application and you already know your facility's EPA I.D. Number, or if this is a revised application, enter your facility's EPA I.D. Number in Item I above.

A. FIRST APPLICATION (place an "X" below and provide the appropriate date)

☒ **1. EXISTING FACILITY** (See instructions for definitions of "existing" facility. Complete items below.)

FOR EXISTING FACILITIES, PROVIDE THE DATE (Yr., Mo., & Day) OPERATION BEGAN ON THE DATE CONSTRUCTION COMMENCED (use the boxes to the left)

Yr. 8 Mo. 06 Day 15

☐ **2. NEW FACILITY** (Complete items below.)
FOR NEW FACILITIES, PROVIDE THE DATE (Yr., Mo., & Day) OPERATION BEGAN OR IS EXPECTED TO BEGIN

B. REVISED APPLICATION (place an "X" below and complete item 1 below)

☐ **1. FACILITY HAS INTERIM STATUS**

☐ **2. FACILITY HAS A RCRA PERMIT**

III. PROCESSES - CODES AND DESIGN CAPACITIES

A. PROCESS CODE - Enter the code from the list of process codes below that best describes each process to be used at the facility. Ten lines are provided for entering codes. If more lines are needed, enter the code(s) in the space provided. If a process will be used that is not included in the list of codes below, then describe the process (including its design capacity) in the space provided on the form (Item III-C).

B. PROCESS DESIGN CAPACITY - For each code entered in column A enter the capacity of the process:

1. **AMOUNT** - Enter the amount.

2. **UNIT OF MEASURE** - For each amount entered in column B(1), enter the code from the list of unit measure codes below that describes the unit of measure used. Only the units of measure that are listed below should be used.

PROCESS CODE	APPROPRIATE UNITS OF MEASURE FOR PROCESS DESIGN CAPACITY	PROCESS CODE	APPROPRIATE UNITS OF MEASURE FOR PROCESS DESIGN CAPACITY
Storage:		Treatment:	
CONTAINER (barrel, drum, etc.)	501 GALLONS OR LITERS	TANK	502 GALLONS PER DAY OR LITERS PER DAY
TANK	502 GALLONS OR LITERS	RESERVOIR IMPOUNDMENT	503 GALLONS PER DAY OR LITERS PER DAY
WASTE PILE	503 CUBIC YARDS OR CUBIC METERS	INCINERATOR	504 METRIC TONS PER HOUR OR GALLONS PER DAY
SURFACE IMPOUNDMENT	504 GALLONS OR LITERS		
Disposal:			
INJECTION WELL	505 GALLONS OR LITERS		
LANDFILL	506 ACRES-FOOT (the volume that would cover one acre to a depth of one foot) OR HECTARE-METER		
LAND APPLICATION	507 ACRES OR HECTARES		
OCEAN DISPOSAL	508 GALLONS PER DAY OR LITERS PER DAY		
SURFACE IMPOUNDMENT	509 GALLONS OR LITERS		
UNIT OF MEASURE CODE		UNIT OF MEASURE CODE	
GALLONS	01	ACRES-FOOT	01
LITERS	02	HECTARE-METER	02
CUBIC YARDS	03	ACRES	03
CUBIC METERS	04	HECTARE	04
GALLONS PER DAY	05		
LITERS PER DAY	06		
TONS PER HOUR	07		
METRIC TONS PER HOUR	08		
GALLONS PER HOUR	09		
LITERS PER HOUR	10		

EXAMPLE FOR COMPLETING ITEM III (shown in the numbers 1, 2, and 3 below): A facility has three storage tanks, one tank can hold 3,500 gallons and the other can hold 400 gallons. The facility also has an incinerator that can burn up to 20 gallons per hour.

LINE NUMBER	A. PROCESS CODE (from list above)	B. PROCESS DESIGN CAPACITY	UNIT OF MEASURE CODE	FOR OFFICIAL USE ONLY	LINE NUMBER	A. PROCESS CODE (from list above)	B. PROCESS DESIGN CAPACITY	UNIT OF MEASURE CODE	FOR OFFICIAL USE ONLY
1	S 0 2	3,500	G		5	S 0 2	3,500	G	
2	T 0 3	20	L		6	T 0 2	24,000	U	
3	S 0 4	372,000	G		7	T 0 1	360,000	U	
4	T 0 1	1,200	F		8	S 0 1	1,616	G	
5	S 0 4	270,000	G		9	S 0 1	1,090	H	
6	S 0 4	270,000	G		10				

III. PROCESSES (continued)

C. SPACE FOR ADDITIONAL PROCESS CODES OR DESCRIBING OTHER PROCESSES (code "T04" FOR EACH PROCESS ENTERED HERE INCLUDE DESIGN CAPACITY.

OR DESCRIBING OTHER PROCESSES (code "T04" FOR EACH PROCESS ENTERED HERE

IV. DESCRIPTION OF HAZARDOUS WASTES

A. EPA HAZARDOUS WASTE NUMBER — Enter the four-digit number from 40 CFR, Subpart D for each listed hazardous waste you will handle. If you handle hazardous wastes which are not listed in 40 CFR, Subpart D, enter the four-digit number from 40 CFR, Subpart C that describes the characteristics and/or the toxic constituents of those hazardous wastes.

B. ESTIMATED ANNUAL QUANTITY — For each listed waste entered in column A, estimate the quantity of that waste that will be handled on an annual basis. For each characteristic or toxic constituent entered in column A, estimate the total annual quantity of all the non-listed waste(s) that will be handled which possess that characteristic or constituent.

C. UNIT OF MEASURE — For each quantity entered in column B, enter the unit of measurement. List the units which must be used and the appropriate code.

ENGLISH UNIT OF MEASURE

CODE

METRIC UNIT OF MEASURE

CODE

POUNDS

POUNDS

GALLONS

METRIC TONS

If facility records use any other unit of measure for quantity, the unit of measure must be converted into one of the required units of measure taking account the appropriate density or specific gravity of the waste.

D. PROCESSES**1. PROCESS CODES**

For listed hazardous waste: For each listed hazardous waste entered in column A, select the codes from the list of process codes contained in Item 1 to indicate how the waste will be treated, stored, and/or disposed of at the facility.

For non-listed hazardous waste: For each characteristic or toxic constituent entered in column A, select the codes from the list of process codes contained in Item 1 to indicate all the processes that will be used to store, treat, and/or dispose of all the non-listed hazardous waste that possess that characteristic or toxic constituent.

Note: Four spaces are provided for entering process codes. If more are needed: (1) Enter the first three as described above; (2) Enter "900" in the extreme right box of Item D(2); and (3) Enter in the space provided on page 4, the line number and the additional code(s).

2. PROCESS DESCRIPTION If a code is not listed for a process that will be used, describe the process in the space provided on the form.

NOTE: HAZARDOUS WASTES DESCRIBED BY MORE THAN ONE EPA HAZARDOUS WASTE NUMBER — Hazardous wastes that can be described by more than one EPA Hazardous Waste Number, shall be described on the form as follows:

1. Select one of the EPA Hazardous Waste Numbers and enter it in column A. On the same line complete columns B, C, and D by estimating the total annual quantity of the waste and describing all the processes to be used to treat, store, and/or dispose of the waste.

2. In column A of the next line enter the other EPA Hazardous Waste Number that can be used to describe the waste. In column D(2) on that line enter "Included with above" and make no other entries on that line.

Repeat step 2 for each other EPA Hazardous Waste Number that can be used to describe the hazardous waste.

EXAMPLE FOR COMPLETING ITEM IV shown in the numbers X-1, X-2, X-3, and X-4 below: A facility will treat and dispose of an estimated 900 pounds per year of chrome sludge from leather tanning and finishing operation. In addition, the facility will treat and dispose of three non-listed wastes. Two wastes are corrosive only and there will be an estimated 200 pounds per year of each waste. The other waste is corrosive and ignitable and there will be an estimated 300 pounds per year of that waste. Treatment will be in an incinerator and disposal will be in a landfill.

LINE NO.	A. EPA HAZ. WASTE NO. (enter code)	B. ESTIMATED ANNUAL QUANTITY OF WASTE	C. UNIT OF MEASURE (enter code)	D. PROCESSES	
				1. PROCESS CODES (if a code is not entered in D(1))	2. PROCESS DESCRIPTION
X-1	K051	900	P	T03D80	
X-2	D002	200	P	T03D80	
X-3	D002	200	P	T03D80	
X-4	D002				Included with above

EPA Form 3510-3 (8-90)

IV. DESCRIPTION OF HAZARDOUS WASTE

(continued)

E. USE THIS SPACE TO LIST ADDITIONAL PROCESS CODES FROM ITEM D(1) ON PAGE 3.

EPA ID NO. (enter from page 1)												
F	T	X	D	0	0	0	8	3	7	3	6	9
											6	

V. FACILITY DRAWING

All existing facilities must include in the space provided on page 5 a scale drawing of the facility (see instructions for more detail).

VI. PHOTOGRAPHS

All existing facilities must include photographs (aerial or ground-level) that clearly delineate all existing structures; existing storage, treatment and disposal areas; and sites of future storage, treatment or disposal areas (see instructions for more detail).

VII. FACILITY GEOGRAPHIC LOCATION

LATITUDE (degree, minutes, & seconds) LONGITUDE (degree, minutes, & seconds)

29 31 47

95 06 10

VIII. FACILITY OWNER

A. If the facility owner is also the facility operator as listed in Section VIII on Form 1, "General Information," place an "X" in the box to the left and skip to Section IX below.

B. If the facility owner is not the facility operator as listed in Section VIII on Form 1, complete the following items:

1. NAME OF FACILITY'S LEGAL OWNER 2. PHONE NO. (area code & no.)

3. STREET OR P.O. BOX 4. CITY OR TOWN 5. ST. 6. ZIP CODE

IX. OWNER CERTIFICATION


I certify under penalty of law that I have personally examined and am familiar with the information submitted in this and all attached documents, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

A. NAME (print or type) R. M. McCUISTION VICE PRESIDENT	B. SIGNATURE <i>R. M. McCuiston</i>	C. DATE SIGNED 11-18-80
---	--	----------------------------

X. OPERATOR CERTIFICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this and all attached documents, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

A. NAME (print or type)	B. SIGNATURE	C. DATE SIGNED
-------------------------	--------------	----------------




Webster Generating Station
Houston Lighting & Power Co.

USGS- League City, Texas 1916-53
Friendswood, Texas 1943-55(69PR)

WASTE OIL & SLUDGE
COLLECTION FACILITY

SOLIDWASTE
DISPOSAL SITE
(NOT SHOWN ON PHOTO)



SOLID WASTE
DISPOSAL
SITE

METAL CLEAN
ING ORGANIC
ACIDS
COLLECTION
POND
0.46 ACRE

DEMINERAL-
IZER
REGENERANT
COLLECTION
POND
0.65 ACRE

METAL CLEAN
ING INORGAN-
IC ACIDS
COLLECTION
POND
0.71 ACRE

SAND DRYING
BEDS

CHEMICAL
WASTE
TREATMENT
SYSTEM

WEB
9-80

WEBSTER GENERATING STATION (607.762 ACRES)

1"-300"

WEBSTER GENERATING STATION


7369

13

METAL CLEANING
ORGANIC ACIDS
COLLECTION POND

DEMINERALIZER REGENERANT
COLLECTION POND

METAL CLEANING
INORGANIC ACIDS
COLLECTION POND





CHEMICAL WASTE
TREATMENT SYSTEM

WEBSTER GENERATING STATION

7369

14



SAND DRYING BEDS


September 8, 1980

WEBSTER GENERATING STATION

1369

15

WASTE OIL & SLUDGE
COLLECTION FACILITY



Reference 14

CD. SER. 013634 Y89029387

552.67

N0512951 185

STANDA

57835

STANDARD AND POORS
CORPORATION

1989 V.1
CORP

STANDARD AND POORS
REGISTER OF CORPORA

POOR

DALLAS PUBLIC LIBRARY
BUSINESS AND TECHNOLOGY

Reference Use Only

REGISTER of CORPORATIONS, DIRECTORS AND EXECUTIVES

Volume 1

1989

Public Library

MAR 10 1989

Dallas, Texas

Library of Congress Catalog Card Number: 76-642986
ISSN: 0361-3623

STANDARD & POOR'S CORPORATION
A McGraw-Hill Financial Services Company



25 Broadway, New York, N.Y. 10004

Telephone—212-208-8702



COPYRIGHT ©1989 STANDARD & POOR'S CORPORATION, ALL RIGHTS RESERVED

Accts—Deloitte Haskins & Sells, Houston, Texas
 Primary Bank—Texas Commerce Bank-Houston, N.A.
 Primary Law Firm—Bracewell & Patterson
 Employees: 1,900
 *Also DIRECTORS—Other Directors Are:
 Frank A. Bennack, Jr. Robert J. Danzig
 Peter J. DeMaria Gilbert C. Maurer
 BUSINESS: Publishing newspapers
 S.I.C. 2711

HOUSTON DIE CASTING CO.

(Subs. Chemilite Corp.)

3315 W. 11th Street, Houston, Texas 77008
 Tel. 713-869-1434

*Pres—Harold L. Gluckman
 Exec V-P (Product & Sales)—Joe Richard
 *Secy & Compt—Peggy Papageorgiou
 Purch Agt—Keith Humber
 Accts—P. Levin & Co., Houston, Texas
 Primary Bank—Ameriway Bank/Woodway, N.A.
 Primary Law Firm—Weyerer, Kaplan, Pulaski & Zuber
 Sales: \$3Mil Employees: 45

*Also DIRECTORS
 PRODUCTS: Die castings & machining
 S.I.C. 3599; 3363; 3364; 3541

HOUSTON ELECTRIC CO.

201 Redmond, Warner Robins, Ga. 31093
 Tel. 913-922-8813

Pres—Charles G. McDonald
 Gen Coun—R. Jones Leo
 Project Mgr—William H. Bernard
 Accts—Walker, Meadows & Childs, Warner Robins, Ga.
 Primary Bank—First National Bank of Atlanta
 Sales: \$1.30Mil Employees: 23
 BUSINESS: Electrical
 S.I.C. 5063; 5065

HOUSTON ELECTRONICS CORP.

(Div. Dick Industries Inc.)

501 Pine St. Ext., Kane, Pa. 16735
 Tel. 814-837-9550

Pres—John M. Laumt
 V-P—Jack E. Laumt
 Purch Agt—R. Iwanaky
 Sales Range: \$2—\$Mil Employees: 150
 PRODUCTS: Quartz crystal bases, glass to metal seals
 S.I.C. 3679

HOUSTON ENGINEERS, INC.

(Subs. Wilson Industries, Inc.)

P. O. Box 567, Houston, Texas 77001
 Tel. 713-227-3050

*Pres—Dwight E. Beach, Jr.
 V-P (Eng)—Derrell D. Webb
 V-P (Eng)—D. Hunter
 V-P (Eng)—J. P. Doyle
 V-P (Eng)—J. P. Doyle
 Accts—Arthur Andersen & Co., Houston, Texas
 Primary Bank—Texas Commerce Bank-Houston, N.A.
 Sales: \$12Mil Employees: 140

*Also DIRECTORS—Other Directors Are:
 Edwin A. Anderson James K. Andrews
 W. J. Miller Preston Moore

Wallace S. Wilson
 PRODUCTS: Oil well tools
 S.I.C. 3533

H.W. HOUSTON CONSTRUCTION CO.

210 S. Victoria, Pueblo, Colo. 81003
 Tel. 719-544-2791

Pres & Treas—Albert Concialdi
 V-P & Secy—Kenneth W. West
 V-P—Robert Concialdi
 Gen Coun—Mickey W. Smith
 Accts—C.L. Brown & Associates, Pueblo, Colo.
 Primary Bank—Minneapolis Bank of Pueblo
 Primary Law Firm—Smith & Billups
 Sales: \$15Mil Employees: 100
 BUSINESS: General contractor
 S.I.C. 1542

HOUSTON INDUSTRIES INCORPORATED

P.O. Box 4567, Houston, Texas 77210
 Tel. 713-629-3000

H Houston Industries Incorporated

*Pres & Chief Exec Officer—D. D. Jordan
 *Exec V-P & Chief Fin Officer—H. E. Dean
 V-P & Treas—W. A. Cropper
 V-P (Cor Devel)—R. E. Dyer
 V-P, Gen Coun & Secy—H. R. Kelly
 V-P & Compt—D. M. McClanahan
 V-P—D. D. Sykora
 Accts—Deloitte Haskins & Sells, Houston, Texas
 Primary Bank—Chemical Bank, N.A.
 Primary Law Firm—Baker & Botts
 Revenue: \$3.63Bil Employees: 11,506
 Stock Exchange(s): NYS, BSE, PAC, MID, CIN, PSX
 *Also DIRECTORS—Other Directors Are:
 Charles E. Bishop John T. Cater
 Floyd L. Culler, Jr. Joseph M. Hendrie
 Howard W. Horne James R. Leach

Jon S. Lindsay
 Randall Meyer
 Jack T. Trotter

Thomas B. McDade
 Kenneth L. Schnitzer, Sr.

BUSINESS: Holding co.; generation, transmission, distr. & sale of electric energy, oil & gas; coal supply serv., cable TV; development & marketing of lighting, purchase of accounts receivable of subsidiary & venture capital
 S.I.C. 6719; 1221; 1311; 4911; 5063; 6799

HOUSTON INSTRUMENT

(Div. Ametek Inc.)

8500 Cameron Rd., Austin, Texas 78753
 Tel. 512-835-0900

Pres—Doyle K. Cavin
 V-P (Mktg)—John J. Carr, Jr.
 V-P (Mfg)—Vern Glover
 V-P (Eng)—Eric Silverberg
 V-P (Admin)—Robert Zurack
 Compt—Ted Middelberg
 Accts—Arthur Young, Philadelphia, Pa.
 Primary Bank—Chase Manhattan Bank, N.A.
 Primary Law Firm—Stroock & Stroock & Lavan
 Employees: 400
 PRODUCTS: Computer graphic peripheral devices; plotters, digitizers, scanners
 S.I.C. 3577; 3575; 3577

HOUSTON LIGHTING & POWER COMPANY

(Subs. Houston Industries Incorporated)

P.O. Box 1700, Houston, Texas 77251
 Tel. 713-228-9211



The Light company

Houston Lighting & Power

*Chrm & Chief Exec Officer—D. D. Jordan
 *Pres & Chief Oper Officer—D. D. Sykora
 Group V-P (Nuclear)—J. H. Goldberg
 Group V-P (External Affairs)—R. J. Snokhouse
 Group V-P (Power Oper)—D. E. Simmons
 Group V-P (Admin & Support)—E. A. Turner
 Sr V-P, Gen Coun & Secy—H. R. Kelly
 V-P (Energy Prod)—D. G. Tees
 V-P (Human & Ind Resources)—R. E. Dean
 V-P (Sys Oper)—J. D. Greenwade
 V-P (Fossil Pitt Eng & Constr)—L. R. Horrigan, Jr.
 V-P (Regulatory Rel)—K. S. Leibetter
 V-P (Cost Rel)—A. D. Maddox
 V-P & Compt—J. S. Brian
 V-P (Fossil Fuel Resources)—L. G. Brackeen
 V-P (Nuclear Oper)—Gerald E. Vaughn
 Treas—K. W. Nabors
 Purch Agt—B. Commander, Jr.
 Accts—Deloitte Haskins & Sells, Houston, Texas
 Primary Bank—Texas Commerce Bank, N.A.
 Primary Law Firm—Baker & Botts
 Revenue: \$3Bil Employees: 10,400
 *Also DIRECTORS—Other Directors Are:
 Charles E. Bishop John T. Cater
 Hollis R. Dean Joseph M. Hendrie
 Howard W. Horne James R. Leach
 Thomas B. McDade Kenneth L. Schnitzer, Sr.
 Jack T. Trotter

PRODUCTS: Generation, transmission, distr. & sale of electric energy
 S.I.C. 4911

HOUSTON METALS CORP.

910-800 Pender St., Vancouver, B.C., Can. V6G 2V6
 Tel. 604-683-4245

*Pres & Secy—Adolf A. Potancic
 Accts—Elliott Tulk Pryce & Anderson, Vancouver, B.C., Can.
 Primary Law Firm—Hornsworth & Schmidt
 Assets: \$1.96Mil
 Stock Exchange(s): VAN
 *Also DIRECTORS—Other Directors Are:
 H. Farris John Potancic
 George Stewart

PRODUCTS: Oil & gas explor.
 S.I.C. 1311

HOUSTON OIL & ENERGY INC.

422 Petroleum Bldg., Abilene, Texas 79603

Pres—C. Houston
 BUSINESS: Oil & gas explor.
 S.I.C. 1311

HOUSTON OIL & MINERALS CORPORATION

(Subs. Seagull Energy Corp.)

1100 Louisiana St., Houston, Texas 77002
 Tel. 713-757-3131

*Chrm & Pres—Philip Oakley
 *Exec V-P—Stephen D. Chabre
 Sr V-P—G. W. Frank
 V-P—G. E. Burgher, Jr.
 V-P—John L. Elliott
 V-P & Asst Secy—C. B. Mastre
 V-P—E. J. Milan
 V-P—Vernon M. Turner
 Treas—Gerald L. George
 Secy—Karl A. Stew
 Cont—T. S. Corbett

SUBSIDIARY

HOUSTON OIL INTER

(SUBS.)

Chrm & Pres—Philip Oakley

HOUSTON OIL & MINERALS COMPANY (SUBS.)

Chrm & Pres—S. D. Chabre

HOUSTON OIL & MINERALS COMPANY (SUBS.)

Chrm—Joe B. Foster

Pres & Chief Exec Officer—

HOUSTON OIL & MINERALS DEVELOPMENT

Chrm & Pres—S. D. Chabre

HOUSTON PRODUCTION

Chrm & Pres—S. D. Chabre

HOUSTON ROYALTY

Chrm & Pres—S. D. Chabre

Accts—Arthur Andersen & Co.

Primary Bank—Comptroller

Trust Co. of Chicago

Total Income: \$174,711

*Also DIRECTORS

J. D. Gooch

BUSINESS: Oil & gas explor.

S.I.C. 1311; 1312

HOUSTON OIL & MINERALS (SUBS.)

1901 Pender St.

V-P & Chief Exec Officer—

Accts—Post Messing & Co.

Primary Bank—First City

Primary Law Firm—

Sales: \$6,691M

Stock Exchange(s): NYSE

BUSINESS: Oil & gas explor.

S.I.C. 1311; 1312

HOUSTON OIL & MINERALS (SUBS.)

1100 Louisiana St.

Sr V-P (Admin)—George

Accts—Post Messing & Co.

Primary Bank—NCH

Sales: \$31.56M

Stock Exchange(s): NYSE

BUSINESS: Oil & gas explor.

S.I.C. 6799

HOUSTON OIL & MINERALS (SUBS.)

1200 Travis St.

*Chrm & Chief Exec Officer—

Vice-Chrm—

Pres & Chief Oper Officer—

*Exec V-P & Chief Gen Counsel—

*Exec V-P & Chief Fin Officer—

Sr V-P & Chief Admin Officer—

Sr V-P—R. G. Bennett

Sr V-P—J. E. K.

V-P & Treas—D. H.

V-P & Cont—D. G.

Secy—Peggy

Accts—Deloitte Haskins & Sells

Employees: 2,900

Stock Exchange(s): NYSE

*Also DIRECTORS

BUSINESS: Natural gas

S.I.C. 4922

HOUSTON OIL & MINERALS (SUBS.)

(Subs. Tereosol Inc.)

P.O. Box 670, Houston

*Pres—J. D. Craig

*Publishers & Treas—

V-P & Gen Coun—

V-P (Prod)—

V-P (Mktg)—

Editor in Chief—

Mgt Editor—

Chrm—George

Adv Dir—Jerry

Accts—Cotton

Primary Bank—

Primary Law Firm—

Employees: 1,200

*Also DIRECTORS

BUSINESS: Newspaper

S.I.C. 2711

HOUSTON OIL & MINERALS (SUBS.)

701 N. Sam Houston

*Pres & Treas—

V-P—Arthur

Secy—Irving L.

Primary Bank—

Primary Law Firm—

Grossberg

Sales: Over \$2M

*Also DIRECTORS

BUSINESS: Public

S.I.C. 4222; 4223

HOUSTON OIL & MINERALS (SUBS.)

9800 Market St.

*Chrm & Pres—Michael

V-P (Sales)—Richard

<p>RECORD OF COMMUNICATION</p> <p>Ref. 15</p>	<table border="0"><tr><td><input checked="checked" type="checkbox"/> XXX</td><td>Phone Call</td><td><input type="checkbox"/></td><td>Discussion</td><td><input type="checkbox"/></td><td>Field Trip</td></tr><tr><td><input type="checkbox"/></td><td>Conference</td><td><input type="checkbox"/></td><td colspan="3">Other (Specify)</td></tr></table> <hr/> <p>(Record of Item Checked Above)</p>	<input checked="checked" type="checkbox"/> XXX	Phone Call	<input type="checkbox"/>	Discussion	<input type="checkbox"/>	Field Trip	<input type="checkbox"/>	Conference	<input type="checkbox"/>	Other (Specify)		
<input checked="checked" type="checkbox"/> XXX	Phone Call	<input type="checkbox"/>	Discussion	<input type="checkbox"/>	Field Trip								
<input type="checkbox"/>	Conference	<input type="checkbox"/>	Other (Specify)										
<p>TO: Mr. Sewers Houston Water Authority (713) 223-1095</p>	<p>FROM: Pam Fetzer FIT - ICF ICF Technology (214) 744-1641</p>	<p>DATE: 3-14-89</p> <hr/> <p>TIME: 0830 hours</p>											
<p>SUBJECT: Intake Locations for Lake Houston</p> <hr/> <p>SUMMARY OF COMMUNICATION:</p> <p>The intakes are located on the dam (south end of lake on East Federal Road).</p> <p>They also pump water from the Trinity River south of Liberty, TX. They are building a treatment plant north of Ellington Field to treat the water pumped from the Lynchburg Canal.</p> <p>They service Nassau Bay, League City, Webster and Clear Lake City, among others for surface water. No water is obtained for drinking from Clear Lake.</p> <p style="text-align: right;"><i>Pam Fetzer</i></p>													
<p>CONCLUSIONS, ACTION TAKEN OR REQUIRED:</p>													
<p>INFORMATION COPIES</p> <p>TO:</p> <hr/> <p>EPA Form 1300-6 (7-72) Replaces EPA HQ Form 5300-3 Which May Be Used Until Supply Is Exhausted.</p>													

RECORD OF
COMMUNICATION

Ref. 16

☒ XXX

Phone Call

☐

Discussion

☐

Field Trip

☐

Conference

☐

Other (Specify)

(Record of Item Checked Above)

TO: Will Moberly
Clear Lake City
Water Authority

FROM: Pam Fetzner
FIT - ICF
ICF Technology
(214) 744-1641

DATE: 3-13-89

TIME: 1530 hours

SUBJECT: Public Water Source for Clear Lake City

SUMMARY OF COMMUNICATION:

Mr. Moberly said that they purchase the majority of their water from Houston (Lake Houston). They service 42,000 people with 90% surface water and 10% ground water. They have 6 wells that are screened in the Lower Chicot Aquifer. The well locations are as follows:

- | | |
|------------------------------|----------------------------|
| 1) 17507 El Camino Real | south end of town |
| 2) 600 Eldorado | east end of town off Hwy 3 |
| 3) 4231 Manor | Clear Lake forest |
| 4) 1600 Diane (golf course) | Taylor Lake, south of town |
| 5) 900 Barry Blvd. | south of #2 off of Hwy 3 |
| 6) 1700 Racida (golf course) | east of #4 (irrigation) |

The wells are screened at 200 to 250 feet. The static water level is \pm 190 feet.

Pam Fetzner


CONCLUSIONS, ACTION TAKEN OR REQUIRED:

INFORMATION COPIES

TO:

EPA Form 1300-6 (7-72)

Replaces EPA HQ Form 5300-3 Which May Be Used Until Supply Is Exhausted.

<p>RECORD OF COMMUNICATION</p> <p>Ref. 17</p>	<div style="display: flex; justify-content: space-between; align-items: flex-start;"> <div style="text-align: center;"> <input checked="" type="checkbox"/> XXX Phone Call <input type="checkbox"/> Conference </div> <div style="text-align: center;"> <input type="checkbox"/> Discussion <input type="checkbox"/> Other (Specify) </div> <div style="text-align: center;"> <input type="checkbox"/> Field Trip </div> </div> <hr style="border: 0; border-top: 1px solid black; margin: 10px 0;"/> <p style="text-align: center;">(Record of Item Checked Above)</p>	
<p>TO: Mr. Ernest Baker U.S.G.S. Hydrologist (512) 832-5791</p>	<p>FROM: Pam Fetzer FIT - ICF ICF Technology (214) 744-1641</p>	<p>DATE: 3-14-89</p> <hr style="border: 0; border-top: 1px solid black; margin: 5px 0;"/> <p>TIME: 1030 hours</p>
<p style="text-align: center;">SUBJECT: Hydrogeology of the Southeast Houston Area</p> <hr style="border: 0; border-top: 1px solid black; margin: 10px 0;"/> <p>SUMMARY OF COMMUNICATION:</p> <p>Mr. Baker stated that the wells for Webster were screened in the Lower Chicot Aquifer; more specifically the Alta Loma Sand member. The member is 120 feet thick and is stratigraphically between the Upper Chicot and the Evangeline Formations. The base of the Lower Chicot is approximately 665 feet below sea level.</p> <p>The Upper and Lower Chicot are interconnected but the Upper Chicot is a much tighter formation, consisting of a higher ratio of clay to sand.</p> <p>The Evangeline aquifer is not used as frequently as a drinking water source in the SE Houston area as the encroachment of salt water is likely and the Alta Loma Sand, being a shallower water bearing unit is a prolific producer.</p> <p>The Webster City well is 622 feet deep and is screened at 528 to 610 feet. The static water level in 1955 was 137 feet but in 1971 it was 207 feet.</p>		
<p>CONTINUATION OF SUMMARY OF COMMUNICATION: The Webster Power Plant Well is 664 feet deep, screened between 500 to 645 feet. The static water level in 1951 was 90 feet and in 1971 was 200 feet.</p> <div style="text-align: right; margin-top: 100px;">  </div>		
<p>INFORMATION COPIES</p> <p>TO:</p> <hr style="border: 0; border-top: 1px solid black; margin: 10px 0;"/> <p>EPA Form 1300-6 (7-72) Replaces EPA HQ Form 5300-3 Which May Be Used Until Supply Is Exhausted.</p>		

RECORD OF
COMMUNICATION

Reference 18

☒ Phone Call ☐ Discussion ☐ Field Trip
☐ Conference ☐ Other (Specify)

(Record of Item Checked Above)

TO: Joe Castleberry
Texas Public Utilities
Commission

FROM: Pam Fetzner
FIT - ICF
ICF Technology
(214) 744-1641

DATE: 3-7-89

TIME: 1100 hours

SUBJECT: Financial History of the Webster Generating Plant

SUMMARY OF COMMUNICATION:

He said that three units operated at this plant. The first turbine came on line in 1954 and the last in 1965. The last is the only unit currently operating. He did not know the net worth of this plant because the company values each unit separately and publishes the total cost of each type of unit. They do not generate separate reports for each plant. The original cost of the steam turbines is (b) (4) and the gas turbine is (b) (4)

Pam Fetzner

CONCLUSIONS, ACTION TAKEN OR REQUIRED:

INFORMATION COPIES

TO:

EPA Form 1300-6 (7-72)

Replaces EPQ HQ Form 5300-3 Which May Be Used Until Supply Is Exhausted.

RECORD OF
COMMUNICATION

Reference 19

XXX

Phone Call

☐

Discussion

☐

Field Trip

☐

Conference

☐

Other (Specify)

(Record of Item Checked Above)

TO: Dan Bulla
Shareholder Relations
Houston Industries
(713) 629-3060

FROM: Pam Fetzer
FIT - ICF
ICF Technology
(214) 744-1641

DATE: 3-7-89

TIME: 1040 hours

SUBJECT: Value of the Webster Generating Plant

SUMMARY OF COMMUNICATION:

He said that Houston Lighting and Power has a book asset value of (b) (4)
(b) (4) The net value is not known as it depends on what bank you ask.

The Webster Generating Plant is fully depreciated. He suggested that I speak with the Texas Public Utilities Commission.

Pam Fetzer

CONCLUSIONS, ACTION TAKEN OR REQUIRED:

INFORMATION COPIES

TO:

EPA Form 1300-6 (7-72)

Replaces EPQ HQ Form 5300-3 Which May Be Used Until Supply Is Exhausted.

RECORD OF
COMMUNICATION

Reference 20

☒

Phone Call

☐

Discussion

☐

Field Trip

☐

Conference

☐

Other (Specify)

(Record of Item Checked Above)

TO: Janet Greenwood
Galveston City, Dept.
of Health - Supervisor
(713) 534-2531

FROM: Pam Fetzner
FIT - ICF
ICF Technology
(214) 744-1641

DATE: 3-14-89

TIME: 1110 hours

SUBJECT: Private Ground Water Wells

SUMMARY OF COMMUNICATION:

She said that in Galveston County, privately owned wells are in use. A rough estimate of the Southeast Houston area for people that pump ground water from their own wells is about 8,360 people.

Pam Fetzner

CONCLUSIONS, ACTION TAKEN OR REQUIRED:

INFORMATION COPIES

TO:

EPA Form 1300-6 (7-72)

Replaces EPQ HQ Form 5300-3 Which May Be Used Until Supply Is Exhausted.

**TEXAS
WATER
DEVELOPMENT
BOARD**




Report 178

**GROUND-WATER DATA FOR
HARRIS COUNTY, TEXAS
VOLUME II
RECORDS OF WELLS, 1892-1972**

January 1974

No.	Owner	Driller	Date completed	Depth of well (ft.)	Casing		Water bearing unit	Altitude of land surface (ft.)	Water level		Method of lift	Use of water	Remarks
					Size (in.)	Depth (ft.)			Above (+) below land surface datum (ft.)	Date of measurement			
65-32-611	Seabrook Shipyard	McMasters and Poweroy	1939	523	6	523	C	7	50	1939	T, E 5	Ind	Reported yield 150 gpm with 40 ft. drawdown when drilled.
612	Iraa Christy	Wallie Burns	1913	521	4	521	C	12	49.4	June 7, 1940	N	N	Well destroyed.
613	Harris County WC and ID No. 50 El Lago	Layne Texas Co.	1965	390	10 6	530 590	CL	16	167	June 3, 1965	T, E 20	P	Screen from 537 to 577 ft. 2/
615	J. A. Wilkins	M. R. Pretty	1938	527	4	527	CL	11	48	June 17, 1938	N	N	Screen from 505 to 527 ft. Well destroyed. 2/
616	John Chapman	Wallie Burns	1920	660 ⁺	2	660 ⁺	C	10			N	N	Well destroyed.
621	Harris County WC and ID No. 55 Seabrook	Layne Texas Co.	1967	665	14 8	530 665	CL	19	181 218			P	Screen from 540 to 650 ft. Reported yield 1,254 gpm with 38 ft. drawdown when drilled. 1/ 2/
624	Harris County WC and ID No. 50 El Lago Well 3	do	1968	655	20 14	530 655	CL	16	213	June 5, 1968		P	Screen from 540 to 640 ft. Reported yield 1,153 gpm with 41 ft. drawdown when drilled. Test hole drilled to 664 ft. 2/
701	City of Webster Well 1	do	1955	622	10 5	-- 622	CL	24	137 207	Aug. 1955 Mar. 4, 1971	T, E 25	P	Screen from 528 to 610 ft. Test hole drilled to 693 ft. 1/ 2/
702	Houston Lighting and Power Co. Webster Plant Well 1	do	1952	636	16 10	475 636	CL	18	112	Apr. 10, 1952	T, E 200	Ind	126 ft. of screen between 480 and 618 ft. Reported yield 1,791 gpm with 98 ft. drawdown when drilled.
703	Houston Lighting and Power Co. Webster Plant Well 2	do	1951	664	24 20 10	494 492 664	CL	19	80 200	Sept. 1951 Feb. 11, 1971	Sub, E	Ind	125 ft. of screen between 500 and 645 ft. Reported yield 1,440 gpm with 76 ft. drawdown when drilled. 1/
705	S. Siabara	Layne Bowler Co.	1908	659	24 10	-- 659	CL	24	28.5 99.7	Apr. 3, 1931 Feb. 12, 1952	N	N	Screen from 547 to 659 ft. Formerly used for rice irrigation. Well destroyed. 2/ 3/
706	G. H. Witcomb	Aberson and Altemus	Old	563	2	563	C	26	34.9	Oct. 7, 1932	N	N	Well destroyed.
707	Webster School	Wallie Burns	1927	500 ⁺	3	500 ⁺	C	25	--	--	N	N	Well destroyed.
710	Galveston Houston Electric Co.	Layne Bowler Co.	1910	788	6	788	CL	5	--	--	N	N	61 ft. of screen between 588 and 653 ft. Well destroyed. 2/
711	Humble Pipe Line Co. Well 2	Layne Texas Co.	1938	660	8 6	592 660	CL	9	42 181.0	June 11, 1938 Feb. 17, 1971	Sub, E	Ind	Screen from 592 to 659 ft. Supplies pump station. 1/
738	Forest Park East Cemetery	do	1935	637	10 6	-- 637	CL	22	112	Mar. 2, 1955	T, E 30	Irr	Screen from 560 to 620 ft.
739	City of Webster Well 2	do	1967	645	14 8	515 645	CL	24	186 201.6	July 20, 1967 Mar. 4, 1971	T, E	P	Screen from 525 to 635 ft. Reported yield 510 gpm with 23 ft. drawdown when drilled. Test hole drilled to 670 ft. 1/ 2/
740	A. A. Polk	L. Wilson	1932	130	4	130	CU	27	--	--	C, E	D	Screen from 103 to 125 ft.

See footnotes at end of table.



<p style="text-align: center;">RECORD OF COMMUNICATION</p> <p style="text-align: center;">Ref. 22</p>	<div style="display: flex; justify-content: space-between; align-items: flex-start;"> <div style="text-align: center;"> <input checked="" type="checkbox"/> Phone Call <input type="checkbox"/> Conference </div> <div style="text-align: center;"> <input type="checkbox"/> Discussion <input type="checkbox"/> Other (Specify) </div> <div style="text-align: center;"> <input type="checkbox"/> Field Trip </div> </div> <hr style="border: 0; border-top: 1px solid black; margin: 5px 0;"/> <p style="text-align: center;">(Record of Item Checked Above)</p>	
<p>TO: Henry Fleming Corps of Engineers (409) 766-3070</p>	<p>FROM: Pam Fetzner FIT - ICF ICF Technology (214) 744-1641</p>	<p>DATE: 3-14-89</p> <hr style="border: 0; border-top: 1px solid black; margin: 5px 0;"/> <p>TIME: 1120 hours</p>
<p>SUBJECT: Surface Water use in the S.E. Houston Area</p> <hr style="border: 0; border-top: 1px solid black; margin: 10px 0;"/> <p>SUMMARY OF COMMUNICATION:</p> <p>Clear Lake and Clear Creek are used for recreation but not as a drinking water supply. Galveston Bay is used for commercial fishing and contact recreation. No intakes are on Clear Lake or Clear Creek because there are tidal surges up to I-45.</p> <div style="text-align: right; margin-top: 100px;"> <i>Pam Fetzner</i> </div>		
<p>CONCLUSIONS, ACTION TAKEN OR REQUIRED:</p>		
<p>INFORMATION COPIES TO:</p> <hr style="border: 0; border-top: 1px solid black; margin: 10px 0;"/> <p>EPA Form 1300-6 (7-72) Replaces EPA HQ Form 5300-3 Which May Be Used Until Supply Is Exhausted.</p>		

TX0006432

FORM
20
NPDES

U.S. ENVIRONMENTAL PROTECTION AGENCY
APPLICATION FOR PERMIT TO DISCHARGE WASTEWATER
EXISTING MANUFACTURING, COMMERCIAL, MINING AND SILVICULTURAL OPERATIONS
Consolidated Permits Program

I. OUTFALL LOCATION

For each outfall, list the latitude and longitude of its location to the nearest 15 seconds and the name of the receiving water.

A. OUTFALL NUMBER (list)	B. LATITUDE			C. LONGITUDE			D. RECEIVING WATER (name)
	1. DEG.	2. MIN.	3. SEC.	1. DEG.	2. MIN.	3. SEC.	
001	95	03	15	29	33	00	Clear Lake in Segment 2425
002	95	04	30	29	33	30	of the Texas bay waters
003	95	06	15	29	31	45	
004	95	06	15	29	31	45	

II. FLOWS, SOURCES OF POLLUTION, AND TREATMENT TECHNOLOGIES

A. Attach a line drawing showing the water flow through the facility. Indicate sources of intake water, operations contributing wastewater to the effluent, and treatment units labeled to correspond to the more detailed descriptions in Item B. Construct a water balance on the line drawing by showing average flows between intakes, operations, treatment units, and outfalls. If a water balance cannot be determined (e.g., for certain mining activities), provide a pictorial description of the nature and amount of any sources of water and any collection or treatment measures.

B. For each outfall, provide a description of: (1) All operations contributing wastewater to the effluent, including process wastewater, sanitary wastewater, cooling water, and storm water runoff; (2) The average flow contributed by each operation; and (3) The treatment received by the wastewater. Continue on additional sheets if necessary.

1. OUTFALL NO (list)	2. OPERATION(S) CONTRIBUTING FLOW		3. TREATMENT		
	a. OPERATION (list)	b. AVERAGE FLOW (include units)	a. DESCRIPTION	b. LIST CODES FROM TABLE 2C-1	
001	NONCONTACT ONCE-THROUGH	209.111 MGD			
	COOLING WATER AND PREVIOUSLY				
	MONITORED EFFLUENTS				
	(2/3 FLOW)				
002	NONCONTACT ONCE-THROUGH	104.222 MGD			
	COOLING WATER AND PREVIOUSLY				
	MONITORED EFFLUENTS				
	(1/3) FLOW)				
003	LOW VOLUME WASTEWATER:	0.047 MGD	COAGULATION, FLOCCULATION	2-D	1-G
	floor drainage		SEDIMENTATION, SKIMMING	1-U	XX
			AIR FLOTATION	1-H	
004	LOW VOLUME WASTEWATER:	0.069 MGD	COAGULATION, SEDIMENTATION	2-D	1-U
	demineralizer regenerant		NEUTRALIZATION	2-K	
	boiler blowdown				
104	METAL CLEANING WASTEWATER	0*	CHEMICAL PRECIPITATION	2-C	
			COAGULATION, SEDIMENTATION	2-D	
			NEUTRALIZATION	2-K	
	*infrequent discharge				
NOTE:	Sludge produced by all systems is disposed of offsite by a licensed contractor				

RECEIVED

APR 14 1987

6vv-13

V. INTAKE AND EFFLUENT CHARACTERISTICS

A, B, & C: See instructions before proceeding — Complete one set of tables for each outfall — Annotate the outfall number in the space provided.
NOTE: Tables V-A, V-B, and V-C are included on separate sheets numbered V-1 through V-9.

D. Use the space below to list any of the pollutants listed in Table 2c-3 of the instructions, which you know or have reason to believe is discharged or may be discharged from any outfall. For every pollutant you list, briefly describe the reasons you believe it to be present and report any analytical data in your possession.

1. POLLUTANT	2. SOURCE	1. POLLUTANT	2. SOURCE
Aluminum Sulfate	- Wastewater Treatment	Sulfuric Acid	- Wastewater Treatment - Demineralizer Process - Water Conditioning
Ammonia	- Water Conditioning		
Chlorine	- Water Conditioning - Disinfection	Various trace	- Proprietary Polymers - Laboratory Reagents
Sodium Nitrite	- Water Conditioning		
Sodium Phosphates (di and tri)	- Water Conditioning - Cleaning Solutions		
Sodium Hydroxide	- Wastewater Treatment - Demineralizer Process		

VI. POTENTIAL DISCHARGES NOT COVERED BY ANALYSIS

Is any pollutant listed in Item V-C a substance or a component of a substance which you currently use or manufacture as an intermediate or final product or byproduct?

☐ YES (list all such pollutants below)

☒ NO (go to Item VI-B)

The Light company

Houston Lighting & Power P.O. Box 1700 Houston, Texas 77001 (713) 228-9211

April 2, 1987

Mr. Joe Korpics
Environmental Protection Agency
Region VI
1445 Ross Ave.
Dallas, Texas 75202-2733

SUBJECT: WEBSTER ELECTRIC GENERATING STATION
NPDES DISCHARGE PERMIT NO. TX0006432

Attached please find a standard Form 2C renewal application for the Webster Electric Generating Station. The existing discharge permit for this facility will expire on October 3, 1987. Sampling data results required in support of this renewal will be transmitted at a later date.


HL&P requests one addition to the renewed permit. Consistent with EPA's practice with other once through cooling water power plants, the following acknowledgement should be added to Part III of the permit:

"The cooling water intake system is approved pursuant to the best technology requirements of Section 316(b) of the CWA"

The 316(b) Demonstration Document for this facility was submitted to EPA on January 27, 1981.

Should you have any questions with regard to this renewal, please do not hesitate to contact Kerry M. Whelan at (713)922-2200.

Sincerely,



W. F. McGuire, Manager
Environmental Protection Dept

RECEIVED
APR 14 1987

6vv-rs

KMW/pm/L9

cc: Mr. R. A. Newton (TWC)

Attachments

RECORD OF COMMUNICATION Reference 24	<div style="display: flex; justify-content: space-between;"> <div style="text-align: center;"> <input checked="checked" type="checkbox"/> XXXX <input type="checkbox"/> </div> <div style="text-align: center;"> <input type="checkbox"/> <input type="checkbox"/> </div> </div> <div style="display: flex; justify-content: space-between;"> <div style="text-align: center;">Phone Call Conference</div> <div style="text-align: center;">Discussion Other (specify)</div> <div style="text-align: center;"> <input type="checkbox"/> Field Trip </div> </div>	
(Record Of Item Checked Above)		
TO: Gene Keepper U.S. EPA Biologist (214) 655-2263	FROM: Pam Fetzner FIT - ICF (214) 744-1641	DATE: 3-23-89 TIME: 1523 hours
SUBJECT: Wetlands in the Southeast Houston Area		
SUMMARY OF COMMUNICATION: <p style="margin-left: 40px;">Gene said that the area around the Houston Lighting and Power Plant (Webster) is a coastal wetland. The impoundments are located in this wetland. The wetlands are located in the area of Clear Lake, Clear Creek and into Galveston Bay.</p>		
CONCLUSIONS, ACTION TAKEN OR REQUIRED: <div style="height: 40px;"></div>		
INFORMATION COPIES TO: <div style="height: 40px;"></div>		
EPA Form 1300-6 (7-72) Replaces EPA HQ Form 5300-3 Which May Be Used Until Supply Is Exhausted.		

CME

Mail To:

Kirby Bldg.

1504 Main Street
Suite 900
Dallas, TX 75201

TWC Req. No. 31633

TEXAS WATER COMMISSION
Comprehensive GW Monitoring Evaluation (CME) Report

INSPECTION COVER SHEET

EPA ID No. TXD0008377369

SEP 10 1987

C.O. Use Only

688-7 AN

Date Entry Date

NAME OF COMPANY Houston Lighting and Power - Webster

SITE ADDRESS P.O. Box 1700, Houston, TX Tel 713 922-2186

COUNTY Harris TYPE OF INDUSTRY Electric Power Generation

Current GW Monitoring Status: HL&P is no longer sampling

(Specify for each Waste
Management Area "WMA")

Wells.

Inspection Information:

Inspector(s) Robert Hahn Date(s) 4-24-87

Participants _____

Type of Inspection (check) EV CME X → SA X

Evaluation:

S U

A. Monitoring System

B. Sampling Procedures

C. Analysis & Results X

D. Records & Response

Signed: Robert W. Hahn
Inspector

Date: 5-27-87

Signed: Marlyn G. Long
Reviewer

Date: 9-15-87

PSL 9/16/87

S= Satisfactory U= Unsatisfactory

Overall Evaluation: Compliant X NonCompliant

TEXAS WATER COMMISSION
Comprehensive GW Monitoring Evaluation (CME) ReportCONTENTS SHEETFACILITY NAME Houston Lighting and Power

- X 1. Code Sheet (0814)
- X 2. Interoffice Memorandum (IOM)
- X 3. Inspection Cover Sheet
- X 4. Technical Report, with supporting Attachments
 - A. Monitoring System
 - B. Sampling Procedures
 - X C. Analysis and Results
 - D. Records and Response
- 5. EV Inspection Checklist (if joint inspection with District Office)
- 6. Notice of Violation (NOV) / Enforcement Letter to Facility
- 7. Other (describe) _____

* If a required Checklist is omitted, Explain: _____

Texas Water Commission

INTEROFFICE MEMORANDUM

TO : The Files DATE: 9-4-87

THRU : Mr. Russel Kimble, Reports and Management Group
Hazardous and Solid Waste Division

FROM : *RWH* Robert Hahn, RCRA Ground-water Enforcement Unit
Hazardous and Solid Waste Division

SUBJECT: Houston Lighting and Power- Webster Generating Station

Attached is an addendum report to the Comprehensive Monitoring Evaluation (CME) of Houston Lighting and Power which includes results of analysis of monitor well samples taken during the inspection. These results were not available at the time of the CME report submittal. The attachment to this memo should be affixed to the original CME report.

Summary:

On April 24, 1987, a Comprehensive Monitoring Evaluation was conducted at the HL&P Webster Generating Station, Harris County, Texas.

RWH Discrepancies that exist in the HL&P analytical program include:

1. Results of spikes, duplicates or blanks are not reported.
2. Cation- anion data for samples collected from MW-1 appears to be erroneous and dissimilar to split sample results analyzed by the Texas Department of Health.

Houston Lighting and Power will be requested to explain the discrepancies in their data.

C. Analysis and Results

1. Tabulation of Analytical Methods - Attachment P
Indicate directly on Attachment which analyses are performed by:
 - a. Off-site contract laboratory (*)
 - b. On-site operator laboratory (**)
 - c. Field measurement (***)
2. Are all samples analyzed with an EPA-approved method (yes/no)? YES
. If not, indicate on Attachment (above) which methods are not EPA-approved.
3. Analytical Methods
 - a. Has the operator consistently utilized the same analytical methodology during the monitoring program (yes/no)? YES
 - b. Has the operator changed analytical laboratories during the monitoring program (yes/no)? Yes, however HL&P has retained APR as the contract lab for the past 3 years.
 - c. Describe any inconsistencies and how the operator has tried to resolve them: None, see comments below (Section C.5.c) for peculiarities in the May 31, 1987 laboratory data.
4. What is the sample analysis turn-around time (i.e., the time required to receive results from the laboratory)? 1 month.
5. Laboratory Quality Assurance/Quality Control (QA/QC)
 - a. Describe the laboratory's QA/QC program:

The laboratory QA/QC program is uncertain. The necessary information such as results of laboratory blanks, spikes and replicates was not included.
 - b. Example of analytical results and/or QA/QC results as reported by the laboratory to the operator - Attachment Q
 - c. Do the results of the QA/QC program verify the validity and reliability of the laboratory and field-generated data (yes/no)?

No QA/QC results were included with the laboratory results; therefore, the reliability of the data is questionable.
6. Review the operator's records of analytical results for:
 - a. Parameters of initial year of sampling which exceed IPDWS;

Attachment R

b. Parameters sampled as part of a Ground Water Quality Assessment Plan. Included as Attachment S.

7. Overall, does the analysis program enable the reliable detection of, and for assessment purposes, the quantification of a release of hazardous constituents to ground-water from the monitored WMA (yes/no)? No, without appropriate QA/QC data included in the report and the large discrepancy observed between the TWC and HLP data for the MW-1 sample collected on 4-24-87, the analysis program is unreliable and therefore noncompliant.

8. Results of co-sampling events:

a. Results of Operator Sample Analysis - Attachment T

b. Results of TWC Sample Analysis

1) COC Tags - Attachment U

2) Tabulated Inorganic Constituents - Attachment V

3) Tabulated Organic Constituents - Not sampled

c. Do TWC results confirm operator results (yes/no)? NO .
If not, describe apparent discrepancies between data sets and possible sources of error:

1. TWC values and APR values differ in some parameters by over 50 %. For example, bicarbonate values for MW-1 are 254 mg/L for the TWC sample and 3256 mg/L for the HLP sample.

A percent difference $\frac{(A - B)}{(A + B)/2} \times 100$ was calculated for each

of the cations and anions in the MW-1 sample:

Parameter (mg/L)	TWC	HLP	% Diff.
Calcium	559	716	25%
Magnesium	246	263	6%
Sodium	2139	2725	24%
Potassium	3	6	66%
Bicarbonate	254	3256	171%
Sulfate	568	350	47%
Chloride	4463	4173	6.7%

2. A percent error of less than 1 % was calculated for both the TWC and HLP MW-1 sample data. This seems peculiar considering the large difference in individual values between the TWC and HLP data sets (Attachment 2). It is likely that the data was incorrectly reported by the laboratory in order for the data to fall within an acceptable amount of error. Furthermore, the TWC data appears to fall in the range of historical results.

3. An explanation has been provided above noting the discrepancy between the TWC and HLP data. The error appears to lie only with the sample for MW-1. The HL&P report indicated that the bicarbonate analysis was performed on a sample that was acidified and filtered in the field. As indicated in Section II.B. of this CME, no samples were filtered in the field. Even though analyzing for bicarbonate from an acidified sample is considered incorrect in procedure, it is also peculiar that a high value for bicarbonate would be found on an acidified sample regardless of the acid that was used. It is possible that the other cations were analyzed from a field acidified sample because their values appear much higher with respect to the TWC samples, but this would not account for an error of less than 1 %.
- d. Compare data sets to historical results - note here any parameters which do not occur within previously observed ranges:

A summary of the historical results is provided in Attachment W

Historically, there exists some variability in the range of concentrations for conductivity, especially in monitor well 1. As shown in section 9 below, the quality of water at MW-1 is highly influenced by the quality of water from the discharge canal located approximately 100 feet to the north.

TOC values in all wells appear highest in 1982 during the first year of sampling which could correlate with a change in laboratories in 1983.

As shown in Attachment S, apparent small increases in concentrations of cation-anion data can be observed in the 4-24-87 samples relative to the 1984 Assessment Report data. These increases could be due to differences in sampling techniques, seasonal variability, or differences in contract laboratories.

9. Describe the ground-water quality, based on TWC results, utilizing Stiff diagrams, tri-linear plots, etc., to compare inorganic water quality between wells. Include the diagram(s) as Attachment X. Do the results indicate changes in ground-water quality downgradient of the WMA (yes/no)? NO . If yes, explain in comments.

Comments:

The ground water quality in the monitored zone at the HL&P site can be described as a predominantly sodium -chloride type water. As part of a ground water assessment program conducted in 1984, HL&P sampled and analyzed water from the 4 monitor wells as well as surface water from the impoundments and the cooling water discharge canal. A map showing the sample locations is presented as

Attachment Y₁²⁰⁴. A table presenting the data is shown in Attachment Y₂. From this data, one can observe the similarity between the analysis of sample MW-1 and the discharge canal sample SI-4, especially in the magnesium, chloride and conductivity concentrations. The conclusions of the assessment report stated that any seepage from the surface impoundments that might be detected in the monitor wells would be masked by the ground-water mound from the discharge canal. This conclusion, although somewhat oversimplified, points out the difficulty in detecting a release from a surface impoundment or delineating the source of that release from one of several impoundments. The range in water qualities from the monitor wells and the surface impoundments is shown on the 1984 Assessment Report trilinear and stiff diagrams (Attachment X₂²⁰⁴) and as summarized below: Attachment X₁ (204)

1. The inorganic acid surface impoundment (SI-1) plots in the lower field of the diamond shaped domain of the trilinear diagram due to its high bicarbonate and high sodium concentrations.
2. The demineralizer regenerant surface impoundment (SI-2) plots in the sodium-sulfate domain.
3. Monitor wells 2, 3 and 4 plot close to the discharge canal sample (SI-4), the demineralizer regenerant pond (SI-2) and the sludge drying bed (SI-6) indicating the possible influences of the surface waters on the ground water.
4. Monitor wells 2, 3 and 4 appear to plot in the middle of an imaginary line connecting monitor well 1 and the inorganic acid surface impoundment 1 (SI-1) indicating a lesser degree of influence from the discharge canal (SI-4) and possible mixing with water quality from the inorganic acid surface impoundment.

Mixing- In order to determine if the ground-water qualities in the monitor well samples represent mixing of ground water with surface water sources, a binary mixing model (HC-GRAM4) was used. The output from the computer program indicated that the data did not fit any binary mixing calculations. If mixing has occurred, it is more complicated than the simple binary mixing model can predict.

5. A release from anyone of the surface impoundments would be difficult to determine. For example, a release from the demineralizer regenerant impoundment might result in increases in sulfate but decreases in chloride and alkalinity in the monitor well samples. At this site, cations and anions would not serve as useful indicator parameters.

TWC CME data

TWC and HL&P samples collected during the CME were plotted on stiff and trilinear diagrams (Attachment Z) to illustrate variability between the two sources of laboratory data. The TWC sample

collected at MW-1 more closely falls within the previous observed concentrations for this well than the HL&P sample.

10. Releases to ground water:

- a. Were hazardous constituents detected by TWC sample analysis (yes/no)? YES. If yes, identify unit and constituents.

An arsenic concentration of 0.040 mg/L was detected in MW-1 near the IPDWS maximum concentration level for arsenic (As=0.050 mg/L). A Chromium concentration of 0.076 mg/ in MW-1 exceeds the IPDWS maximum concentration level of 0.050 mg/L for chromium. A mercury concentration of 0.0011 mg/L was detected in MW-2 near the IPDWS maximum concentration level for mercury (0.002 mg/L).

The arsenic and chromium indicates a release has occurred either from a pond storing cooling tower blowdown or from a release of acidic wastes from which leaching of the soil beneath the impoundments has occurred. Both are difficult to prove based on the fact that historically low pH's have not been detected in any of the monitor wells. Soil sample results presented in the closure certification (9-2-86) possibly provide some evidence that leaching may have taken place. As shown on Attachment AA, the arsenic, barium, chromium, lead and selenium concentrations in the background samples were all higher than the values found in samples of the clay liner. This data possibly indicates that the metals were leached from the soils and carried into the ground water.

- b. Has the operator detected hazardous constituents in the ground water (yes/no)? NO. If yes, identify unit and constituents.

Arsenic and chromium were not detected above the detection limits at the APR laboratory.

- c. Do the TWC sample results confirm operator results (yes/no)? . If no, explain in comments.

NO. The detection limit used by HL&P for chromium (0.100 mg/L) is above the IPDWS for chromium, hence it was not detected.

Mercury was not analyzed by the HLP contract lab.

- d. Do TWC sample results and/or operator results indicate non-hazardous constituents have been released from the WMA (yes/no)? NO. If yes, explain in comments.



ANALYTICAL METHODS

All samples obtained for monitoring should be analyzed in accordance with approved EPA methods which are listed below.

<u>Parameter</u>	<u>Method</u>	<u>Reference</u>	<u>Description</u>
* * Conductivity	120.1	1	Conductometric
* * pH	150.1	1	Electrometric
* Chloride	325.3	1	Titrimetric
* Sulfate	375.4	1	Turbidimetric
* Iron	236.1	1	AA/Aspiration
* Manganese	243.1	1	AA/Aspiration
* Sodium	273.1	1	AA/Aspiration
* Phenol	420.1	1	Colorimetric
* Total Organic Carbon	415.1	1	Combustion/IR
* Total Organic Halogen	450.1	2	Combustion/HECD

1. EPA 600/4-79-020, March 1979, "Methods for Chemical Analysis of Water and Wastes".
2. EPA Interim Method, November, 1980, "Interim Method for Total Organic Halide".

Attachment P

ANALYTICAL
PETROLEUM
RESEARCH

laboratories, Inc.

HOUSTON LIGHTING AND POWER COMPANY
12301 KURLAND
HOUSTON, TEXAS 77034
ATTENTION: MR. RICHARD BYE

MAY 31, 1987

INVOICE NO: 13272
CERTIFICATE #32134

=====

SUBMITTED BY: DOUG CHIN
LOCATION: WEBSTER
DATE OF SAMPLE: APRIL 24, 1987 DATE RECEIVED: APRIL 24, 1987
DESCRIPTION: MW-1 A

SAMPLE ANALYSIS =====	RESULTS IN MG/L =====	DATE =====	TIME =====	ANALYST =====
CALCIUM	716	05/24	0900	GT
MAGNESIUM	263	05/14	0800	GT
SODIUM	2725	05/18	0800	DD
POTASSIUM	6.0	05/14	1200	GT
BICARBONATE	3256 *	05/20	1630	DD
CARBONATE	<1	05/20	1630	DD
CHLORIDE	4173	05/18	1100	TP
SULFATE	350	05/19	1300	JR
TOTAL DISSOLVED SOLIDS	11,546	04/29	0900	GT
MANGANESE	0.8	05/14	1000	DD
FLUORIDE	0.2	05/20	1600	TP
ARSENIC	<0.02	05/11	1200	GT
BORON	1.45	05/14	1100	GT
CADMIUM	<0.01	05/11	1100	GT
CHROMIUM	<0.1	05/11	1200	GT
IRON	8.33	05/19	0800	DD

PAGE ONE OF TWO

Attachment Q

7

TDWR Registration #31633

WEBSTER GENERATING STATION

Groundwater Parameters and their Concentrations Which Exceed the EPA
Interim Primary Drinking Water Standards

	<u>Parameter</u>	<u>Concentration</u>
<u>1st Quarter</u>		
Well 3	Gross Beta	25 \pm 3 pCi/l
	Coliform	150 1/100 ml
Well 4	Gross Beta	7 \pm 2 pCi/l
	Coliform	1700 1/100 ml
<u>2nd Quarter</u>		
Well 1	Barium	13.4 mg/l
Well 2	Barium	3.7 mg/l
Well 3	Barium	4.1 mg/l
Well 4	Barium	3.5 mg/l
<u>3rd Quarter</u>		
No parameters found to exceed drinking water standards		
<u>4th Quarter</u>		
Well 1	Mercury	.003 mg/l
Well 4	Mercury	.003 mg/l
	Coliform	8 1/100 ml

Attachment R

Parameters	MW-1 UPGRADIENT		MW-2 DOWNGRADIENT	
	1984 Assessment	TWC-1987 CHE	1984 Assessment	TWC-1987 CHE
Calcium	560	559	59	69
Magnesium	270	246	34	42
Potassium	3.8	3	2.4	2
Sodium	1700	2139	300	419
Acidity	0	-	0	-
Alkalinity	190	208	374	492
Sulfate	450	568	160	248
Chloride	3900	4463	220	352
Fluoride	0.9	0.6	1.3	1.4
Nitrate	<0.05	0.03	<0.05	0.66
Silica	12	19	2	21
Copper	0.28	0.064	<0.01	<0.02
Iron	0.25	74.6	<0.05	3.71
Zinc	1.6	0.150	0.05	<0.02
Conductivity	12000.	17000.	1600.	3190
Dissolved Solids	8700.	8123	990	1453
pH	7.24	7.02	7.93	7.10

Attachment S
Comparison of Results
of Assessment 1984 with
CHE-TWC 1987 ^{ROW} for MW1
and MW-2.

The Light company

Houston Lighting & Power P.O. Box 1700 Houston, Texas 77001 (713) 228-9211

June 29, 1987

Mr. Robert Hahn
Texas Water Commission
Hazardous & Solid Waste Division
P. O. Box 13087
Capitol Station
Austin, Texas 78711


SUBJECT: ANALYTICAL RESULTS OF SAMPLES FROM GROUNDWATER
MONITORING WELLS AT HL&P'S WEBSTER GENERATING
STATION TWC NO. 31633

Dear Mr. Hahn:

Attached per your request are the results of the two samples we collected in duplicate with your samples on April 24, 1987. As discussed with you when you made your inspection visit, our compliance samples are analyzed by an outside contract commercial laboratory, in this case, APR Laboratories.

Should you have any additional questions, please contact Mr. D. B. Chin at (713) 922-2203.

Sincerely yours,



R. W. Lawhn, Manager
Environmental Assessment &
Waste Management
Environmental & Research Department

DBC/jcc:L10

Attachments

Attachment T



RECEIVED
JUN 3 1987

ANALYTICAL
PETROLEUM
RESEARCH

ENVIRONMENTAL
LABORATORY

Laboratories, Inc.

HOUSTON LIGHTING AND POWER COMPANY
12301 KURLAND
HOUSTON, TEXAS 77034
ATTENTION: MR. RICHARD BYE

MAY 31, 1987

INVOICE NO: 13272
CERTIFICATE #32134

=====

SUBMITTED BY:	DOUG CHIN		
LOCATION:	WEBSTER		
DATE OF SAMPLE:	APRIL 24, 1987	DATE RECEIVED:	APRIL 24, 1987
DESCRIPTION:	MW-1 A		

SAMPLE ANALYSIS =====	RESULTS IN MG/L =====	DATE =====	TIME =====	ANALYST =====
CALCIUM	716	05/24	0900	GT
MAGNESIUM	263	05/14	0800	GT
SODIUM	2725	05/18	0800	DD
POTASSIUM	6.0	05/14	1200	GT
BICARBONATE	3256 *	05/20	1630	DD
CARBONATE	<1	05/20	1630	DD
CHLORIDE	4173	05/18	1100	TP
SULFATE	350	05/18	1300	JR
TOTAL DISSOLVED SOLIDS	11,546	04/29	0900	GT
MANGANESE	0.8	05/14	1000	DD
FLUORIDE	0.2	05/20	1600	TP
ARSENIC	<0.02	05/11	1200	GT
BORON	1.45	05/14	1100	GT
CADMIUM	<0.01	05/11	1100	GT
CHROMIUM	<0.1	05/11	1200	GT
IRON	8.33	05/19	0800	DD

PAGE ONE OF TWO

PAGE TWO

CERTIFICATE NUMBER: 32134

* THIS SAMPLE WAS FILTERED AND ACIDIFIED IN THE FIELD.

QUALITY ASSURANCE: THESE ANALYSES ARE PERFORMED IN ACCORDANCE WITH EPA GUIDELINES FOR QUALITY ASSURANCE. THESE PROCEDURES INCLUDE THE FOLLOWING AS MINIMUM REQUIREMENTS: COMPARISONS AGAINST KNOWN STANDARDS IN EACH RUN, ONE IN TEN SAMPLE SPLITS, AND A QUARTERLY METHODS REVIEW AGAINST KNOWN SPIKE SAMPLES.

A P R LABORATORIES, INC.

Sammy Russo ^{gh}

Sammy Russo

SR/gf1



RECEIVED
14 JUN 1987

**ANALYTICAL
PETROLEUM
RESEARCH**

ENVIRONMENTAL ANALYSIS
ENV. ANALYST/CLERK

Laboratories, Inc.

HOUSTON LIGHTING AND POWER COMPANY
12301 KURLAND
HOUSTON, TEXAS 77034
ATTENTION: MR. RICHARD BYE

MAY 31, 1987

INVOICE NO: 13272
CERTIFICATE #32135

=====

SUBMITTED BY:	DOUG CHIN			
LOCATION:	WEBSTER			
DATE OF SAMPLE:	APRIL 24, 1987	DATE RECEIVED:	APRIL 24, 1987	
DESCRIPTION:	MW-2 A			

SAMPLE ANALYSIS =====	RESULTS IN MG/L =====	DATE =====	TIME =====	ANALYST =====
CALCIUM	76.2	05/24	0900	GT
MAGNESIUM	42.1	05/14	0800	GT
SODIUM	306	05/18	0800	DD
POTASSIUM	3.4	05/14	1200	GT
BICARBONATE	450	05/20	1630	DD
CARBONATE	<1	05/20	1630	DD
CHLORIDE	345	05/18	1100	TP
SULFATE	175	05/18	1300	JR
TOTAL DISSOLVED SOLIDS	1400	04/29	0900	GT
MANGANESE	<0.1	05/14	1000	GT
FLUORIDE	0.4	05/20	1600	TP
ARSENIC	<0.02	05/11	1200	GT
BORON	<0.1	05/14	1100	GT
CADMIUM	<0.01	05/11	1100	GT
CHROMIUM	<0.1	05/11	1200	GT
IRON	2.07	05/19	0800	DD


PAGE ONE OF TWO

PAGE TWO

CERTIFICATE NUMBER: 32135

QUALITY ASSURANCE: THESE ANALYSES ARE PERFORMED IN ACCORDANCE WITH EPA GUIDELINES FOR QUALITY ASSURANCE. THESE PROCEDURES INCLUDE THE FOLLOWING AS MINIMUM REQUIREMENTS: COMPARISONS AGAINST KNOWN STANDARDS IN EACH RUN, ONE IN TEN SAMPLE SPLITS, AND A QUARTERLY METHODS REVIEW AGAINST KNOWN SPIKE SAMPLES.

A P R LABORATORIES, INC.

A handwritten signature in cursive script, reading "Sammy Russo", with a small flourish at the end.

Sammy Russo

SR/gfl

No. **GW 03801**P.O. Box 13087, Capitol Station
Austin, Texas 78711Org. No. 444
Sample No. MW-1

Owner HLP Address Houston, TX Zip _____
 County Harris Well No. MW-1
 Location Webster station #31633
 Date Drilled _____ Depth _____ Aquifer Beaumont FM
 Water Level _____ Sample After Pumping _____ Mins. (Hrs.) Yield _____ GPM Temperature _____ °F
 Point of Collection well MW-1 Appearance _____ Clear Turbid Red. & Silty Color
 Use monitor Remarks _____ (Over)
 Date Collected 4-24-87 Time 10:00 AM By Robert Hahn
 Send copy of completed analysis to Robert Hahn TDWR Office No. 1116A

TDWR-0778 (Rev. 10-24-84)

No. **GW 03801**

TEXAS DEPARTMENT OF WATER RESOURCES

P.O. Box 13087, Capitol Station

 Work No. 4003
 Org. No. 444
 Sample No. MW-1
Point of Collection MW-1Lab Used TDHMethod of Preservation none

Type of Facility _____

Date Completed 4/28/87Analyst's Signature ML

	Mg/l	EPM		Mg/l	EPM	Other Ions	Mg/l
<input checked="" type="checkbox"/> Silica	19		<input checked="" type="checkbox"/> Carbonate	0	0.00	<input checked="" type="checkbox"/> Bromide	3.1
<input checked="" type="checkbox"/> Calcium	559	27.96	<input checked="" type="checkbox"/> Bicarbonate	254	4.16	<input checked="" type="checkbox"/> Iodide	1.2
<input checked="" type="checkbox"/> Magnesium	246	20.22	<input checked="" type="checkbox"/> Sulfate	568	11.83		
<input checked="" type="checkbox"/> Sodium	2139	93.00	<input checked="" type="checkbox"/> Chloride	4463	125.82		
	Total	141.18	<input checked="" type="checkbox"/> Fluoride	0.6	0.03		
<input checked="" type="checkbox"/> Potassium	3	0.02	<input checked="" type="checkbox"/> Nitrate-N	0.03	0.00		
<input checked="" type="checkbox"/> Boron	0.91	141.26	pH	7.6			
<input checked="" type="checkbox"/> Iron	see heavy metals		Total	8123	141.85		
			Dissolved Solids (sum)				
			Phenolphthalein Alkalinity as CaCO ₃				
			Total Alkalinity as CaCO ₃		(4.16) 20.8		
			Total Hardness as CaCO ₃				
			Specific Conductance (Micromhos/cm)		6250		
			Diluted Conductance (Micromhos/cm)				

Remarks _____

[*] Items will be analyzed if checked, total iron requires separate sample.

TDWR-0778 (Rev. 10-24-84)

Attachment U

HM 11346 H L & P
Charger Name Webster
nt Name
thod of Flow Measurement
District 7 County Harris Basin
Time Collected 11:50 AM
Point of Collection monitor well
MW-2-

PERMIT NUMBER	PAGE NO.	CARD TYPE	DATE			MAT. STAMP	Chlorine Contact Time
			Mo.	Day	Yr.		
910121314151617181920							
1633			04	24	87		Date Shipped 4-27-87
Collector's Signature [Signature]							
21 CODE	26 PARAMETER VALUE	35 CODE	40 PARAMETER VALUE	49 CODE	54 PARAMETER VALUE	62	
Flow (gpd)		Water Temperature (°F)		pH			
0056		00011		00400			
O. (mg/l)		Turbidity (JTU)					
0300		00070					

KAS DEPARTMENT OF WATER RESOURCES

HM 11346 District 7 Lab Used TDH Lab. No. EW71412
Sample: Heavy Metals
b HW-2 Composite Hr. Type Facility surf. independent
Observations APR 27 '87
Date Completed
Analyst's Signature

21 CODE	26 PARAMETER VALUE	35 CODE	40 PARAMETER VALUE	49 CODE	54 PARAMETER VALUE	62
Arsenic ✓		Barium ✓				
	< 25		71			
Cadmium ✓		Chromium ✓		Copper ✓		
	< 10		< 20		< 20	
Lead ✓		Manganese ✓		Mercury ✓		
	< 30		43		1.1	
Nickel ✓		Selenium		Selenium		
	< 20					
Zinc ✓		Iron (Total) ✓		Values are µg/l		
	< 20		3710			

Attachment 11

Attachment V Tabulated TWC-CME Results

ter (mg/L)	MW-1	MW-2
um	559	69
nesium	246	42
assium	3	2
dium	2139	419
ilica	19	21
oron	0.91	0.35
ron	74.6 ²	3.710 ²
arbonate	0	0
Bicarbonate	254	600
ulfate	568	248
chloride	4463	352
Fluoride	0.6	1.4
Nitrate	0.03	0.66
Bromide	3.1	0.3
Iodide	1.2	5.9
Senic	0.040 ^{RWH}	0.025
Barium	0.052	0.071
admium	<0.010	<0.010
hromium	0.076' ^{RWH}	<0.020
opper	0.064	<0.020
ead	<0.050	<0.050
Manganese	0.850 ²	^{RWH} 0.043
lcury	0.0004	0.0011
ickel	0.060	<0.020
Zinc	0.150	<0.020

(W)

note
Exceeds IPDWS Maximum Concentration Level
Exceeds Secondary Drinking water Standards

Attachment W Summary of Historical Results

HW1

Parameter Units Sample Type	Ground Water (m, ft) Sample Number	pH Standard Grab	Conductivity (micro mhos/cm) Grab	Total Dissolved Solids (mg/l) Grab	Total Dissolved Solids (mg/l) Grab	Chloride (mg/l) Grab	Iron (mg/l) Grab	Manganese (mg/l) Grab	Phenols (mg/l) Grab	Sodium (mg/l) Grab	Sulfate (mg/l) Grab
Date											
**First Year (Initial) Background arithmetic mean											
052882	ND	7.13	9300	16	0.114	2760	0.39	0.15	< 0.01	1500	440
080582	6	7.13	9675	56	0.091	3430	0.05	0.21	< 0.01	1000	305
092982	7	7.03	12000	42	0.026	4094	1.00	0.17	< 0.01	2300	350
111982	7	7.25	13750	33	0.025	4931	1.45	0.11	< 0.01	1363	440

1983	5	7.3	9000	4.2	0.04	4290	2.35	0.15	< 0.01	1900	1170
1984	8.28	7.2	14,500	1.0	0.01	4,900	0.11	0.04	< 0.001	2,100	620
1985	9.48	6.9	15,925	1.4	< 0.005						512
1986	9.48	6.72 7.02	7,625 3863	13.0 5.5	0.009 < 0.005	3600	4.7	0.18	< 0.005	1015	160
1987 _{CME}						4173	8.33	0.8	-	2725	350
1987 _{TWC}	9.65	7.02	17,000	-	-	4463	74.6	0.85	-	2139	568

HW2

Parameter Units Sample Type	Ground Water (m, ft) Sample Number	pH Standard Grab	Conductivity (micro mhos/cm) Grab	Total Dissolved Solids (mg/l) Grab	Total Dissolved Solids (mg/l) Grab	Chloride (mg/l) Grab	Iron (mg/l) Grab	Manganese (mg/l) Grab	Phenols (mg/l) Grab	Sodium (mg/l) Grab	Sulfate (mg/l) Grab
Date											
**First Year (Initial) Background arithmetic mean											
052882	ND	7.85	2600	19	0.176	522	0.3	0.11	< 0.01	1300	250
080582	10	7.58	2500	70	0.103	691	0.48	0.07	< 0.01	350	233
092982	11	7.47	3000	68	0.043	534	1.70	0.19	< 0.01	420	170
111982	11	7.87	2700	25	0.144	584	1.75	0.20	< 0.01	265	200

1983	9	7.61	1507	6	0.07	350	0.75	0.05	< 0.01	325	185
1984	7.61	7.4	2300	1	< 0.005	330	< 0.05	0.03	0.003	340	190
1985	9.11	7.27	1853	2.3	< 0.005	-	-	-	-	-	168
1986	8.11	7.07 7.8	3400 1375	< 1.0 7.0	< 0.005 < 0.005	254	3.1	0.06	0.02	123	150
1987 _{CME}						345	2.07	< 0.1	-	306	175
1987 _{TWC}	11.46	7.10	3190	-	-	352	3.71	0.043	-	419	248

1

Нв3

1983	15	7.11	2437	2.7	0.07	750	1.47	0.05	<0.01	410	58
1984	3.7	7.2	3400	<1.0	<0.005	720	<0.05	0.01	0.005	380	65
1985	3.94	6.87	2955	0.7	<0.005	-	-	-	-	-	-
1986	3.94	6.88	2625	1.25	<0.005	340	2.0	<0.01	<0.005	208	42
1987	Not sampled.										

MW4

[illegible]

HM 11348
Charger Name
District 7 County Harris Basin
Time Collected 10:30 A
Point of Collection Equipment - Follows
Bailer decon
Method of Flow Measurement

PERMIT NUMBER	PAGE NO.	CARD TYPE	DATE			NAT. STAMP	Chlorine Contact Time
			Mo.	Day	Yr.		
11633	9 10 12 13		14 15 16 17 18 19 20				Date Shipped 4-27-87
							Collector's Signature Robert W. Hahn
21 CODE	26 PARAMETER VALUE	35 CODE	40 PARAMETER VALUE	49 CODE	54 PARAMETER VALUE	62	
Flow (gpd)		Water Temperature (°F)		pH			
0 0 5 6		0 0 0 1 1		0 0 4 0 0			
O. (mg/l)		Turbidity (JTU)					
0 3 0 0		0 0 0 7 0					

KAS DEPARTMENT OF WATER RESOURCES

HM 11348 District 7 Lab Used CDH Lab EW71414
Sample: Heavy Metals Material Sampled: Raw, Partially Treated
Equipment BLANK Composite Hr. Method of Preservation Nitric / ice
Observations APR 27 '87 Type Facility Surf Imp
Auxiliary Tags
Date Completed
Analyst's Signature

21 CODE	26 PARAMETER VALUE	35 CODE	40 PARAMETER VALUE	49 CODE	54 PARAMETER VALUE	62
Arsenic ✓		Barium ✓				
	< 45		< 20			
Cadmium ✓		Chromium ✓		Copper ✓		
	< 10		< 20		< 20	
Lead ✓		Manganese ✓		Mercury ✓		
	< 30		< 20		< 10	
Nickel ✓		Selenium		Silver		
	< 20					
Zinc ✓		Iron (Total) ✓				
	< 20		51			

Attachment U

25 1997

o. HM

District

County Harris

Basin

Discharger Name 11347

Time Collected 4-24-87/10:00 AM

Plant Name Water

Point of Collection monitor well

Method of Flow Measurement

MW-1

PERMIT NUMBER	PAGE NO.	ORD. TYPE	DATE			MAY STAMP					
			Mo.	Day	Yr.						
31633	9	10	12	13	14	15	16	17	18	19	20
					0	4	2	4	8	7	

Chlorine Contact Time

Date Shipped

4-27-87

Collector's Signature

Robert Hahn

21 CODE	26 PARAMETER VALUE	35 CODE	40 PARAMETER VALUE	49 CODE	54 PARAMETER VALUE 62
Flow (gpd)		Water Temperature (°F)		pH	
00056		00011		00400	
D.O. (mg/l)		Turbidity (JTU)			
00300		00070			

TEXAS DEPARTMENT OF WATER RESOURCES

Jo. HM

11347

District

7

Type Sample: Heavy Metals

31633

Lab

MW-1

Component

Hr.

Lab Used

TDH

Lab No.

11347

Material Sampled: Raw, Partic.

Method of Preservation

None

Type Facility

Surv. imp.

Auxiliary Tags

Date Completed

APR 27 '87

Analyst's Signature

[Signature]

Observations

APR 27 '87


9+

21 CODE	26 PARAMETER VALUE	35 CODE	40 PARAMETER VALUE	49 CODE	54 PARAMETER VALUE 62
Arsenic ✓		Barium ✓			
	1.2		5.2		
Cadmium ✓		Chromium ✓		Copper ✓	
	< 1.0		7.6		6.4
Lead ✓		Manganese ✓		Mercury ✓	
	< 3.0		3.00		0.4
Nickel		Chromium		Mercury	
	1.0				
Zinc ✓		Iron (Total)		Values are µg/l	
	1.50		17.4000		

Attached to

Attachments X_1, X_2
Attachments Y_1, Y_2

Tables and Diagrams
from HLEP Ground Water
Quality Assessment Report
May 1984







Figure 14. Modified Sini Diagrams, Webster Generating Station Monitor Wells and Surface Impoundments.



0 200 400 600
FEET

MW-1 MONITOR WELL

**Figure 13. Location of Monitor Wells and Surface Impoundments,
Webster Generating Station.**



TABLE 8

Water Quality Analysis, Webster Generating Station, Monitor Wells and Surface Impoundments

	<u>MW</u> <u>No. 1</u>	<u>MW</u> <u>No. 2</u>	<u>MW</u> <u>No. 3</u>	<u>MW</u> <u>No. 4</u>	<u>SI-1</u>	<u>SI-2</u>	<u>SI-3</u>	<u>SI-4</u>	<u>SI-5</u>	<u>SI-6</u>
Calcium	560	59	200	130	34	71	11	110	64	150
Magnesium	270	34	77	50	2.1	8.7	3.8	260	1.7	24
Potassium	3.8	2.4	3.2	7.0	5.2	5.7	2.5	78	4.1	5.5
Sodium	1,700	300	440	530	4,300	1,300	60	2,100	1,100	620
Acidity	0	0	0	0	0	1,600	0	0	0	0
Alkalinity	190	374	420	410	8,300	0	87	120	120	800
Sulfate	450	160	60	220	220	3,600	5	640	1,400	1,600
Chloride	3,900	220	740	560	120	150	12	3,700	90	85
Fluoride	0.9	1.3	1.0	1.2	4.6	1.4	0.49	0.55	0.46	3.3
Nitrate	<0.05	<0.05	<0.05	<0.05	5.9	<0.05	6.1	<0.05	<0.05	<0.05
Silica	12	2	2	8	27	19	7	<1	10	3
Copper	0.28	<0.01	0.01	<0.01	0.63	0.07	0.48	0.21	0.07	<0.01
Iron	0.25	<0.05	0.33	0.37	0.59	5.9	15	0.35	0.71	0.78
Zinc	1.6	0.05	2.7	3.0	0.99	2.1	0.29	1.0	2.6	1.7
Conductivity	12,000	1,600	3,200	3,000	26,000	11,000	290	14,000	3,100	4,600
Dissolved Solids	8,700	990	1,600	1,500	9,900	4,800	360	7,300	2,300	3,200
pH	7.24	7.93	7.2	7.27	12.89	1.93	7.95	8.11	8.31	10.24

All concentrations are in mg/L except Conductivity (umhos) and pH (standard units).

2011-01-12

HC-GRAM


HydroChemical Graphic Representation Analysis Methods

Version: HC-GRAM 1.09

04-Sep-1987

09:41:33.17

Project: hlp webster April 24, 1987



Chemical Constituents in ppm

Sample	Ca	Mg	Na	K	HCO3	CO3
01-1 (TWC)	217.00	446.00	2159.00	3.00	34.00	0.00
01-2 (HLP)	218.00	446.00	2159.00	3.00	34.00	0.00
01-3 (HLP)	76.00	42.00	306.00	3.00	450.00	0.00

Chemical Constituents in ppm

Sample	SO4	Cl	NO3	PO4	Si	Fe
01-1 (TWC)	543.00	1423.00	0.00	N.D.	10.00	0.00
01-2 (HLP)	150.00	1423.00	0.00	N.D.	10.00	0.00
01-3 (HLP)	150.00	1423.00	0.00	N.D.	10.00	0.00


N.D = not analyzed for

Attachment Z
Trilinear and Stiff Diagram

Title: HLP
4-SEP-1987
09:50:30.01

Percent Reacting Values

Sample	%Ca	%Mg	% (Na+K)	%Cl	%PO4	%HCO3	TDS, mg/l	%
MW-1 (TWC)	18.25	14.25	65.73	21.73	3.38	3883.45		0
MW-1 (HLP)	20.25	14.25	67.48	22.00	3.07	3883.45	11842.33	0
MW-2 (TWC)	18.25	14.25	65.73	21.73	3.38	3883.45	18005.32	0
MW-2 (HLP)	18.40	14.75	64.84	22.90	17.55	55.54	1874.77	0



Title: 4-SEP-1987
09:50:30.01

Chemical Constituents in ppm

Sample	Ca	Mg	Na	K	HCO3	CO3
MW-1 (TWC)	559.00	246.00	2139.00	3.00	254.00	0.00
MW-1 (HLP)	716.00	263.00	2725.00	6.00	3256.00	0.00
MW-2 (TWC)	69.00	43.00	419.00	3.00	600.00	0.00
MW-2 (HLP)	76.20	42.10	306.00	3.40	450.00	0.00

Chemical Constituents in ppm

Sample	SO4	Cl	NO3	PO4	Si	Fe
MW-1 (TWC)	508.00	4463.00	0.03	0.ND	19.00	74.60
MW-1 (HLP)	350.00	4173.00	0.00	0.ND	0.00	2.23
MW-2 (TWC)	248.00	352.00	0.66	0.ND	21.00	3.71
MW-2 (HLP)	175.00	345.00	0.00	0.ND	0.00	2.07

09:57:08.41

Chemical Constituents in Equivalents per Million

Sample	Ca	Mg	Na	K	HCO3	CO3
MW-1 (TWC)	27.89	20.54	23.05	0.02	4.16	0.00
MW-1 (HLP)	33.72	21.53	118.54	0.15	53.37	0.00
MW-2 (TWC)	3.44	2.18	13.83	0.01	9.83	0.00
MW-2 (HLP)	3.80	2.18	13.81	0.01	7.38	0.00

Chemical Constituents in Equivalents per Million

Sample	SO4	Cl	NO3	PO4	Si	Fe
MW-1 (TWC)	11.17	105.00	0.00	0.ND	0.00	2.40
MW-1 (HLP)	7.17	71.00	0.00	0.ND	0.00	0.26
MW-2 (TWC)	4.15	2.00	0.01	0.ND	1.00	1.10
MW-2 (HLP)	3.84	2.00	0.00	0.ND	0.00	0.09


Table 2

**Clay Liner Samples
Demineralizer Regenerant Impoundment
Webster Generating Station**

Sample Point				EP Toxicity (mg/l)								Total Metals (mg/kg)							
	pH 0-2 inch	pH 6 inch	pH 18 inch	As	Ba	Cd	Cr	Pb	Hg	Aq	Se	As	Ba	Cd	Cr	Pb	Hg	Aq	Se
1	8.0	8.5		<0.002	<0.25	<0.05	0.1	<0.05	<0.002	<0.05	<0.002	2.93	105	<10	16	<10	<0.10	<10	0.042
2	8.6	8.7	8.7	<0.002	<0.25	<0.05	0.1	0.7	<0.002	<0.05	<0.002	4.15	180	<10	15	16	<0.10	<10	0.070
3	8.5	8.7																	
4	7.9	8.3		<0.002	<0.25	<0.05	0.2	<0.05	<0.002	<0.05	<0.002	3.70	228	<10	16	<10	<0.10	<10	0.069
5	8.2	7.7	8.3	0.007	<0.25	<0.05	<0.05	<0.05	<0.002	0.07	<0.002	3.84	203	<10	17	11	<0.10	<10	0.057
6	8.6	8.6																	
7	8.1	8.2																	
8	8.6	8.3	8.9	0.006	<0.25	<0.05	<0.05	<0.05	<0.002	0.2	<0.002	2.75	190	<10	13	<10	<0.10	<10	0.066
9	8.5	8.5																	
10	8.2	8.5																	
11	8.4	8.3	8.7	0.006	<0.25	<0.05	0.7	<0.05	<0.002	<0.05	<0.002	3.27	173	<10	12	13	<0.10	<10	0.059
12	8.1	8.2		0.002	<0.25	<0.05	<0.05	<0.05	<0.002	<0.05	<0.002	3.37	84	<10	12	<10	<0.10	<10	0.091
Sample Mean												3.43	166	<10	14	11	<0.10	<10	0.065
Background Samples ✓																			
1												10.9	356	< 1	26	26	<0.2	< 1	0.25
2												10.6	253	< 1	21	16	<0.2	< 1	<0.2
3												9.89	80.4	< 1	20	20	<0.2	< 1	0.31
Background Mean												10.5	230	< 1	22	21	<0.2	< 1	0.253

RESOURCE ENGINEERING

Attachment AA



— LEGEND —

- MONITOR WELL
- A DEMINERALIZER REGENERANT SURFACE IMPOUNDMENT
- B INORGANIC METAL CLEANING SURFACE IMPOUNDMENT
- SOIL SAMPLING LOCATIONS (Background)


0 800
SCALE IN FEET



RESOURCE ENGINEERING INC.

ENVIRONMENTAL CONSULTANTS
HOUSTON, TEXAS

FIGURE 2
FACILITY MAP
WEBSTER GENERATING STATION



 BORING LOCATIONS



RESOURCE ENGINEERING INC.

ENVIRONMENTAL CONSULTANTS
HOUSTON, TEXAS

**FIGURE 3
DEMINERALIZER REGENERANT/
BOILER BLOWDOWN IMPOUNDMENT
CLAY LINER BORING LOCATIONS
WEBSTER GENERATING STATION**

DRAWN BY: N.L.J.

DATE: 11-4-85

PROJECT NO: 344-01

Attachment AA
Location Map for Figure 3

No. **GW 03800**

APR 30 1987

TEXAS DEPARTMENT OF WATER RESOURCES
P.O. Box 13087, Capitol Station
Austin, Texas 78711Org. No. 444
Sample No. MW-2Owner H L & P Address Houston Zip _____County Harris Well No. MW-2Location Webster Power Sta. 31633

Date Drilled _____ Depth _____ Aquifer _____

Water Level _____ Sample After Pumping _____ Mins. (Hrs.) Yield _____ GPM Temperature _____ °F

Point of Collection well / bailer Appearance _____ Clear (Turbid) Red/silty ColorUse Monitor well Remarks _____ (Over)Date Collected 4-24-87 Time 11:50 A By Robert HahnSend copy of completed analysis to Robert W. Hahn TDWR Office No. 1116A

TDWR-0778 (Rev. 10-24-84)

No. **GW 03800**

TEXAS DEPARTMENT OF WATER RESOURCES

Point of Collection MW-2

P.O. Box 13087, Capitol Station

Work No. 4003Org. No. 444Sample No. MW-2Lab Used TDH APR 27 '87

Lab _____

Method of Preservation ice / noneType of Facility Power PlantDate Completed JUN 12 '87Analyst's Signature [Signature]

	Mg/l	EPM		Mg/l	EPM	Other Ions	Mg/l
<input checked="" type="checkbox"/> Silica	<u>21</u>		<input checked="" type="checkbox"/> Carbonate	<u>0</u>	<u>0.00</u>	<input checked="" type="checkbox"/> Bromide	<u>0.3</u>
<input checked="" type="checkbox"/> Calcium	<u>69</u>	<u>3.42</u>	<input checked="" type="checkbox"/> Bicarbonate	<u>600</u>	<u>9.84</u>	<input checked="" type="checkbox"/> Iodide	<u>5.9</u>
<input checked="" type="checkbox"/> Magnesium	<u>42</u>	<u>3.44</u>	<input checked="" type="checkbox"/> Sulfate	<u>248</u>	<u>5.17</u>	<input type="checkbox"/>	
<input checked="" type="checkbox"/> Sodium	<u>419</u>	<u>18.22</u>	<input checked="" type="checkbox"/> Chloride	<u>352</u>	<u>9.92</u>	<input type="checkbox"/>	
	Total	<u>25.14</u>	<input checked="" type="checkbox"/> Fluoride	<u>1.4</u>	<u>0.07</u>	<input type="checkbox"/>	
<input checked="" type="checkbox"/> Potassium	<u>2</u>	<u>0.05</u>	<input checked="" type="checkbox"/> Nitrate-N	<u>0.66</u>	<u>0.05</u>	<input type="checkbox"/>	
<input checked="" type="checkbox"/> Boron	<u>0.35</u>	<u>25.19</u>	pH <u>8.0</u>	Total	<u>25.05</u>	<input type="checkbox"/>	
<input checked="" type="checkbox"/> Iron	<u>see Heavy metals</u>		Dissolved Solids (sum)	<u>1453</u>			

Remarks _____

Phenolphthalein Alkalinity as CaCO₃ _____

Total Alkalinity as CaCO₃ (9.84) 492

Total Hardness as CaCO₃ _____

Specific Conductance (Micromhos/CM) 1780

Diluted Conductance (Micromhos/CM) _____

☐ Items will be analyzed if checked, total Iron requires separate sample.

TDWR-0778 Rev. 10-24-84

Attachment U